


CITY OF WHITTIER, ALASKA


WHITTIER WELL FIELD UPGRADE

DECEMBER 2021

FINAL DESIGN




PREPARED FOR:



CITY OF WHITTIER

PREPARED BY:



3940 ARCTIC BLVD. SUITE 300
ANCHORAGE, ALASKA 99503
PHONE: (907) 562-3252
#AECL882-AK

**BETTISWORTH
NORTH**

LEGEND

COMMON ABBREVIATIONS

SYMBOL		SYMBOL		
EXISTING	PROPOSED	EXISTING	PROPOSED	
				CONTOUR LINE
				SPOT ELEVATION
				APPROX. FILL SLOPE LIMITS
				APPROX. CUT SLOPE LIMITS
				ELECTRIC LINE
				ELECTRIC LINE (OVERHEAD)
				ELECTRIC & TELEPHONE (OVERHEAD)
				NATURAL GAS LINE
				SANITARY SEWER LINE
				TELEPHONE LINE
				TELEPHONE LINE (OVERHEAD)
				WATER LINE (ABANDONED)
				WATER LINE

SYMBOL		
EXISTING	PROPOSED	
		GRADE OF PAVEMENT AT CENTER LINE
		EXISTING GROUND OVER PIPE
		APPROXIMATE EXCAVATION LIMITS
		PIPE (PROFILE)
		PIPE (SECTION)
		WATER LEVEL
		SANITARY SEWER MANHOLE & PIPE

SYMBOL	DESCRIPTION
	CENTERLINE
	PROPERTY LINE
	EASEMENT LINE
	UNPAVED (GRAVEL) EDGE OF ROAD/DRIVEWAY
	EDGE OF PAVED ROAD/DRIVEWAY
	STREAM/EDGE OF WATERWAY
	DRAINAGE SWALE
	DRAINAGE ARROW
	BLUFF AREA/ EARTHWORK SLOPE
	CULVERT
	BOTTOM OF DITCH
	CHAINLINK FENCE
	WOOD FENCE
	VEGETATION, BRUSH & TREELINE
	STREET SIGN
	TEST BORING OR TEST HOLE
	HOUSE OR STRUCTURE

ABBR.	DESCRIPTION
AC	ASPHALT CONCRETE
APPROX, APPX	APPROXIMATE
BM	BENCH MARK
BOP	BEGINNING OF PROJECT
C&G	CURB AND GUTTER
CB	CATCH BASIN
CBMH	CATCH BASIN MANHOLE
C/L, CL	CENTERLINE
CMP	CORRUGATED METAL PIPE
CO	CLEANOUT
CONST	CONSTRUCTION
CPEP	CORRUGATED POLYETHYLENE PIPE
DIA	DIAMETER
DIP	DUCTILE IRON PIPE
D.W.	DETECTABLE WARNING
E	EAST
ELEC	ELECTRIC / ELECTRICAL
ELEV, EL	ELEVATION
EOP	END OF PROJECT / EDGE OF PAVEMENT
EX, EXIST	EXISTING
F&I	FURNISH AND INSTALL
FG	FINISHED GRADE
GB	GRADE BREAK
JB	JUNCTION BOX
LC	LOAD CENTER
IAW	IN ACCORDANCE WITH
IE	INVERT ELEVATION
INTX	INTERSECTION
INV	INVERT
LF	LINEAR FOOT
LT, L	LEFT
LUM	LUMINAIRE
MAX	MAXIMUM
MH	MANHOLE
MIN.	MINIMUM
MON	MONUMENT
MSL	MEAN SEA LEVEL
N	NORTH
N/A	NOT APPLICABLE
N.I.C.	NOT IN CONTRACT
NTS	NOT TO SCALE
NWT	NO WATER TABLE
OC	ON CENTER
OCEW	ON CENTER EACH WAY
OD	OUTSIDE DIAMETER
OH	OVERHEAD
PC	POINT OF CURVATURE
PCC	PORTLAND CONCRETE CEMENT
PCC	POINT OF CONTINUOUS CURVATURE
PI	POINT OF INTERSECTION
PL, P/L	PROPERTY LINE
PCMP	PRECOATED CORRUGATED METAL PIPE
POPEP	PERFORATED CORRUGATED POLYETHYLENE PIPE
PT	POINT OF TANGENCY
PUE	PUBLIC USE EASEMENT
PVC	POINT OF VERTICAL CURVATURE
PVI	POINT OF VERTICAL INTERSECTION
PVT	POINT OF VERTICAL TANGENT
ROW, R/W	RIGHT OF WAY
RT, R	RIGHT
R.W.	RETAINING WALL
S	SOUTH
SEC COR	SECTION CORNER
SCH/SCHD	SCHEDULE
SI	STREET INTERSECTION
SS	SANITARY SEWER, STAINLESS STEEL
ST	STREET
STA	STATION / STATIONING
STD	STANDARD
STRUCT	STRUCTURE
S/W	SIDEWALK
TBC	TOP BACK OF CURB
TBM	TEMPORARY BENCH MARK
TCP	TEMPORARY CONSTRUCTION PERMIT
TELE	TELEPHONE
TH	TEST HOLE
(TYP.)	TYPICAL
UG	UNDERGROUND
UTIL	UTILITY
V	VOLT
VB	VALVE BOX
VC	VERTICAL CURVE
W	WEST



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

NOTES, ABBREVIATIONS, AND LEGEND

REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	KEG
DESIGNED	WVS
REVIEWED	PB

SHEET NO.


G003

GENERAL NOTES

1. CAUTION! UNDERGROUND UTILITIES EXIST WITHIN THE PROJECT AREA. CONTRACTOR SHALL CALL FOR UTILITY LOCATES PRIOR TO BEGINNING CONSTRUCTION. CALL 907-240-2019 TO CONTACT CITY OF WHITTIER PUBLIC WORKS DEPARTMENT FOR CITY UTILITIES LOCATES.
2. ALL CONSTRUCTION SHALL BE INSTALLED AS SPECIFIED IN THE 2015 EDITION OF THE MUNICIPALITY OF ANCHORAGE (MOA) STANDARD SPECIFICATIONS (HEREINAFTER REFERRED TO AS MASS); THE MOST RECENT VERSION OF THE AWWU DESIGN AND CONSTRUCTION PRACTICES MANUAL (DCPM); AND THE SPECIAL PROVISIONS.
3. THE LOCATIONS OF THE EXISTING FEATURES AND UTILITIES SHOWN IN THESE DRAWINGS ARE APPROXIMATE. CONTRACTOR SHALL FIELD VERIFY THE LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION.
4. THE CONTRACTOR SHALL VERIFY THE HORIZONTAL AND VERTICAL LOCATION OF ALL UTILITIES ENCOUNTERED AND RECORD THEIR LOCATION ON THE CONTRACT RECORD DRAWINGS. DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE ENGINEER. CONTRACTOR SHALL ADJUST ALIGNMENT OR GRADE OF PROPOSED PIPING AS NECESSARY TO AVOID CONFLICTS WITH EXISTING UTILITIES.
5. ALL WORK IN CLOSE PROXIMITY TO EXISTING OVERHEAD AND UNDERGROUND TELEPHONE AND ELECTRIC UTILITIES SHALL COMPLY WITH APPLICABLE FEDERAL, STATE AND LOCAL STATUTES, CODES AND GUIDELINES AND THE CLEARANCE REQUIREMENTS OF THE SERVING UTILITY.
6. ALL WORK SHALL BE PERFORMED WITHIN PUBLIC RIGHT-OF-WAY, PUBLIC USE EASEMENT, UTILITY EASEMENT, OR TEMPORARY CONSTRUCTION EASEMENT AREAS.
7. ALL WORK AND EQUIPMENT REQUIRED FOR REMOVING ANY LITTER OR DEBRIS WITHIN THE PROJECT LIMITS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT AND NO SEPARATE PAYMENT WILL BE MADE.
8. THE LOCATIONS OF VEGETATION AND BRUSH SHOWN IN THESE DRAWINGS ARE APPROXIMATE. THE CONTRACTOR SHALL PROVIDE ALL CLEARING AND GRUBBING NECESSARY TO CONSTRUCT THE IMPROVEMENTS AS SHOWN ON THE DRAWINGS.
9. ALL ORGANIC MATERIAL SHALL BE REMOVED FROM THE SUBGRADE TO A DEPTH TO BE DETERMINED BY THE ENGINEER. NO ORGANIC MATERIAL OR OTHER DELETERIOUS MATERIAL SHALL BE UTILIZED FOR BACKFILL.
10. NO DUMPSITE IS PROVIDED. CONTRACTOR SHALL BE RESPONSIBLE FOR DISPOSAL OF ALL MATERIALS REMOVED/DEMOLISHED.
11. CONTRACTOR SHALL PROVIDE RECORD DRAWINGS IN ACCORDANCE WITH THE REQUIREMENTS OF MASS AND THE MOST RECENT VERSION OF AWWU DESIGN AND CONSTRUCTION PRACTICES MANUAL. CONTRACTOR SHALL SUBMIT ALL FIELD SURVEY BOOKS (SURVEY LINE AND GRADE BOOKS) WITH THE RECORD DRAWINGS PRIOR TO CONTRACT FINAL PAYMENT.
12. CONTRACTOR SHALL RESTORE ALL PROPERTY (INCLUDING, BUT NOT LIMITED TO, DRAINAGE SWALES, STRUCTURES, BASKETBALL COURT, CITY PARK) DISTURBED BY CONSTRUCTION TO PRE-CONSTRUCTION CONDITIONS, UNLESS OTHERWISE DIRECTED BY ENGINEER. RESTORING DISTURBED PROPERTY SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT AND NO SEPARATE PAYMENT SHALL BE MADE.
13. MAINTAIN A MINIMUM OF 10 FEET HORIZONTAL AND 18 INCHES VERTICAL SEPARATION BETWEEN WATER AND SANITARY OR STORM SEWER MAINS AND SERVICES. WHERE WATER AND SEWER MAINS CROSS, SEWER MAIN JOINTS SHALL BE AT LEAST 9 FEET FROM WATER MAIN JOINTS.
14. SHRINK WRAP ALL WATER PIPE JOINTS WITHIN 10 FEET HORIZONTAL OF SANITARY AND STORM SEWER CROSSINGS WITH CANUSAWRAP. INSTALL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
15. IF ANY SANITARY OR STORM SEWER PIPE JOINTS ARE EXPOSED DURING EXCAVATION OF WATER MAIN, SHRINK WRAP SANITARY AND STORM SEWER PIPE JOINTS WITH CANUSAWRAP. INSTALL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
16. MAINTAIN A MINIMUM OF 36 INCHES OF VERTICAL SEPARATION BETWEEN ANY STORM SEWER (STORM DRAIN OR FOOTING DRAIN) AND WATERLINE (MAINS OR SERVICES) OR SANITARY SEWER (MAINS OR SERVICES). IF 36 INCHES CANNOT BE MAINTAINED, PROVIDE A MINIMUM R-20 INSULATION. IF 18 INCHES CANNOT BE MAINTAINED, RELOCATE WATER MAIN.
17. CONSTRUCT WATER MAIN SO THAT JOINTS ARE EQUIDISTANT FROM EXISTING SANITARY SEWER AND EXISTING STORM SEWER PIPES.
18. IN CASE OF CONFLICT BETWEEN STATIONING OR DIMENSIONED LOCATION OF PIPE OR FITTINGS, USE DIMENSIONED LOCATIONS RELATIVE TO THE CENTERLINE AND PROPERTY LINE. THE DIMENSIONED LOCATIONS SHALL GOVERN.
19. ALL WATER PIPE INSULATION SHALL BE RIGID BOARD, HIGH DENSITY EXTRUDED POLYSTYRENE MIN. 60 P.S.I., FOR UNDERGROUND INSTALLATIONS EQUIVALENT TO R-20.
20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR EROSION AND SEDIMENT CONTROLS AS NECESSARY TO COMPLY WITH FEDERAL, STATE, AND MUNICIPAL LAWS THAT PROHIBIT UNPERMITTED DISCHARGE OF POLLUTANTS, INCLUDING SEDIMENTS, THAT ARE A RESULT OF EROSION AND OTHER CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL CONDUCT ALL WORK SO SEDIMENT IS NOT TRANSPORTED ONTO THE ROADWAY OR ADJACENT PROPERTY. AT A MINIMUM, THE CONTRACTOR SHALL SWEEP UP ANY SEDIMENT TRACKED ONTO PAVED SURFACES IN PUBLIC RIGHT-OF-WAY WITHIN 24 HOURS OF THE TRACKING TO MINIMIZE THE WASH-OFF OF SEDIMENT INTO THE STORM DRAINS OR WATERWAYS.
21. WATER RESULTING FROM THE CONTRACTOR'S DEWATERING EFFORT MAY NOT BY PUMPED OR OTHERWISE DIVERTED INTO EXISTING STORM DRAINS UNLESS REQUIRED PERMITS, INCLUDING, BUT NOT LIMITED TO, THE ALASKA DEPARTMENT OF ENVIRONMENT CONSERVATION ARE OBTAINED BY THE CONTRACTOR. UNDER NO CIRCUMSTANCES WILL THE CONTRACTOR BE ALLOWED TO DIVERT WATER FROM EXCAVATION ONTO ROADWAYS. THE CONTRACTOR SHALL PROVIDE DISPOSAL SITE FOR EXCESS WATER AND SHALL BE RESPONSIBLE FOR SECURING ALL NECESSARY PERMITS AND APPROVALS. THE CONTRACTOR SHALL PROVIDE COPIES OF PERMITS AND APPROVALS TO THE ENGINEER PRIOR TO BEGINNING DEWATERING.
22. "BOP" IS DEFINED AS THE OUTSIDE BOTTOM OF PIPE. INVERT "INV" IS DEFINED AS THE INSIDE BOTTOM OF PIPE.
23. ALL WATER STATIONING IS PIPE STATIONING.
24. ALL NUTS, BOLTS AND WASHERS USED TO CONSTRUCT VALVES SHALL BE STAINLESS STEEL (TYPE 316).
25. DAMAGE TO SEWER SERVICE CONNECTIONS MADE DURING WATERLINE CONSTRUCTION SHALL BE REPAIRED USING APPROVED MATERIALS WITH APPROVED COUPLINGS, AT CONTRACTOR'S EXPENSE.
26. CONTRACTOR SHALL INSTALL RESTRAINED FITTINGS ON ALL MECHANICAL JOINTS.
27. ANY EXISTING SURVEY MONUMENTATION DISTURBED BY CONTRACTOR OPERATIONS SHALL BE REPLACED AT CONTRACTOR'S EXPENSE BY SURVEYOR LICENSED TO PRACTICE IN THE STATE OF ALASKA.

WATER NOTES

1. CITY OF WHITTIER AND EXISTING CUSTOMERS SHALL BE NOTIFIED SEVENTY-TWO (72) HOURS IN ADVANCE OF WATER SERVICE INTERRUPTION. THE CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE TEMPORARY WATER SERVICE TO THE EXISTING CUSTOMERS IF THE OUTAGE EXCEEDS 6-HOURS OR IF DEEMED NECESSARY BY THE ENGINEER.
2. ALL WATER MAINS SHALL BE DUCTILE IRON PIPE, CLASS 52 AS SHOWN IN THE PLANS, CONFORMING TO THE REQUIREMENTS OF MASS SECTION 60.02 FURNISH AND INSTALL PIPE.
3. ALL FITTINGS AND VALVES SHALL HAVE MECHANICAL JOINT CONNECTIONS UNLESS OTHERWISE SHOWN ON THE PLANS. INSTALL THRUST BLOCKS AT ALL FITTINGS.
4. ALL MECHANICAL JOINTS SHALL BE RESTRAINED BY EBAA IRON MEGALUG SERIES 1100 OR APPROVED EQUAL.
5. ALL WATER MAIN JOINTS SHALL BE RESTRAINED. U.S. PIPE FIELD LOK GASKET SYSTEM OR EQUAL.
6. NO PIPE LENGTH LESS THAN 8 FEET SHALL BE INCORPORATED IN THE WATER SYSTEM EXCEPT FOR THOSE NECESSARY FOR VALVE LOCATIONS.
7. ALL WATER MAIN TRENCH BACKFILL MATERIALS AND BEDDING SHALL BE COMPACTED TO A MINIMUM OF 95% OF MAXIMUM DENSITY.
8. ALL WATER MAINS AND SERVICES SHALL HAVE A MINIMUM OF 7 FEET OF COVER AT ALL POINTS, UNLESS OTHERWISE NOTED.
9. CONTRACTOR SHALL VERIFY THE LOCATION OF EXISTING WATER MAINS. INFORMATION HAS BEEN COMPILED FROM AS-BUILTS AND MAY VARY.
10. ALL PIPE BEDDING FOR DUCTILE IRON PIPE SHALL BE CLASS 'E' PER THE SPECIFICATIONS.
11. ALL DUCTILE IRON PIPE SHALL BE ENCASED IN 8-MIL V-BIO ENHANCED POLYETHYLENE ENCASEMENT PER MASS SECTION 60.02 FURNISH AND INSTALL PIPE.
12. MAXIMUM DEFLECTION OF PIPE PER JOINT SHALL NOT EXCEED 80% OF THE MANUFACTURERS RECOMMENDED DEFLECTION (4 DEGREES) FOR DIP.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

GENERAL AND WATER NOTES

REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	KEG
DESIGNED	WVS
REVIEWED	PB

SHEET NO.

G004

A

B


C

D

ALASKA RAILROAD
TERMINAL RESERVE

LEGEND

- EXISTING BRASS CAP
- EXISTING ALUMINUM CAP
- ⊙ BENCHMARK
- EXISTING REBAR OR IRON PIPE
- (601) CONTROL POINT NUMBER




FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1" 1"

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY



HORIZONTAL CONTROL STATEMENT

THIS PROJECT IS ON AN ASSUMED LOCAL COORDINATE SYSTEM, BASED ON PREVIOUS WHITTIER WATER IMPROVEMENTS PHASE 1 PROJECT DATED APRIL 1993. IT IS A GROUND BASED COORDINATE SYSTEM IN U.S. SURVEY FEET.


VERTICAL CONTROL STATEMENT

THE BASIS OF VERTICAL CONTROL IS U.S.G.S. B.M. Q-74 LOCATED AT FLOOR LEVEL ON THE EAST SIDE OF THE NORTHWEST BAY OF DOORS IN THE COMPOSITE (P-12) BUILDING. ELEVATION = 28.15' PER WHITTIER WATER IMPROVEMENTS PHASE 1 PROJECT DATED APRIL 1993.

NOTES

1. ALL COORDINATES AND DIMENSIONS SHOWN ARE IN U.S. SURVEY FEET.
2. FIELD SURVEY WAS CONDUCTED APRIL 21 THROUGH MAY 18TH, 2021.
3. POINTS 701-710 WERE ESTABLISHED BY RTK GPS USING POINT 601 AND 702 AS THE BASIS OF COORDINATES.
4. POINTS 601 AND 702 WERE LEVELED TO FROM POINT BM Q-74 USING LEICA DNA10 LEVEL AND PROCESSED USING LEICA INFINITY VER. 3.0.
5. ALL POINTS SHOWN HEREON WERE ESTABLISHED BY RTK OR STATIC GPS SURVEY METHODS, USING LEICA 1200 & GS14 GPS UNITS, AND PROCESSED USING LEICA GEO OFFICE VER. 8.4 AND LEICA INFINITY VER. 3.0.
6. WHETHER LISTED OR NOT, ALL MONUMENTS OR PROPERTY MARKERS, CORNERS, OR ACCESSORIES, WHICH WILL BE DISTURBED OR BURIED, SHALL BE REFERENCED OR RE-ESTABLISHED IN THEIR ORIGINAL POSITION (A.S. 19.10.260) AND RECORDED (A.S. 34.65.040).
7. ALL MONUMENTS ARE SUBJECT TO SEASONAL DISTURBANCE. ELEVATIONS MUST BE VERIFIED PRIOR TO CONSTRUCTION.

DETAIL SHOWING
ADDITIONAL MONUMENTS



VERTICAL SURVEY CONTROL				
Point #	Northing	Easting	Elevation	Description
601	6421	5447	26.79	FOUND 2" ALUMINUM CAP IN MONUMENT CASE, 0.7' BELOW RIM, NW CORNER OF CITY OF WHITTIER SUBD, PLUMB AND GOOD CONDITION.
702	6361	5491	29.39	FOUND 2" BRASS CAP, FLUSH WITH CONCRETE, NW CORNER OF LOT 1 BLOCK 2, CITY OF WHITTIER SUBD, PLUMB AND GOOD CONDITION.
BM Q-74			28.15	B.M. Q-74 LOCATED AT FLOOR LEVEL ON THE EAST SIDE OF THE NORTHWEST BAY OF DOORS IN THE COMPOSITE (P-12) BUILDING.



HORIZONTAL SURVEY CONTROL				
Point #	Northing	Easting	Description	
601	6420.74	5446.75	FOUND 2" ALUMINUM CAP IN MONUMENT CASE, 0.7' BELOW RIM, NW CORNER OF CITY OF WHITTIER SUBD, PLUMB AND GOOD CONDITION	
701	5000.00	5000.00	FOUND 3 1/4" ALUMINUM CAP ON 2 1/2" ALUMINUM POST, 0.1' ABOVE GROUND, SW CORNER OF CITY OF WHITTIER SUBD, PLUMB AND GOOD CONDITION	
701	5000.00	5000.00	FOUND 3 1/4" ALUMINUM CAP ON 2 1/2" ALUMINUM POST, 0.1' ABOVE GROUND, SW CORNER OF CITY OF WHITTIER SUBD, PLUMB AND GOOD CONDITION	
702	6360.51	5490.69	FOUND 2" BRASS CAP, FLUSH WITH CONCRETE, NW CORNER OF LOT 1 BLOCK 2, CITY OF WHITTIER SUBD, PLUMB AND GOOD CONDITION	
703	6199.28	5440.02	FOUND 2" ALUMINUM CAP, 0.2' BELOW GRADE, SW CORNER OF LOT 1 BLOCK 2, CITY OF WHITTIER SUBD, PLUMB AND GOOD CONDITION	
704	6345.85	6216.18	FOUND 3 1/4" ALUMINUM CAP ON 2 1/2" ALUMINUM POST, 0.5' BELOW GRADE, PLUMB AND GOOD CONDITION	
705	5801.20	5977.11	FOUND 2" ALUMINUM CAP, FLUSH WITH GRADE, NE CORNER OF LOT 4 BLOCK 3, CITY OF WHITTIER SUBD, PLUMB AND GOOD CONDITION	
706	5971.83	5368.46	FOUND 5/8" REBAR	
707	4988.19	5058.90	FOUND 5/8" REBAR	
710	5441.15	5138.57	FOUND 5/8" REBAR	

WHITTIER WELL FIELD UPGRADE
WHITTIER ALASKA
PROJECT NO. 20403.14

SURVEY CONTROL


REVISION SCHEDULE

NO.	DESCRIPTION	DATE

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN SB
DESIGNED AJR
REVIEWED AJR
SHEET NO.

V001


PLOT DATE: 1/05/2021



1 **SITE PLAN**

NOTES:

1. REFER TO ARCHITECTURAL, STRUCTURAL, MECHANICAL, AND ELECTRICAL SHEETS FOR MANIFOLD BUILDING.
2. STUBOUTS FOR FUTURE WELL MINIMUM 15' FROM OUTSIDE EDGE OF MANIFOLD BUILDING FOUNDATION.
3. FOR INSTALLATION OF NEW LEVEL MONITOR AT RESERVOIR, REFER TO INSTRUMENTATION AND CONTROLS SHEETS.
4. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL EXISTING DEBRIS FROM STAGING AREA. DEBRIS INCLUDES CONCRETE RUBBLE, SCRAP STEEL, AND OTHER MATERIALS. DEBRIS DOES NOT INCLUDE HAZARDOUS WASTE.
5. LIMITS OF VEGETATION AND TREE CLEARING TO BE FLAGGED BY CONTRACTOR AND APPROVED BY ENGINEER. CHIP ALL BRUSH AND TREES ONSITE AND THEN GRADE SITE SMOOTH.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
SITE PLAN

REVISION SCHEDULE

NO.	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	KEG
DESIGNED	WVS
REVIEWED	PB

SHEET NO.

C101

PLOT DATE: 1/19/2022

A

B

C


D

1

2

3

PLOT DATE: 1/14/2022




1

GRADING PLAN - MANIFOLD BUILDING & WELL A




POINT TABLE			
POINT NO	NORTHING	EASTING	DESCRIPTION
1	6249.11	4824.33	NW BLDG CORNER
2	6242.64	4859.06	NE BLDG CORNER
3	6211.84	4853.32	SE BLDG CORNER
4	6218.31	4818.59	SW BLDG CORNER
5	6261.69	4838.75	DRY WELL CENTER



2

GRADING PLAN - WELL B



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
GRADING PLAN

REVISION SCHEDULE		
NO.	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	KEG
DESIGNED	WVS
REVIEWED	PB


SHEET NO. **C102**

A

B

C


D




WELL A ALIGNMENT PLAN




- NOTES**
1. EXTEND PIPE VERTICALLY FOR CONNECTION TO MANIFOLD BUILDING PIPING, SEE SHEET C205, DETAIL 1. SEE MECHANICAL SHEETS FOR BUILDING PIPING ELEVATION.
 2. CAUTION!!! THE LOCATION OF EXISTING UTILITY CROSSINGS SHOWN IN PROFILE ARE APPROXIMATE.



WELL B ALIGNMENT PLAN



WELL A ALIGNMENT PROFILE



WELL B ALIGNMENT PROFILE



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" = 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
 WELL A AND B PLAN AND PROFILE

REVISION SCHEDULE

NO.	DESCRIPTION	DATE

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN CMK
 DESIGNED WWS
 REVIEWED PB

SHEET NO.

C201


1

2


3

PLOT DATE: 1/16/2022

1
2
3
PLOT DATE: 1/14/2022



MANIFOLD ALIGNMENT PLAN



MANIFOLD ALIGNMENT PROFILE

NOTES

1. EXTEND PIPE VERTICALLY FOR CONNECTION TO MANIFOLD BUILDING PIPING, SEE SHEET C205, DETAIL 1. SEE MECHANICAL SHEETS FOR BUILDING PIPING ELEVATION.
2. CAUTION!!! THE LOCATION OF EXISTING UTILITY CROSSINGS SHOWN IN PROFILE ARE APPROXIMATE.
3. DISCONNECTION OF WELL NO. 2 AND NO. 3 TO OCCUR AFTER COMMISSIONING PROPOSED FACILITIES IAW SHEET C301.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
 PROJECT No. 20403.14

MANIFOLD PLAN AND PROFILE


REVISION SCHEDULE

NO.	DESCRIPTION	DATE

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN CMK
 DESIGNED WVS
 REVIEWED PB


SHEET NO.

C202




TYPICAL PIPE TRENCH

SCALE: NTS



TYPICAL PIPE AND ELECTRICAL TRENCH

SCALE: NTS



TYPICAL ELECTRICAL TRENCH

SCALE: NTS

TRENCH SECTIONS NOTES

1. TRENCH EXCAVATION AND SHORING SHALL COMPLY WITH ALL LOCAL, STATE, AND OSHA REGULATIONS AND REQUIREMENTS. INDICATED TRENCH WALL SLOPES AND DIMENSIONS ARE FOR PAY QUANTITY DETERMINATIONS ONLY.
2. TRENCH BACKFILL SHALL BE NATIVE MATERIAL AS APPROVED BY THE ENGINEER OR IMPORTED TYPE II CLASSIFIED FILL. ROADWAYS AND ROADWAY PRISMS SHALL HAVE 8" MAXIMUM ROCK SIZE.
3. BEDDING MATERIAL (CLASS E) COMPACTED TO 95% OF MODIFIED PROCTOR (ASTM D1557) MAXIMUM DRY DENSITY, PER MANUFACTURER RECOMMENDATIONS OR GOVERNING UTILITY ENTITY REQUIREMENTS.
4. WHERE OTHER UTILITIES ARE ENCOUNTERED, PROVIDE BEDDING MATERIAL AS SHOWN IN DETAIL 1.
5. REFER TO SHEET E006 FOR ELECTRICAL AND INSTRUMENT CONDUIT SIZES. INSTALL PER NEC REQUIREMENTS.

TRENCH FINISH SCHEDULE

1. BUILDING AND WELL PAD: FINISH WITH NATIVE MATERIAL, GRADED SMOOTH.
2. OTHER: FINISH WITH NATIVE MATERIAL, GRADED SMOOTH.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

CIVIL DETAILS - TRENCH

REVISION SCHEDULE

NO.	DESCRIPTION	DATE

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN KEG
DESIGNED WVS
REVIEWED PB

SHEET NO.


C203

A

B


C

D




SLEEVE DETAIL

1 **WATER PIPE FLOOR PENETRATION**
SCALE: NTS



2 **BUILDING FOUNDATION DETAIL**
SCALE: NTS



3 **EXTERIOR CONCRETE ACCESS PAD DETAIL**
SCALE: NTS

- BUILDING FOUNDATION NOTES:
- BACKFILL SHALL BE NATIVE MATERIAL AS APPROVED BY ENGINEER OR IMPORTED TYPE IIA CLASSIFIED FILL, AND COMPACTED IN 12" MAX. LIFTS TO 95% OF MAXIMUM DENSITY.
 - SUBGRADE EXPOSED AT BOTTOM OF EXCAVATION SHALL BE SCARIFIED A MINIMUM 4", MOISTURE CONDITIONED, AND COMPACTED TO 95% OF MAXIMUM DENSITY.
 - EXCAVATE NATIVE MATERIAL TO A MINIMUM 3' BELOW GROUND SURFACE WITHIN FOOTPRINT OF BUILDING AND FOUNDATION. REMOVE AND DISPOSE OF ALL ORGANIC MATERIALS IN ACCORDANCE WITH MASS SECTION 20.27. REMOVE ROCKS LARGER THAN 8". PLACE AND COMPACT REUSED NATIVE MATERIAL TO 95% OF MAX DENSITY.
 - SEE SHEET C102 FOR GRADING.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
CIVIL DETAILS

REVISION SCHEDULE

NO.	DESCRIPTION	DATE


PROJECT NO. 20403.14
DATE DEC 2021
DRAWN KEG
DESIGNED WVS
REVIEWED PB

SHEET NO. **C205**

PLOT DATE: 1/14/2022

1

2



NOTES:

1. REFER TO SHEET E003 FOR ELECTRICAL DEMO OF WELL HOUSE NO. 2 AND 3.
2. COORDINATE ALL NECESSARY WATER SHUT DOWNS WITH CITY OF WHITTIER.
3. DEMO TO OCCUR AFTER COMMISSIONING PROPOSED MANIFOLD BUILDING, WELL A, AND B.
4. COORDINATE WITH ENSTAR TO ABANDON GAS SERVICES AS CLOSE AS ALLOWED TO ENSTAR'S GAS MAIN.
5. CONTRACTOR SHALL PROVIDE CITY OF WHITTIER 72-HOUR NOTICE OF POWER SHUTOFF. CITY OF WHITTIER HAS FIRST RIGHT TO SALVAGE, REFER TO SPECS.





1 **WELL NO. 2 & 3 SITE PLAN - DEMOLITION**



2 **WELL NO. 3**



3 **WELL NO. 2**



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
DEMOLITION PLAN - WELLS 2 AND 3

REVISION SCHEDULE


NO.	DESCRIPTION	DATE

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN KEG
 DESIGNED WVS
 REVIEWED PB

SHEET NO.

C301


REMOVE EXISTING ELECTRICAL AND GAS SERVICES TO BUILDING
 REMOVE ALL PIPING AND ALL APPURTENANCES TO 90-DEGREE
 BEND BELOW SLAB
 DECOMMISSION WELL NO. 1
 DEMOLISH WELL HOUSE NO. 1
 DEMOLISH CONCRETE FOUNDATION




WELL NO. 1 SITE PLAN - DEMOLITION

NOTES:

1. REFER TO SHEET E004 FOR ELECTRICAL DEMO OF WELL HOUSE NO. 1.
2. COORDINATE ALL NECESSARY WATER SHUT DOWNS WITH CITY OF WHITTIER.
3. DEMO TO OCCUR AFTER COMMISSIONING PROPOSED MANIFOLD BUILDING, WELL A, AND B.
4. COORDINATE WITH ENSTAR TO ABANDON GAS SERVICES AS CLOSE AS ALLOWED TO ENSTAR'S GAS MAIN.
5. CONTRACTOR SHALL PROVIDE CITY OF WHITTIER 72-HOUR NOTICE OF POWER SHUTOFF. CITY OF WHITTIER HAS FIRST RIGHT TO SALVAGE, REFER TO SPECS.



WELL NO. 1



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14

DEMOLITION PLAN - WELL 1 (N.I.C.)

REVISION SCHEDULE

NO.	DESCRIPTION	DATE

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN KEG
 DESIGNED WVS
 REVIEWED PB

SHEET NO.

C302

SYMBOL LEGEND

BUILDING SECTION	
WALL SECTION	
EXTERIOR ELEVATION	
PARTIAL/ENLARGED PLAN OR DETAIL	
INTERIOR ELEVATION	
DOOR NUMBER	
RELITE NUMBER	
WINDOW NUMBER	
LOUVER NUMBER	
ROOM NAME	ROOM NAME
ROOM NUMBER	100
ASSEMBLY TYPE	
INTERIOR PARTITION	
CEILING HEIGHT	8'-0" AFF

MATERIAL LEGEND

BATT INSULATION	
GYPSUM BOARD	
SOIL	
CMU	
RIGID INSULATION	
PLYWOOD	
CONCRETE	
BLOCKING	
CONTINUOUS BLOCKING	


STANDARD ARCHITECTURAL ABBREVIATIONS

AB	AIR BARRIER	GA	GAUGE	SECT	SECTION
ADJ	ADJUSTABLE	GALV	GALVANIZED	SF	SQUARE FEET
AFF	ABOVE FINISH FLOOR	GLB	GLULAM BEAM	SIM	SIMILAR
AFG	ABOVE FINISHED GRADE	GYP	GYPSUM BOARD	SPEC	SPECIFICATIONS
ALT	ALTERNATE	HB	HOSE BIB	SSTL	STAINLESS STEEL
ALUM	ALUMINUM	HGT	HEIGHT	STL	STEEL
APPROX	APPROXIMATE	HM	HOLLOW METAL	STRUCT	STRUCTURAL
ARGYP	ABUSE RESISTANT GYPSUM	HORIZ	HORIZONTAL	SUSP	SUSPENDED
AWW	ALL WEATHER WOOD	HR	HOUR	TBD	TO BE DETERMINED
CJ	CONTROL JOINT	HW-X	HARDWARE (IF PROVIDED, X INDICATES DOOR HARDWARE GROUP #)	TO CONC	TOP OF CONCRETE
CL	CENTERLINE	ID	INSIDE DIAMETER	TO DECK	TOP OF DECKING
CLG	CEILING	INSUL	INSULATION	TO PLT	TOP OF PLATE
CMU	CONCRETE MASONRY UNIT	INT	INTERIOR	TO SLAB	TOP OF SLAB
COL	COLUMN	MATL	MATERIAL	TO STL	TOP OF STEEL
CONC	CONCRETE	MAX	MAXIMUM	TO SUB	TOP OF SUBFLOOR
CONT	CONTINUOUS	MECH	MECHANICAL	TSTAT	THERMOSTAT
CUH	CABINET UNIT HEATER	MFR	MANUFACTURER	TYP	TYPICAL
DBL	DOUBLE	MIN	MINIMUM	UNO	UNLESS NOTED OTHERWISE
DIA	DIAMETER	MIR	MIRROR	VIF	VERIFY IN FIELD
DIM	DIMENSION	MISC	MISCELLANEOUS	VR	VAPOR RETARDER
DN	DOWN	MRGYP	MOISTURE-RESISTANT GYPSUM BOARD	VTR	VENT THROUGH ROOF
DTL	DETAIL	MR	MOP RACK	WB	WEATHER BARRIER
EA	EACH	MTD	MOUNTED	WD	WOOD
EF	EPOXY FLOOR	MTL	METAL	WP	WATER PROOF
ELEC	ELECTRICAL	NA	NOT APPLICABLE	WPT	WOOD PRESERVATIVE TREATED
EQ	EQUAL	NFS	NON-FROST SUSCEPTIBLE	WSCT	WAINSCOT
EXIST	EXISTING	NIC	NOT IN CONTRACT		
EXT	EXTERIOR	OC	ON CENTER		
FBG	FIBERGLASS	OH	OVERHEAD		
FD	FLOOR DRAIN	OPP	OPPOSITE		
FDC	FIRE DEPARTMENT CONNECTION	OTS	OPEN TO STRUCTURE		
FDN	FOUNDATION	OVS	OIL-WATER SEPARATOR		
FE	FIRE EXTINGUISHER	PLYWD	PLYWOOD		
FEC	FIRE EXTINGUISHER CABINET	PR	PAIR		
FF	FACTORY FINISH	P	PAINT		
FLR	FLOOR	RAD	RADIUS		
FIN	FINISH	REQ	REQUIRED		
FOC	FACE OF CONCRETE	REV	REVISED / REVISION		
FOF	FACE OF FINISH	RM	ROOM		
FOS	FACE OF STUD	RO	ROUGH OPENING		
FRP	FIBERGLASS REINFORCED PLASTIC PANEL				
FRT	FIRE RETARDANT TREATED				
FT	FOOT / FEET				
FTG	FOOTING				
FURR	FURRING				

ASSEMBLY TYPE KEY

TYPE	DESCRIPTION
11 THRU 99	INTERIOR PARTITIONS
FA, FB, FC, ETC.	FLOORS
RA, RB, RC, ETC.	ROOFS
EA, EB, EC, ETC.	EXTERIOR WALLS


INTERIOR PARTITION KEY



PRIMARY FRAMING KEY

#	METAL	WOOD	CONC	MASONRY
1	7/8"	1x1	NA	NA
2	2 1/2"	2x2	NA	NA
3	3 5/8"	2x3	NA	NA
4	4"	2x4	4"	3 5/8"
6	6"	2x6	6"	5 5/8"
8	8"	2x8	8"	7 5/8"

FIRE RATING/PARTITION HEIGHT KEY



FIRE RATING/PARTITION HEIGHT NOTES

- W = NON-RATED, PARTIAL HEIGHT
- Y = NON-RATED, CEILING HEIGHT
- Z = NON-RATED, ABOVE CEILING HEIGHT
- 0 = NON-FIRE-RATED, ACOUSTIC WALL
- S = SMOKE PARTITION
- .5 = 1/2-HR RATED
- 1 = 1-HR RATED
- 2 = 2-HR RATED
- 3 = 3-HR RATED
- 4 = 4-HR RATED
- 5 = 1-HR RATED SMOKE BARRIER

BETTISWORTH
NORTH



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
 ABBREVIATIONS, GENERAL PROJECT NOTES, SYMBOLS


REVISION SCHEDULE

#	DESCRIPTION	DATE
---	-------------	------


PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	JLL
DESIGNED	KEI
REVIEWED	KEI

SHEET NO.

A001



1 FIRST FLOOR PLAN
A110 1/4" = 1'-0"



2 FIRST FLOOR REFLECTED CEILING PLAN
A110 1/4" = 1'-0"



REFLECTED CEILING PLAN LEGEND

	GYPSUM WALL BOARD CEILING
	LIGHT FIXTURE, SEE ELECTRICAL

GENERAL FLOOR PLAN NOTES

FIELD VERIFICATION: THE CONTRACTOR SHALL FIELD-VERIFY ALL DIMENSIONS PRIOR TO WORK. PROMPTLY NOTIFY THE ARCHITECT, OWNER'S REPRESENTATIVE, AND/OR THE CONTRACTING OFFICER IN WRITING OF ALL DISCREPANCIES IN NEW OR EXISTING CONDITIONS.

DIMENSIONING GUIDE: ALL DIMENSIONS ARE TAKEN FROM GRIDS, FACE OF METAL/WOOD STUD PARTITION, OR FACE OF MASONRY UNLESS OTHERWISE NOTED. DIMENSIONS BETWEEN SURFACES WILL BE NOTED WHERE APPLICABLE FROM MATERIAL FINISHES. UNLESS OTHERWISE NOTED ALL DIMENSIONS REFERENCED HEREIN ARE IMPERIAL STANDARDS AND SHALL BE TREATED WITHOUT ANY HIERARCHY OR ORDER OF PRECEDENCE.

REFERENCE ELEVATION: ALL ELEVATIONS NOTED ON THIS PLAN CORRESPOND TO REFERENCE ELEVATION 0'-0" FOR THIS FLOOR LEVEL. VARIANCES IN THIS ELEVATION MAY EXIST, AS INDICATED. UPPER FLOOR ELEVATIONS TO BE NOTED ACCORDINGLY.

DOOR OPENINGS: ALL DOOR OPENINGS ARE TAGGED IN CORRESPONDENCE WITH THE DOOR TYPE SCHEDULE ON SHEET A401. THIS MAY INCLUDE MISCELLANEOUS OPENINGS SUCH AS OVERHEAD SECTIONAL OR COILING, SLIDING, AND OPERABLE PANEL ASSEMBLIES. TYPICAL DOOR JAMBS ARE LOCATED 6" FROM FACE OF STUD AT ADJACENT WALL TO JAMB ROUGH OPENING UNO.

FLOOR SLOPE: UNLESS OTHERWISE NOTED THE FLOOR SHALL BE SLOPED TO THE DRAIN IN AREAS TO RECEIVE FLOOR DRAINS.

BETTISWORTH NORTH



FINAL DESIGN

VERIFY SCALE
BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
FIRST FLOOR PLAN, FIRST FLOOR REFLECTED CEILING PLAN

REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	JLL
DESIGNED	KEI
REVIEWED	KEI

SHEET NO. **A110**

A B C D

EXTERIOR FINISH LEGEND

EF-1	CMU
EF-2	STANDING SEAM METAL ROOF
EF-3	SINGLE SKIN METAL PANEL SIDING

NOTE: INSTALL ALL EXTERIOR WALL PENETRATING DEVICES PER MFR. SEAL ALL EXTERIOR WALL PENETRATIONS.

**BETTISWORTH
NORTH**



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
EXTERIOR ELEVATIONS

REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	JLL
DESIGNED	KEI
REVIEWED	KEI

SHEET NO.


A301

1


2

3


PLOT DATE: 4/14/2022 8:54:46 AM




1 NORTH ELEVATION
A301 1/4" = 1'-0"




2 EAST ELEVATION
A301 1/4" = 1'-0"




3 SOUTH ELEVATION
A301 1/4" = 1'-0"




4 WEST ELEVATION
A301 1/4" = 1'-0"




1 SECTION - N-S GENERATOR
1/4" = 1'-0"




2 SECTION - E-W
1/4" = 1'-0"



3 SECTION - N-S MANIFOLD ROOM
1/4" = 1'-0"



DOOR PANEL TYPES



DOOR FRAME TYPES


DOOR NO.	PANEL							FRAME					
	TYPE	WIDTH	HEIGHT	THICKNESS	MATERIAL	FINISH	TYPE	MATERIAL	FINISH	JAMB	HEAD	FIRE RATING	HARDWARE
101A	F	3'-0"	7'-0"	1 3/4"	FBG	FF	1	FBG	FF				01
101B	F	3'-0"	7'-0"	1 3/4"	FBG	FF	1	FBG	FF				02
102	OHD	10'-0"	12'-0"	1 1/2"	STL	FF	-	STL	FF				

A


B

C


D




1 EXTERIOR DOOR HEAD
A501 3" = 1'-0"




3 INTERIOR DOOR HEAD
A501 3" = 1'-0"




5 OHD HEAD
A501 3" = 1'-0"




2 EXTERIOR DOOR JAMB
A501 3" = 1'-0"




4 INTERIOR DOOR JAMB
A501 3" = 1'-0"



6 OHD JAMB
A501 3" = 1'-0"



7 LOUVER HEAD
A501 3" = 1'-0"



8 LOUVER SILL
A501 3" = 1'-0"

BETTISWORTH
NORTH



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

EXTERIOR DETAILS - OPENINGS

REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN JLL
DESIGNED
REVIEWED KEI

SHEET NO.

A501

1

2

3


PLOT DATE: 4/14/2022 8:54:49 AM

A


B

C


D




1 EAVE - HIGH END
 A502 3" = 1'-0"




4 EAVE - LOW END
 A502 3" = 1'-0"



2 TOP OF CMU
 A502 3" = 1'-0"



5 WALL BASE
 A502 3" = 1'-0"



3 RAKE
 A502 3" = 1'-0"

BETTISWORTH
 NORTH



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
 EXTERIOR DETAILS

REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN JLL
 DESIGNED
 REVIEWED KEI

SHEET NO.

A502

PLOT DATE: 4/14/2022 8:54:50 AM

ABBREVIATIONS

Table of abbreviations including EXISTING, NEW, ANCHOR BOLT, AMERICAN CONCRETE INSTITUTE, etc.

ABBREVIATIONS

Table of abbreviations including LAMINATED STRAND LUMBER, LAMINATED VENEER LUMBER, LIGHT WEIGHT CONCRETE, etc.

SYMBOLS


Table of symbols including DETAIL NUMBER, SHEET NUMBER, SECTION NUMBER, ELEVATION NUMBER, IMAGE NUMBER, KEYNOTE, etc.

DESIGN CRITERIA

Table of design criteria including DESIGN CODES AND STANDARDS, DESIGN DEAD LOADS, DESIGN LIVE LOADS, DESIGN SNOW LOADS, DESIGN WIND LOADS, DESIGN SEISMIC LOADS, and EARTHWORK.

MATERIALS & STRENGTH

Table of materials and strength including CONCRETE, STRUCTURAL STEEL, REINFORCING STEEL, CONCRETE MASONRY UNITS, WOOD, and PLYWOOD SHEATHING.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING. IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY.

WHITTIER WELL FIELD DESIGN

WHITTIER, ALASKA PROJECT No. 20403.14

STRUCTURAL GENERAL INFORMATION

REVISION SCHEDULE

Table with columns for REVISION, DESCRIPTION, and DATE.

Table with columns for PROJECT NO., DATE, DRAWN, DESIGNED, REVIEWED, and SHEET NO.

S001

GENERAL STRUCTURAL NOTES

(APPLY UNLESS NOTED OTHERWISE)

GENERAL

THE STRUCTURAL ENGINEER AND/OR ARCHITECT HAVE NOT BEEN RETAINED OR COMPENSATED TO PROVIDE DESIGN AND/OR CONSTRUCTION REVIEW SERVICES RELATED TO THE CONTRACTOR'S SAFETY PRECAUTIONS OR TO MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES FOR THE CONTRACTOR TO PERFORM HIS WORK. THE UNDERTAKING OF PERIODIC SITE VISITS BY THE ENGINEER SHALL NOT BE CONSTRUED AS SUPERVISION OF ACTUAL CONSTRUCTION NOR MAKE THEM RESPONSIBLE FOR PROVIDING A SAFE PLACE FOR THE PERFORMANCE OF WORK BY THE CONTRACTOR, SUBCONTRACTORS, SUPPLIERS OR THEIR EMPLOYEES, OR FOR ACCESS, VISITS, USE, WORK, TRAVEL OR OCCUPANCY BY ANY PERSON.

DRAWINGS INDICATE STRUCTURE IN FINAL FORM CAPABLE OF SUPPORTING DESIGN LOADS. PROVIDE TEMPORARY SUPPORT DURING CONSTRUCTION AS REQUIRED, UNTIL STRUCTURAL ELEMENTS ARE PERMANENTLY INSTALLED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SAFETY PRECAUTIONS AND THE METHODS, TECHNIQUES AND SEQUENCES OF PROCEDURES REQUIRED TO PERFORM THE WORK.

CONSTRUCTION MATERIALS SHALL BE DISTRIBUTED APPROPRIATELY IF PLACED ON FRAMED CONSTRUCTION. LOADS SHALL NOT EXCEED THE DESIGN LIVE LOAD PER SQUARE FOOT.

DO NOT SCALE DRAWINGS.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS AND SITE CONDITIONS BEFORE STARTING WORK. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ARCHITECT AND STRUCTURAL ENGINEER IN WRITING OF ANY DISCREPANCIES.

COORDINATE DIMENSIONS, OPENINGS, EMBEDDED ITEMS AND CONDITIONS WITH ARCHITECTURAL, CIVIL, MECHANICAL AND ELECTRICAL CONTRACT DOCUMENTS AND TRADES PRIOR TO CONSTRUCTION. NOT ALL ITEMS ARE INDICATED ON STRUCTURAL CONTRACT DOCUMENTS. NOTIFY STRUCTURAL ENGINEER IN WRITING OF ANY AND ALL DISCREPANCIES.

ALL DETAILS ARE TYPICAL. INCORPORATE INTO PROJECT AT APPROPRIATE LOCATIONS WHETHER SPECIFICALLY INDICATED OR NOT.

SPECIFIC NOTES AND DETAILS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE THE NOTES, DRAWINGS, AND/OR SPECIFICATIONS DIFFER, THE MORE STRINGENT REQUIREMENTS SHALL APPLY.

REFER TO ARCHITECTURAL AND CIVIL DRAWINGS FOR EXTERIOR SLABS AND WALLS.

NOTIFY STRUCTURAL ENGINEER OF ALL FIELD CHANGES PRIOR TO INSTALLATION.

THE CONTRACTOR SHALL MAINTAIN A CURRENT SET OF RED-LINE DRAWINGS ON SITE REFLECTING ALL DESIGN CHANGES TO THE ORIGINAL CONTRACT DOCUMENTS.

FOUNDATIONS AND EARTHWORK

REFERENCE GEOTECHNICAL REPORT NO. 20403.14, BY CRW ENGINEERING GROUP, LLC, DATED 11.5.2021 FOR FOUNDATION AND EXCAVATION INFORMATION.

FOOTINGS AND SLABS ON GRADE SHALL BEAR ON ENGINEERED SOIL PER CIVIL DRAWINGS.

PROVIDE POSITIVE DRAINAGE SLOPES, BOTH DURING AND AFTER CONSTRUCTION, FOR SURFACE AND ROOF RUNOFF, MINIMUM 10'-0" FROM BUILDING FOUNDATIONS.

ALL CONTINUOUS FOOTINGS SHALL BE CENTERED ON THE WALL UNO.

REINFORCED CAST IN PLACE CONCRETE

DETAILING PER APPLICABLE ACI DETAILING MANUAL, UNO.

SIZE, SPACING AND MINIMUM LAP SPLICES OF REINFORCING STEEL SHALL BE PROVIDED AS SHOWN IN CONTRACT DOCUMENTS.

REINFORCEMENT SPACINGS INDICATED ON THE DRAWINGS AND DETAILS ARE GIVEN AS A MAXIMUM ON CENTER.

CONTRACTOR SHALL ACCURATELY PLACE, LOCATE, SECURE AND/OR SUPPORT ALL REINFORCING BARS, ANCHOR BOLTS/RODS, AND EMBEDDED ITEMS PRIOR TO PLACING CONCRETE. CONTRACTOR SHALL USE GALVANIZED METAL CHAIRS, SPACERS, DOBIES OR HANGERS FOR THE CLEAR CONCRETE COVERAGES.

MINIMUM CONCRETE COVER, UNO:

CONCRETE CAST AGAINST AND EXPOSED TO EARTH: 3"

CONCRETE EXPOSED TO EARTH OR WEATHER: 1-1/2"

SLABS: 3/4"

TACK WELDING OF REINFORCING BARS SHALL NOT BE ALLOWED WITHOUT PRIOR REVIEW OF THE PROCEDURE WITH THE STRUCTURAL ENGINEER.

SPLICE HORIZONTAL REINFORCING AT CORNERS AND INTERSECTIONS.

REINFORCING HOOPS SHALL BE PROVIDED WITH CLASS B BAR LAPS REQUIRED FOR THE SPECIFIC BAR SIZE.

CHAMFER EXPOSED CORNERS 3/4" UNO.

DO NOT DROP CONCRETE MORE THAN FIVE FEET WITHOUT THE USE OF TREMIES.

MECHANICALLY VIBRATE ALL CONCRETE WHEN PLACED.

ALL CONCRETE SLABS ON GRADE SHALL BE BOUND BY CONTROL JOINTS (KEYED OR SAW CUT), SUCH THAT THE JOINT SPACING DOES NOT EXCEED 36 TIMES THE SLAB THICKNESS AND THE ASPECT RATIO OF THE ENCLOSED AREA DOES NOT EXCEED 1.5 TO 1.0. SAW CUTS SHALL BE 1/8" WIDE AND 1/4 TIMES THE SLAB THICKNESS IN DEPTH.

REINFORCED CONCRETE MASONRY UNITS (CMU)

DETAILING PER APPLICABLE ACI DETAILING MANUAL, UNO.

LAY UNITS IN RUNNING BOND.

CENTER REINFORCING IN CMU, UNO.

SOLID GROUT ALL CELLS.

SIZE, SPACING AND MINIMUM LAP SPLICES OF REINFORCING STEEL SHALL BE PROVIDED AS SHOWN IN CONTRACT DOCUMENTS. REINFORCEMENT SPACINGS INDICATED ON THE DRAWINGS AND DETAILS ARE GIVEN AS A MAXIMUM ON CENTER.

DOWEL ALL VERTICAL REINFORCING TO THE FOUNDATION WITH DOWELS TO MATCH SIZE AND SPACING OF VERTICAL REINFORCING.

CONTRACTOR SHALL ACCURATELY PLACE, LOCATE, SECURE AND/OR SUPPORT ALL REINFORCING BARS, ANCHOR BOLTS/RODS, EMBEDDED ITEMS, AND WELDED WIRE FABRIC PRIOR TO PLACING GROUT.

REBAR SPLICES SHALL LAP 48 DIAMETERS UNO. SPLICE HORIZONTAL REINFORCING AT ALL CORNERS AND INTERSECTIONS.

PROVIDE (1) VERTICAL BAR (MATCH VERTICAL WALL REINFORCING SIZE) AT ALL CORNERS, INTERSECTIONS AND ENDS, UNO.

AT OPENINGS PROVIDE (2) #5 HORIZONTAL AT HEAD AND SILL AND (1) #5 VERTICAL AT JAMBS, UNO. EXTEND 2'-0" BEYOND OPENING EACH SIDE, UNO.

FABRICATE SLEEVES FOR UTILITY LINES THROUGH WALLS WITH STANDARD WEIGHT STEEL PIPE, UNO.

CONTROL JOINTS: SPACE AT 24'-0" OC MAX, UNO.

MAXIMUM GROUT LIFT IS 4'-8" WITHOUT CLEANOUTS, 8'-0" WITH CLEANOUTS.

MECHANICALLY VIBRATE GROUT IN VERTICAL SPACE IMMEDIATELY AFTER PLACEMENT AND AGAIN ABOUT FIVE MINUTES LATER. DO NOT INTERRUPT GROUTING FOR MORE THAN ONE HOUR.

POST-INSTALLED ANCHORS

POST-INSTALLED ANCHOR EMBEDMENT SHALL BE PROVIDED AS SHOWN ON THE DRAWINGS. ALL POST-INSTALLED ANCHORS AND DOWELS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN RECOMMENDATIONS INCLUDING DRILL BIT SIZE, HOLE DEPTH AND CLEANING, MINIMUM EMBEDMENT, EDGE DISTANCES, MATERIAL PLACEMENT, TEMPERATURE AND MOISTURE CONTROL AND FINAL TORQUING REQUIREMENTS.

CONTRACTOR MAY NOT USE SUBSTITUTES FOR POST-INSTALLED ANCHORS WITHOUT PRIOR WRITTEN APPROVAL FROM THE STRUCTURAL ENGINEER.

NO REINFORCING BARS SHALL BE CUT TO INSTALL ANCHORS. ALL DEFECTIVE ANCHOR HOLES SHALL BE GROUTED WITH EPOXY ADHESIVE AND A NEW HOLE DRILLED A MINIMUM OF (3) BOLT DIAMETERS AWAY.

SPECIAL INSPECTION OF POST-INSTALLED ANCHORS IS REQUIRED.

STRUCTURAL STEEL

ALL STRUCTURAL STEEL CONSTRUCTION SHALL CONFORM WITH APPLICABLE AISC HANDBOOK.

ALL STRUCTURAL STEEL SHALL BE SURFACE PREPARED AND SHOP PAINTED AS NOTED. SURFACE PREPARATION SHALL CONFORM TO SSPC SP-3 POWER TOOL CLEANING TO REMOVE ALL SCALE AND RUST. ALL STRUCTURAL STEEL SHALL BE HOT-DIP GALVANIZED.

CONTRACTOR SHALL SUBMIT SHOP DRAWINGS PRIOR TO FABRICATION. SHOP DRAWINGS SHALL INCLUDE PIECE MARKS, ERECTION PLANS SHOWING BEAM SIZES AND DETAILS WITH CORRESPONDING CONTRACTOR DOCUMENT INDICATORS. SHOP DRAWINGS SHALL MAKE A DISTINCTION BETWEEN SHOP WELDS AND FIELD WELDS.

STRUCTURAL STEEL WELDING

ALL STRUCTURAL WELDING SHALL BE PRE-QUALIFIED AND CONFORM TO AISC AND AWS SPECIFICATIONS.

ALL WELDING SHALL BE IN ACCORDANCE WITH THE APPLICABLE AWS CODE. USE E70 SERIES LOW HYDROGEN ELECTRODES STORED AND MAINTAINED IN DRY CONDITION.

ALL WELDING SHALL BE PERFORMED BY AWS CERTIFIED WELDERS HAVING CURRENT CERTIFICATES AND EXPERIENCE IN THE TYPE OF WELD BEING PERFORMED. WELDING CERTIFICATES SHALL BE THOSE ISSUED BY AN ACCEPTED TEST AGENCY.

ALL CJP GROOVE WELDS SHALL HAVE FILLER MATERIAL THAT HAS A MINIMUM CHARPY-V NOTCH TOUGHNESS OF 20 FT-LB AT -20 °F AND 40 FT-LB AT 70 °F. CONTRACTOR SHALL SUBMIT WELDER QUALIFICATIONS AND PROCEDURE QUALIFICATIONS. WHERE NOT SHOWN, USE MINIMUM WELD SIZE PER AISC AND AWS.

STRUCTURAL CONSTRUCTION DRAWINGS DO NOT DISTINGUISH BETWEEN SHOP WELDS AND FIELD WELDS. THE CONTRACTOR SHALL COORDINATE WELDING DESIGNATIONS BETWEEN FABRICATOR AND ERECTOR. ALL STEEL SHOP DRAWINGS SHALL MAKE DISTINCTION BETWEEN SHOP WELDS AND FIELD WELDS.

ROUGH CARPENTRY AND PLYWOOD

ALL FRAMING SHALL BE PROVIDED IN ACCORDANCE WITH IBC CHAPTER 23. FRAMING LUMBER SHALL COMPLY WITH THE APPLICABLE NDS CODE.

MAXIMUM MOISTURE CONTENT OF LUMBER SHALL NOT EXCEED 19 PERCENT.

ALL SAWN LUMBER SHALL BE STAMPED WITH THE GRADE MARK OF AN APPROVED LUMBER GRADING AGENCY.

ALL LUMBER IN CONTACT WITH CONCRETE OR MASONRY SHALL BE PRESERVATIVE-TREATED WOOD STAMPED BY AN APPROVED AGENCY.

ALL PLYWOOD SHALL CONFORM TO PS-1 OR APA PRP-108, SHALL HAVE AN EXTERIOR OR EXPOSURE 1 CLASSIFICATION AND SHALL BEAR THE STAMP OF AN APPROVED TESTING AGENCY.

PLYWOOD SHALL BE INSTALLED WITH FACE GRAIN ORIENTED PERPENDICULAR TO SUPPORTS, STAGGER JOINTS. PLYWOOD NAILING SHALL BE PROVIDED ON ALL BOUNDARIES, EDGES AND INTERMEDIATE SUPPORTS.

METAL FRAMING CONNECTORS SHALL BE MANUFACTURED BY SIMPSON STRONG-TIE COMPANY, INCORPORATED, OR OTHER APPROVED EQUIVALENT MANUFACTURER. ALL NAIL/SCREW HOLES IN CONNECTORS SHALL BE FILLED WITH NAILS/SCREWS OF THE LARGEST SIZE INDICATED IN THE MANUFACTURER'S CATALOG UNO.

METAL FRAMING CONNECTORS AND FASTENERS IN CONTRACT WITH PRESERVATIVE-TREATED WOOD SHALL BE GALVANIZED OR STAINLESS STEEL.

NAILING SHALL CONFORM TO TABLE 2304.9.1 OF THE IBC. ALL NAILS SHALL BE COMMON SIZE IN ACCORDANCE WITH ASTM F1667.

SILL PLATES SHALL HAVE 5/8" DIA ANCHOR PLACED AT ALL JAMBS, CORNERS, INTERSECTIONS AND DISCONTINUOUS WALL ENDS, AND AT 48" OC MAX UNO (MINIMUM TWO ANCHORS PER PLATE SECTION).

PREFABRICATED WOOD TRUSSES

THE TRUSS MANUFACTURER SHALL BE RESPONSIBLE FOR THE COMPLETE DESIGN, FABRICATION AND ERECTION PROCEDURES OF ALL TRUSSES, BRIDGING AND/OR BLOCKING PANELS, HANGERS, BRACING, ETC. FOR A COMPLETE INSTALLATION OF THE TRUSS SYSTEM. TRUSS CONFIGURATIONS ARE INDICATED ON THE DRAWINGS. ALL BRACING AND BRIDGING SIZES AND SPACINGS PER THE TRUSS MANUFACTURER IN ACCORDANCE WITH THE LATEST RECOMMENDATIONS OF THE TRUSS PLATE INSTITUTE.

TRUSSES SHALL BE DESIGNED AND FABRICATED IN ACCORDANCE WITH IBC CHAPTER 23 TO SUPPORT SELF WEIGHT PLUS LIVE LOAD, SUPERIMPOSED DEAD LOADS, AND LATERAL LOADS STATED IN THE GENERAL STRUCTURAL NOTES OR LOCATED ON PLANS. ROOF TRUSSES SHALL BE DESIGNED TO ACCOMMODATE A FUTURE TOP CHORD DEAD LOAD OF 300 POUNDS AT ANY LOCATION. THE UNIFORM LOADS DO NOT INCLUDE SPECIAL OR ADDITIONAL LOADS NOTED ON THE PLANS OR DETAILS. THE ROOF LOAD DURATION FACTOR IS 1.15.

LIMIT TOTAL LOAD DEFLECTIONS TO SPAN/240 AT SIMPLE SPANS UNO. LIMIT LIVE LOAD DEFLECTIONS TO SPAN/360 AT SIMPLE SPANS UNO. ALL TRUSSES SHALL BE CAMBERED FOR 1.5 TIMES THE DESIGN DEAD LOAD.

ADDITIONAL TRUSSES SHALL BE SUPPLIED AS REQUIRED TO SUPPORT MECHANICAL EQUIPMENT AND AS REQUIRED TO FRAME AROUND DUCT PENETRATIONS. GENERAL CONTRACTOR TO COORDINATE WITH ALL DISCIPLINES AND TRADES.

ALL CONNECTORS SHALL HAVE CURRENT ICC APPROVAL. ALL TRUSS TO TRUSS CONNECTORS SHALL BE DESIGNED BY THE TRUSS MANUFACTURER. MULTIPLE TRUSS MEMBERS SHALL BE FASTENED TOGETHER TO ALLOW TRANSFER OF SHEAR AND TENSION FORCES (MINIMUM 200 PLF) AT PLYWOOD SHEATHING JOINTS AND TO PREVENT CROSS GRAIN BENDING OF TOP CHORDS. ATTACHMENT SHALL BE A CONTINUOUS 20 GAGE METAL PLATE OR OTHER APPROVED MEANS. METHOD OF ATTACHMENT SHALL BE INDICATED ON SHOP DRAWINGS FOR REVIEW.

WHERE PERMANENT BRACING OF TRUSS MEMBERS IS REQUIRED BY THE TRUSS DESIGN, IT SHALL BE ACCOMPLISHED BY THE FOLLOWING METHOD: THE TRUSSES SHALL BE DESIGNED SO THAT THE BUCKLING OF ANY INDIVIDUAL TRUSS MEMBER CAN BE RESISTED INTERNALLY BY THE STRUCTURE (E.G. BUCKLING MEMBER T-BRACING, L-BRACING, ETC.) OF THE INDIVIDUAL TRUSS. THE TRUSS INDIVIDUAL MEMBER BUCKLING REINFORCEMENT SHALL BE INSTALLED AS SHOWN ON THE TRUSS DESIGN DRAWING OR ON SUPPLEMENTAL TRUSS MEMBER BUCKLING REINFORCEMENT DIAGRAMS PROVIDED BY THE TRUSS DESIGNER.

THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS, ERECTION DRAWINGS AND DESIGN CALCULATIONS SEALED BY A REGISTERED ENGINEER FOR REVIEW PRIOR TO MANUFACTURE. CALCULATIONS AND SHOP DRAWINGS SHALL SHOW ANY SPECIAL DETAILS REQUIRED AT BEARING POINTS.

ALL FABRICATION SHALL BE PERFORMED ON THE PREMISES OF A FABRICATOR REGISTERED AND APPROVED TO PERFORM SUCH WORK WITHOUT SPECIAL INSPECTION.

STRUCTURAL SHOP DRAWINGS AND PRODUCT DATA SUBMITTALS

SUBMIT SHOP DRAWINGS AND/OR PRODUCT DATA FOR THE FOLLOWING ITEMS, PRIOR TO FABRICATION:

CONCRETE MATERIALS
CONCRETE REINFORCING STEEL
MASONRY MATERIALS
MASONRY REINFORCING STEEL
STRUCTURAL STEEL FRAMING
WOOD TRUSSES

CONTRACTOR SHALL REVIEW AND STAMP SUBMITTALS PRIOR TO SUBMISSION. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL MATERIALS PLACED PRIOR TO RECEIPT OF REVIEWED SHOP DRAWINGS. CONTRACTOR SHALL ALLOW A MINIMUM OF (10) WORKING DAYS FOR REVIEW.

CONTRACT DOCUMENTS SHALL NOT BE REPRODUCED FOR USE AS SHOP DRAWINGS. THE MANUFACTURER OR FABRICATOR SHALL CLOUD ANY CHANGES, SUBSTITUTIONS AND/OR DEVIATIONS FROM THE CONTRACT DOCUMENTS. ANY CHANGES, SUBSTITUTIONS AND/OR DEVIATIONS THAT ARE NOT CLOUDED OR FLAGGED SHALL NOT BE CONSIDERED ALLOWED AFTER THE ENGINEER'S REVIEW UNO.

THE ENGINEER'S REVIEW IS INTENDED ONLY AS AN AID TO THE CONTRACTOR IN OBTAINING CORRECT SHOP DRAWINGS. RESPONSIBILITY FOR CORRECTNESS AND COMPLETENESS SHALL REST WITH THE CONTRACTOR. SHOP DRAWINGS WILL BE RETURNED FOR RESUBMITTAL IF SIGNIFICANT ERRORS ARE FOUND DURING REVIEW.

THE SHOP DRAWINGS DO NOT REPLACE THE CONTRACT DOCUMENTS. SHOP DRAWINGS PROCESSED BY THE ENGINEER SHALL NOT BE CONSIDERED CHANGE ORDERS. ITEMS THAT ARE OMITTED OR SHOWN INCORRECTLY AND THAT ARE NOT FLAGGED BY THE ENGINEER ARE NOT TO BE CONSIDERED CHANGES TO CONTRACT DOCUMENTS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONSTRUCT ITEMS ACCORDING TO THE CONTRACT DOCUMENTS. SHOULD A DISCREPANCY EXIST BETWEEN THE PROCESSED SHOP DRAWINGS AND THE CONTRACT DOCUMENTS, THE CONTRACT DOCUMENTS SHALL GOVERN.

THE ENGINEER RESERVES THE RIGHT TO MAKE CHANGES TO THE CONTRACT DOCUMENTS, AT ANY TIME BEFORE OR AFTER SHOP DRAWING REVIEW.

FOR HARD COPY SUBMITTALS, PROVIDE NO MORE THAN FOUR SETS FOR REVIEW (ONE COPY TO BE RETAINED BY THE ENGINEER OF RECORD). FOR ELECTRONIC SUBMITTALS, PROVIDE PDF FILES ONLY. ALL SUBMITTALS WITH A REQUESTED REVIEW TIME OF LESS THAN (10) WORKING DAYS MAY BE RETURNED WITHOUT REVIEW AT THE ENGINEER'S DISCRETION.

DEFERRED STRUCTURAL SUBMITTALS

THE FOLLOWING ITEMS ARE DESIGNED AND DETAILED BY THE CONTRACTOR USING THE LOADING AND CRITERIA SHOWN IN THE CONTRACT DOCUMENTS. DEFERRED SUBMITTALS SHALL INCLUDE CALCULATIONS AND DRAWINGS STAMPED BY AN ALASKA REGISTERED ENGINEER AND ARE TO BE SUBMITTED TO THE CONTRACTING OFFICER PRIOR TO FABRICATION:

WOOD TRUSSES
MECHANICAL UNIT SEISMIC RESTRAINT
ROOFING ATTACHMENT

REFER TO ARCHITECTURAL, MECHANICAL AND ELECTRICAL FOR OTHER DEFERRED SUBMITTALS.

DEFERRAL OF ANY SUBMITTAL ITEMS SHALL HAVE PRIOR APPROVAL OF THE BUILDING OFFICIAL. THE ARCHITECT OR ENGINEER OF RECORD SHALL LIST THE DEFERRED SUBMITTALS ON THE CONTRACT DOCUMENTS AND THE CONTRACTOR SHALL SUBMIT THE DEFERRED SUBMITTAL DOCUMENTS FOR REVIEW BY THE BUILDING OFFICIAL.

SUBMITTAL DOCUMENTS FOR DEFERRED SUBMITTAL ITEMS SHALL BE SUBMITTED TO THE CONTRACTING OFFICIAL OR ENGINEER OF RECORD A MINIMUM OF 30 DAYS PRIOR TO FABRICATION. THE DOCUMENTS SHALL BE REVIEWED FOR GENERAL CONFORMANCE WITH THE DRAWINGS. A COPY OF THE DEFERRED SUBMITTAL DOCUMENTS SHALL BE SUBMITTED TO THE BUILDING OFFICIAL WITH A NOTATION INDICATING THAT THE DEFERRED SUBMITTAL DOCUMENTS HAVE BEEN REVIEWED. THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THEIR DESIGN AND SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING

0" 1"

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD DESIGN

WHITTIER, ALASKA
PROJECT No. 20403.14

GENERAL STRUCTURAL NOTES

REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	1/4/2022
DRAWN	MEH
DESIGNED	WS
REVIEWED	NJC

SHEET NO.

S002

3

PLOT DATE: 1/31/2022 12:34:36 PM

GENERAL STRUCTURAL NOTES (CONTINUED)

(APPLY UNLESS NOTED OTHERWISE)

SPECIAL STRUCTURAL INSPECTIONS AND TESTING

THE OWNER (OR REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE ACTING AS THE OWNER'S AGENT) SHALL EMPLOY ONE OR MORE SPECIAL INSPECTORS TO PROVIDE INSPECTION AND TESTING DURING CONSTRUCTION OF THE TYPES OF WORK REQUIRING SPECIAL INSPECTION AS INDICATED ON THE DRAWINGS.

EACH SPECIAL INSPECTOR SHALL BE A QUALIFIED PERSON WHO SHALL DEMONSTRATE COMPETENCE, TO THE SATISFACTION OF THE BUILDING OFFICIAL AND STRUCTURAL ENGINEER OF RECORD, FOR INSPECTION OF THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION REQUIRING SPECIAL INSPECTION.

DUTIES AND RESPONSIBILITIES OF THE SPECIAL INSPECTOR

THE SPECIAL INSPECTOR SHALL OBSERVE THE WORK ASSIGNED FOR CONFORMANCE TO THE APPROVED CONSTRUCTION DOCUMENTS.

THE SPECIAL INSPECTOR SHALL FURNISH INSPECTION REPORTS TO THE BUILDING OFFICIAL AND TO THE ENGINEER OR ARCHITECT OF RECORD. REPORTS SHALL INDICATE THAT WORK INSPECTED WAS DONE IN CONFORMANCE TO APPROVED CONSTRUCTION DOCUMENTS. DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION, THEN IF UNCORRECTED, TO THE ENGINEER OR ARCHITECT OF RECORD AND THE BUILDING OFFICIAL.

UPON COMPLETION OF THE ASSIGNED WORK, THE SPECIAL INSPECTOR SHALL COMPLETE AND SIGN THE APPROPRIATE FORMS CERTIFYING THAT, TO THE BEST OF THEIR KNOWLEDGE, THE WORK IS IN CONFORMANCE WITH THE APPROVED CONSTRUCTION DOCUMENTS AND THE APPLICABLE WORKMANSHIP PROVISIONS OF THE CODE.

DEFINITIONS

CONTINUOUS SPECIAL INSPECTION: CONTINUOUS SPECIAL INSPECTION IS THE FULL TIME OBSERVATION OF THE WORK BY THE SPECIAL INSPECTOR PRESENT IN THE WORK AREA WHENEVER WORK IS BEING PERFORMED. PERFORM CONTINUOUS SPECIAL INSPECTION WHERE SPECIFIED AS INDICATED IN THE SPECIAL INSPECTION TABLES.

PERIODIC SPECIAL INSPECTION: PERIODIC SPECIAL INSPECTION IS THE INTERMITTENT OBSERVATION OF THE WORK BY A SPECIAL INSPECTOR PRESENT IN THE WORK AREA WHILE WORK IS BEING PERFORMED. THE INTERMITTENT OBSERVATION PERIODS SHALL BE AT TIME OF SIGNIFICANT WORK, RECURRENT OVER THE COMPLETE WORK PERIOD AND TOTAL AT LEAST 25 PERCENT OF THE TOTAL WORK TIME FOR A GIVEN TASK. PERFORM PERIODIC SPECIAL INSPECTION WHERE SPECIFIED FOR ITEMS AS INDICATED IN THE SPECIAL INSPECTION TABLES.

SYSTEM OR MATERIAL	IBC CODE REF	CODE OR STANDARD REFERENCE	INSPECTION		REMARKS
			CONTINUOUS	PERIODIC	
CONCRETE					
REINFORCING STEEL AND PRESTRESSING TENDONS AND PLACEMENT	1705.3 1910.4	ACI 318 3.5 ACI 318 7.1 ACI 318 7.2 ACI 318 7.3 ACI 318 7.4 ACI 318 7.5 ACI 318 7.6 ACI 318 7.7		X	---
PLACEMENT OF CAST-IN-PLACE ANCHOR BOLTS	1705.3 1908.5 1909.1	ACI 318 8.1.3 ACI 318 21.1.8		X	ALL ANCHOR BOLTS ARE VISUALLY INSPECTED
VERIFY USE OF REQUIRED MIX DESIGNS(S)	1705.3 1904.2 1910.2 1910.3	ACI 318 5.2 ACI 318 5.3 ACI 318 5.4 ACI 318 CHAPTER 4		X	---
SAMPLING OF CONCRETE FOR STRENGTH, SLUMP, AIR TESTS, AND TEMPERATURE DETERMINATION	1705.3 1910.10	ACI 318 5.8 ASTM C 31 ASTM C 172		X	---
CONCRETE AND SHOTCRETE PLACEMENT	1705.3 1910.6 1910.7 1910.8	ACI 318 5.9 ACI 318 5.10		X	---
CONCRETE AND SHOTCRETE CURING	1705.3 1910.9	ACI 318 5.11 ACI 318 5.12 ACI 318 5.13		X	---

STRUCTURAL SPECIAL INSPECTIONS (CONT.)					
SYSTEM OR MATERIAL	IBC CODE REF	CODE OR STANDARD REFERENCE	INSPECTION		REMARKS
			CONTINUOUS	PERIODIC	
MASONRY (LEVEL C)					
VERIFY COMPLIANCE WITH THE APPROVED SUBMITTALS	1705.4	ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 1.5		X	---
VERIFY THAT THE FOLLOWING ARE IN COMPLIANCE:					
A. PROPORTIONS OF SITE-MIXED MORTAR, GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS	1705.4	ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 2.1, 2.6 A, 2.6 B, 2.6 C, 2.4 G.1.b		X	---
B. GRADE, TYPE, AND SIZE OF REINFORCEMENT AND ANCHOR BOLTS, AND PRESTRESSING TENDONS AND ANCHORAGES	1705.4	ACI 530 SEC. 1.16 ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 2.4, 3.4		X	---
C. PLACEMENT OF MASONRY UNITS AND CONSTRUCTION OF MORTAR JOINTS	1705.4	ACI 530 SEC. 1.16 ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 2.4, 3.4		X	---
D. PLACEMENT OF REINFORCEMENT, CONNECTORS AND PRESTRESSING TENDONS AND ANCHORAGES	1705.4	ACI 530 SEC. 1.16 ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 3.2 E, 3.4, 3.6 A	X		---
E. GROUT SPACE PRIOR TO GROUTING	1705.4	ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 3.2 D, 3.2 F	X		---
F. PLACEMENT OF GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS	1705.4	ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 3.5, 3.6 C	X		---
G. SIZE AND LOCATION OF STRUCTURAL ELEMENTS	1705.4	ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 3.3 F		X	---
H. TYPE, SIZE, AND LOCATION OF ANCHORS INCLUDING OTHER DETAILS OF ANCHORAGE OF MASONRY TO STRUCTURAL MEMBERS, FRAMES, OR OTHER CONSTRUCTION	1705.4	ACI 530 SEC. 1.16.4.3, 1.17.1 ACI 530.1 TABLE 1.19.3	X		---
I. WELDING OF REINFORCEMENT	1705.4	ACI 530 SEC. 3.3.3.4 (c), 8.3.3.4 (b) ACI 530.1 TABLE 1.19.3	X		---
J. PREPARATION, CONSTRUCTION AND PROTECTION OF MASONRY DURING COLD WEATHER (TEMPERATURE BELOW 40°F) OR HOT WEATHER (TEMPERATURE ABOVE 90°F)	1705.4	ACI 530.1 1.19.3 ACI 530.1 ART. 1.8 C, 1.8 D		X	---
K. APPLICATION AND MEASUREMENT OF PRESTRESSING FORCE	1705.4	ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 3.6 B	X		---
L. PLACEMENT OF AAC MASONRY UNITS AND CONSTRUCTION OF THIN-BED MORTAR JOINTS	1705.4	ACI 530.1 TABLE 1.19.3 ART. 3.3 B.8	X		---
M. PROPERTIES OF THIN-BED MORTAR FOR AAC MASONRY	1705.4	ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 2.1 C.1	X		---
OBSERVE PREPARATION OF GROUT SPECIMENS, MORTAR SPECIMENS, AND/OR PRISMS	1705.4	ACI 530.1 TABLE 1.19.3 ACI 530.1 ART. 1.4 B.2.a.3, 1.4 B.2.b.3, 1.4 B.2.c.3, 1.4 B.3, 1.4 B.4	X		---
POST-INSTALLED ANCHORS					
POST-INSTALLED ANCHORS	1705.3 1901.1	ACI 3.8.6 ACI 8.1.3 ACI 318 21.1.8 ICC EVALUATION REPORT		X	SPECIAL INSPECTIONS APPLY TO ANCHOR PRODUCT NAME, TYPE, DIMENSIONS, HOLE DIMENSIONS, COMPLIANCE WITH DRILL BIT REQUIREMENTS, CLEANLINESS OF THE HOLE AND ANCHOR, ADHESIVE EXPIRATION DATE, ANCHOR/ADHESIVE INSTALLATIO...
STRUCTURAL WOOD FRAMING					
FABRICATION OF HIGH-LOAD WOOD DIAPHRAGMS:					
A. VERIFY STRUCTURAL GRADE AND THICKNESS	1705.5.1 TABLE 2306.2(2)		X		---
B. VERIFY NOMINAL SIZE OF FRAMING MEMBERS AT ADJOINING PANEL EDGES	1705.5.1 TABLE 2306.2(2)		X		---
C. VERIFY NAIL OR STAPLE DIAMETER AND LENGTH, NUMBER OF FASTENER LINES AND SPACING BETWEEN FASTENERS IN EACH LINE AND AT EDGE MARGINS	1705.5.1 TABLE 2306.2(2)		X		---

GEOTECHNICAL SPECIAL INSPECTIONS					
SYSTEM OR MATERIAL	IBC CODE REF	CODE OR STANDARD REFERENCE	INSPECTION		REMARKS
			CONTINUOUS	PERIODIC	
SOILS					
VERIFY MATERIALS BELOW SHALLOW FOUNDATIONS ARE ADEQUATE TO ACHIEVE DESIGN BEARING CAPACITY	1705.6	I.B.C.		X	---
VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL	1705.6	I.B.C.		X	---
PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS	1705.6	I.B.C.		X	---
VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL	1705.6	I.B.C.	X		---
PRIOR TO PLACEMENT OF COMPACTED FILL, OBSERVE SUBGRADE AND VERIFY SITE HAS BEEN PROPERLY PREPARED	1705.6	I.B.C.		X	---

TESTING FOR SPECIAL INSPECTIONS					
SYSTEM OR MATERIAL	IBC CODE REF	CODE OR STANDARD REFERENCE	INSPECTION		REMARKS
			CONTINUOUS	PERIODIC	
GEOTECHNICAL					
FILL IN-PLACE DENSITY OR PREPARED SUBGRADE DENSITY	VARIABLES	I.B.C.			
MATERIAL VERIFICATION	VARIABLES	I.B.C.			
CONCRETE					
CONCRETE STRENGTH	1705.3 1905.6	ASTM C39			FREQUENCY: EACH 50 CUBIC YARDS. NOT LESS THAN ONE TEST EACH 5,000 SQUARE FEET OF SLAB OR WALL PLACED EACH DAY
CONCRETE SLUMP	1705.3 1905.6	ASTM C143			FREQUENCY: EACH 50 CUBIC YARDS. NOT LESS THAN ONE TEST EACH 5,000 SQUARE FEET OF SLAB OR WALL PLACED EACH DAY
CONCRETE AIR CONTENT	1705.3 1905.6	ASTM C231			FREQUENCY: EACH 50 CUBIC YARDS. NOT LESS THAN ONE TEST EACH 5,000 SQUARE FEET OF SLAB OR WALL PLACED EACH DAY
CONCRETE TEMPERATURE	1705.3 1905.6	ASTM C1064			FREQUENCY: EACH 50 CUBIC YARDS. NOT LESS THAN ONE TEST EACH 5,000 SQUARE FEET OF SLAB OR WALL PLACED EACH DAY
SHOTCRETE STRENGTH	1705.3 1910.10	ASTM C39			FREQUENCY: EACH 50 CUBIC YARDS. NOT LESS THAN ONE TEST EACH 5,000 SQUARE FEET OF SLAB OR WALL PLACED EACH DAY

SPECIAL INSPECTIONS FOR SEISMIC RESISTANCE					
SYSTEM OR MATERIAL	IBC CODE REF	CODE OR STANDARD REFERENCE	INSPECTION		REMARKS
			CONTINUOUS	PERIODIC	
STRUCTURAL WOOD					
FIELD GLUING OPERATIONS OF DIAPHRAGM AND SHEAR WALL ELEMENTS	1705.11.2			X	---
NAILING, SCREWING, BOLTING, ANCHORING AND OTHER FASTENING OF COMPONENTS WITHIN THE MAIN SEISMIC FORCE-RESISTING SYSTEM, INCLUDING WOOD SHEAR WALLS, WOOD DIAPHRAGMS, DRAG STRUTS, BRACES AND HOLD-DOWNS	1705.11.2			X	SPECIAL INSPECTION IS NOT REQUIRED FOR WOOD SHEAR WALLS, SHEAR PANELS, AND DIAPHRAGMS, INCLUDING NAILING, SCREWING, BOLTING, ANCHORING AND OTHER FASTENING COMPONENTS OF THE MAIN WINDFORCE RESISTING SYSTEM, WHEN THE FASTENER SPACING OF THE SHEATHING IS MORE THAN 4 INCHES ON CENTER
MECHANICAL AND ELECTRICAL COMPONENTS					
INSTALLATION OF ANCHORAGE OF ELECTRICAL EQUIPMENT FOR EMERGENCY OR STANDBY POWER SYSTEMS	1705.11.6			X	APPLIES TO STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY C, D, E OR F
INSTALLATION OF ANCHORAGE OF ALL ELECTRICAL EQUIPMENT	1705.11.6			X	APPLIES TO STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY E OR F



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD DESIGN

WHITTIER, ALASKA
PROJECT No. 20403.14

SPECIAL INSPECTION AND TESTING TABLES

REVISION SCHEDULE

NO.	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	1/4/2022
DRAWN	MEH
DESIGNED	WS
REVIEWED	NJC

SHEET NO.

S003

PLOT DATE: 1/31/2022 12:34:36 PM

A

B

C

D

FOUNDATION (F) SCHEDULE					
NOTES:					
1. FOR FOOTING BEARING DEPTH BELOW GRADE, SEE GSN, UNO.					
2. CENTER FOOTINGS UNDER WALLS OR COLUMNS, UNO.					
3. WHERE FOOTINGS INTERSET, THE GREATER REINFORCING REQUIREMENTS SHALL GOVERN.					
KEYED NOTES:					
A. PROVIDE CLEAR DISTANCE FOR TOP REINFORCING OF 6".					
B. PROVIDE 1" CLEAR SPACE BETWEEN DOUBLE LAYER OF BARS.					
MARK	DIMENSIONS			FOOTING REINFORCING	REMARKS
	HEIGHT	WIDTH	LENGTH		
F1	1'-0"	3'-0"	30'-0 3/4"CONT	(4) #5 BARS CONT. T&B, AND #5 AT 12" OC TRANSVERSE T&B	---
F2	1'-0"	2'-6"	CONT	(4) #5 BARS CONT. T&B, AND #5 AT 12" OC TRANSVERSE T&B	---

FOUNDATION KEYNOTES:


- 1 TYPICAL: 8" CMU WALL, REINF w/ #5 VERTICAL BARS AT 16" OC AND #5 HORIZONTAL BARS AT 24" OC.
- 2 8" CONC SLAB ON GRADE, REINF w/ #4 BARS AT 16" OC, EA WAY, IN TOP 1/3 OF SLAB.
- 3 TYPICAL: CONCRETE CURB, SEE DETAILS.
- 4 TYPICAL: FLOOR DRAIN, COORDINATE WITH MECHANICAL AND ARCHITECTURAL DRAWINGS. SLOPE SLABS TOWARDS FLOOR DRAINS.
- 5 ELECTRIC GENERATOR, COORDINATE WITH ELECTRICAL DRAWINGS. ANCHOR TO SLAB WITH (8) 5/8" DIA. STAINLESS STEEL POST-INSTALLED ANCHORS WITH 6" EMBEDMENT [4 EACH SIDE, EVENLY SPACED].



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY



1 FOUNDATION PLAN
 SCALE: 1/4" = 1'-0"

WHITTIER WELL FIELD DESIGN
 WHITTIER, ALASKA
 PROJECT No. 20403.14
FOUNDATION PLAN

REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO. 20403.14
 DATE 1/4/2022
 DRAWN MEH
 DESIGNED WS
 REVIEWED NJC

SHEET NO.

S201

1

2

3

PLOT DATE: 1/31/2022 12:34:37 PM

A


B

C

D

FRAMING KEYNOTES:

1 ROOF SHEATHING PER SHEET S001. BLOCK ALL EDGES. ATTACH WITH 10D NAILS AT 2" OC AT BOUNDARIES AND 3" OC ALL OTHER EDGES AND 8" OC IN FIELD.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD DESIGN

WHITTIER, ALASKA
PROJECT No. 20403.14

ROOF FRAMING PLAN


REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO. 20403.14
 DATE 1/4/2022
 DRAWN MEH
 DESIGNED WS
 REVIEWED NJC

SHEET NO.

S202




1 ROOF FRAMING PLAN
SCALE: 1/4" = 1'-0"

1

2

3

PLOT DATE: 1/31/2022 12:34:37 PM



1 TYPICAL CONCRETE REINFORCING AT WALLS & FOOTINGS
SCALE: NTS


CONCRETE PSI	TENSION SPLICE LENGTHS (CLASS B)								COMPRESSION BARS	
	$f_c = 2,500/3,000$ PSI		$f_c = 4,000/4,500$ PSI		$f_c = 5,000$ PSI		$f_c < 3,000$ PSI		$f_c \geq 3,000$ PSI	
BAR LOCATION	REGULAR	TOP	REGULAR	TOP	REGULAR	TOP	REGULAR	TOP	ENCLOSED WITH SPIRAL TIES	ENCLOSED WITH SPIRAL TIES
#3	24"	36"	31"	46"	19"	28"	25"	37"	17"	22"
#4	32"	47"	41"	61"	25"	37"	33"	49"	23"	34"
#5	39"	59"	51"	77"	31"	47"	41"	61"	28"	42"
#6	47"	71"	61"	92"	37"	56"	49"	73"	34"	50"
#7	69"	103"	89"	134"	54"	81"	71"	106"	49"	73"
#8	78"	117"	102"	153"	62"	93"	81"	121"	56"	83"
#9	88"	132"	115"	172"	70"	105"	91"	136"	63"	94"
#10	100"	149"	129"	194"	79"	118"	102"	153"	71"	106"
#11	110"	165"	143"	215"	87"	131"	114"	170"	78"	117"

2 TYPICAL MINIMUM REINFORCING BAR SPLICE LENGTHS IN CONCRETE
SCALE: NTS


NOTES:
1. TOP BARS ARE ANY HORIZONTAL BARS PLACED SO THAT MORE THAN 12" OF FRESH CONCRETE IS CAST IN THE MEMBER BELOW THE REINFORCEMENT.
2. CONCRETE COVERAGE AROUND REINFORCING SHALL NOT BE LESS THAN THE DIAMETER OF THE BAR, APPLICABLE TO BARS HAVING A YIELD STRESS OF 60,000 PSI OR LOWER.
3. WHEN BARS OF DIFFERENT SIZE ARE LAP SPICED IN TENSION, SPLICE LENGTH SHALL BE BASED ON LARGER BAR DIAMETER.
4. LAP SPLICES SHALL BE STAGGERED AT LEAST 24 INCHES.
5. FOR SPIRALS, LAP SPLICE SHALL BE THE GREATER OF 12 INCHES OR 48 BAR DIAMETERS.

BAR SIZE	END HOOKS, ALL GRADES		
	FINISHED BEND DIA	180° HOOKS	90° HOOKS
	D	A OR G	J
#3	2 1/4"	5"	3"
#4	3"	6"	4"
#5	3 3/4"	7"	5"
#6	4 1/2"	8"	6"
#7	5 1/4"	10"	7"
#8	6"	11"	8"
#9	9 1/2"	15"	11 3/4"
#10	10 3/4"	17"	13 1/4"
#11	12"	19"	14 3/4"
#14	18 1/4"	27"	21 3/4"
#18	24"	36"	28 1/2"

3 TYPICAL REINFORCING HOOK SCHEDULE
SCALE: NTS




GENERAL NOTES:
A. HORIZONTAL REINFORCING IS CONTINUOUS THRU CONTROL JOINT AT ROOF.
A. UNIFORM WALL REINFORCING NOT SHOWN FOR CLARITY. SEE PLANS FOR BALANCE OF WALL REINFORCING.




4 TYPICAL CONCRETE REINFORCING BAR DETAILS
SCALE: NTS

NOTES:
1. RADIUS = 3 bd FOR BARS NOT OVER #8; 4 bd FOR #9, #10 AND #11 BARS; 5 bd FOR #14 AND #18 BARS; 5 bd FOR ALL GRADE 40 BARS WITH 180° HOOK.
2. BEND AROUND 1 1/2" PIN FOR #3 BARS. BEND AROUND 2" PIN FOR #4 BARS. BEND AROUND 2 1/2" PIN FOR #5 BARS.




5 TYPICAL MASONRY REINFORCING AT WALLS
SCALE: NTS




6 TYPICAL CONTROL JOINT IN MASONRY WALL
SCALE: NTS

GENERAL NOTES:
A. KEYED JOINTS NEED ONLY OCCUR AT EXPOSED EDGES DURING PLACEMENT UNLESS SPECIFICALLY NOTED ON THE PLANS. "TOOL WET JOINT", "SIP STRIP", ETC. SHALL MATCH SAWCUT REQUIREMENTS. SEE GSN FOR JOINT SPACING SPECIFICATIONS.


ANCHOR DIAMETER	VERT BOLT EMBEDMENT LENGTH	HORIZ BOLT EMBEDMENT LENGTH	HEADED STUD FILLET WELD SIZE, "S"
1/2"	7"	4"	1/4"
5/8"	7"	4"	5/16"
3/4"	7"	5"	5/16"
7/8"	8"	6"	5/16"
1"	9"	7"	3/8"
1 1/8"	10"	8"	---
1 1/4"	11"	9"	---




8 TYPICAL CAST-IN-PLACE ANCHOR, ANCHOR BOLT AND HEADED STUD SCHEDULE
SCALE: NTS



9 TYPICAL MASONRY WALL OPENING REINFORCING
SCALE: NTS



10 TYPICAL PIPE THROUGH FOUNDATION WALL AND TRENCH
SCALE: NTS



7 TYPICAL CONTROL JOINTS IN CONCRETE SLAB ON GRADE
SCALE: NTS




FINAL DESIGN
VERIFY SCALE
BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" = 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD DESIGN
WHITTIER, ALASKA
PROJECT No. 20403.14
TYPICAL DETAILS AND SCHEDULES


REVISION SCHEDULE		
NO.	DESCRIPTION	DATE

PROJECT NO. 20403.14
DATE 1/4/2022
DRAWN MEH
DESIGNED WS
REVIEWED NJC


SHEET NO. **S501**




1 MASONRY WALL AT CONCRETE FOOTING
SCALE: NTS




2 WALL OPENING AT CMU FOUNDATION
SCALE: NTS




3 MASONRY WALL AT CONCRETE FOOTING
SCALE: NTS




4 MASONRY WALL AT CONCRETE FOOTING
SCALE: NTS




5 WALL OPENING AT CMU FOUNDATION
SCALE: NTS




6 WOOD TRUSS AT MASONRY WALL
SCALE: NTS




7 WOOD TRUSS AT MASONRY WALL
SCALE: NTS




8 WOOD TRUSS AT MASONRY WALL
SCALE: NTS



9 WOOD TRUSS AT MASONRY WALL
SCALE: NTS



10 TYP MECH UNIT SUPPORT AT MASONRY WALL
SCALE: NTS



FINAL DESIGN
VERIFY SCALE
BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD DESIGN
WHITTIER, ALASKA
PROJECT No. 20403.14
STRUCTURAL DETAILS

REVISION SCHEDULE		
NO.	DESCRIPTION	DATE

PROJECT NO. 20403.14
DATE 1/4/2022
DRAWN MEH
DESIGNED WS
REVIEWED NJC

SHEET NO. **S502**

PIPING LEGEND				PIPING SYMBOL LEGEND (CONTINUED)				HVAC/DUCTWORK LEGEND				LOGIC LEGEND	
PROPOSED - - - - -	VENT	PROPOSED - - - - -	PROCESS PIPE		3-WAY MOTORIZED CONTROL VALVE		INSULATED DUCTWORK		SUPPLY AIR UP		CONNECTION POINT TO EXISTING		SHEET NOTE
	WASTE		NATURAL GAS		BALL VALVE / ISOLATION VALVE		VOLUME DAMPER		SUPPLY AIR DOWN		THERMOSTAT		SENSOR
PIPING SYMBOL LEGEND					CHECK VALVE		DUCTWORK SIZE (SIDE SHOWN/SIDE NOT SHOWN)		EXHAUST AIR UP		DETAIL NUMBER		SHEET LOCATED ON
	PIPE DOWN		ISO FLANGE		STRAINER		MOTORIZED CONTROL DAMPER		EXHAUST AIR DOWN				
	PIPE UP		CAP		PRESSURE GAUGE W/ ISOLATION VALVE								
	TEE DOWN		REDUCER		FLOOR DRAIN								
	TEE UP		CLEANOUT		PUMP								
	UNION		CONTINUATION		THERMOMETER								

ABBREVIATIONS

AFF	ABOVE FINISH FLOOR	DEG	DEGREE	FD-X	FLOOR DRAIN DESIGNATOR	MIN	MINIMUM	OAE	OR APPROVED EQUAL	UPC	UNIVERSAL PLUMBING CODE
AGA	AMERICAN GAS ASSOCIATION	DIA/Ø	DIAMETER	FT	FEET	N.C.	NORMALLY CLOSED	PH	PHASE	V	VENT
BTUH	BRITISH THERMAL UNIT/HOUR	DIP	DUCTILE IRON PIPE	G	NATURAL GAS	NEC	NATIONAL ELECTRICAL CODE	PSI	POUNDS PER SQUARE INCH	VOLTS	VOLTAGE
C/A	CUMBUSTION AIR	E/A	EXHAUST AIR	GUH-X	GAS UNIT HEATER DESIGNATOR	NO.	NUMBER	S/A	SUPPLY AIR	VTR	VENT THROUGH ROOF
CFH	CUBIC FEET PER HOUR	EAT	ENTERING AIR TEMPERATURE	HP	HORSEPOWER	N.O.	NORMALLY OPEN	SS	STAINLESS STEEL	W	WASTE
CFM	CUBIC FEET PER MINUTE	EH-X	ELECTRIC UNIT HEATER DESIGNATOR	KW	KILOWATT	NTS	NOT TO SCALE	TYP	TYP	WC	WATER COLUMN
DA	MOTORIZED CONTROL DAMPER	F	FAHRENHEIT	MAX	MAXIMUM	O/A	OUTSIDE AIR	UL	UNDERWRITERS LABORATORIES		

PLUMBING FIXTURE SCHEDULE

SYMBOL	MANUFACTURER	MODEL	MOUNTING	WASTE	REMARKS
FD-1	ZURN	Z415B	FLOOR	4	DURA-COATED CAST IRON BODY WITH SEEPAGE SLOTS AND ROUND HEAVY DUTY SLOTTED GRATE.

GAS FIRED UNIT HEATER SCHEDULE

SYMBOL	MANUFACTURER	MODEL	FUEL	INPUT (BTUH)	OUTPUT (BTUH)	EAT (DEG F)	CFM	HP	MOTOR DATA (VOLTS/PH)	MAX MOUNTING HEIGHT (FT)	REMARKS
GUH-1	MODINE	HDS30AS01	NATURAL GAS	30,000	24,600	50	505	1/15	115/1	10	CEILING MOUNTED, OSHA FAN GUARD.

ELECTRIC UNIT HEATER SCHEDULE

SYMBOL	MANUFACTURER	MODEL	CAPACITY (KW)	ELECTRICAL DATA (VOLTS/PH)	MAX MOUNTING HEIGHT (FT)	REMARKS
EH-1	MODINE	HER 75C 1201	7.5	240/1	8	CEILING MOUNTED ELECTRIC UNIT HEATER. PROVIDE WITH UNIT MOUNTED THERMOSTAT, THERMAL OVERLOAD PROTECTION, AND UL LISTED.

FAN SCHEDULE

SYMBOL	MANUFACTURER	MODEL	SERVICE	CAPACITY (CFM)	TOTAL STATIC PRESSURE (IN WC)	HP	MOTOR DATA (VOLTS/PH)	REMARKS
SF-1	GREENHECK	SS1-10-428-P	SUPPLY AIR	355	0.20	1/20	115/1	PROVIDE WITH WALL MOUNT, FACTORY MOUNTED DISCONNECT, FAN SPEED CONTROLLER, THERMAL OVERLOAD PROTECTION, UL LISTED AND AMCA CERTIFIED.

LOUVER SCHEDULE

SYMBOL	MANUFACTURER	MODEL	SERVICE	MATERIAL	FINISH	SIZE (IN)	REMARKS
L-1	RUSKIN	ELF6375DX	GENERATOR C/A	ALUMINUM	50% PVDF	64 W X 24 H	HORIZONTAL DRAINABLE BLADES AT 37.5 DEGREES, STAINLESS STEEL BEARINGS, AND WITH 3/4" BIRD SCREEN.

DEHUMIDIFIER SCHEDULE

SYMBOL	MANUFACTURER	MODEL	TYPE	CFM	ENTERING DRY BULB (DEG F)	ENTERING HUMIDITY	MOISTURE REMOVAL (LB/HR)	KW	ELECTRICAL DATA (VOLTS/PH)	DIMENSIONS (IN)	WEIGHT (LBS)	REMARKS
DH-1	QUEST DEHUMIDIFIERS	QUEST 70	SELF CONTAINED	150	80	60%	3.0	0.68	115/1	12 W X 21.5 L X 12 H	55	


TAG IDENTIFICATIONS

TAG	DEFINITION
FIT	FLOW INDICATOR TRANSMITTER
PCV	PRESSURE CONTROL VALVE
PIT	PRESSURE INDICATOR TRANSMITTER
PLC	PROGRAMMABLE LOGIC CONTROLLER
PT	PRESSURE TRANSMITTER
TT	TEMPERATURE TRANSMITTER
YYC	VALVE CLOSE REQUEST
ZS	POSITION CONTROL

TAG NUMBERS

TYPICAL: PCV314 - INSTRUMENT IDENTIFICATION OR TAG NUMBER
 FORMAT PCV - FUNCTIONAL IDENTIFICATION
 P - FIRST-LETTER
 CV - SUCCEEDING-LETTER(S)

FIRST LETTER ——— SUCCEEDING LETTERS



INSTRUMENT LOOP NUMBER ——— (INSTRUMENT SYMBOLS)

EXPANDED: PCV314 - TAG NUMBER
 FORMAT A - OPTIONAL SUFFIX



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD DESIGN
 WHITTIER, ALASKA
 PROJECT No. 20403.14

MECHANICAL LEGEND AND ABBREVIATIONS


REVISION SCHEDULE

#	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	BCA
DESIGNED	TLM
REVIEWED	TLM

SHEET NO.

M001



SHEET NOTES:

1. CAPPED 2 INCH HUB DRAIN.
2. 2 INCH WASTE UP FOR INDIRECT DRAIN.
3. DEHUMIDIFIER, DH-1, TO BE MOUNTED ON WALL. ROUTE CONDENSATE DRAIN TO NEAREST INDIRECT DRAIN. SEE 5/M501 FOR DETAIL.
4. LOUVER, L-1, TO BE HEAT TRACED. SEE 6/M501 FOR DETAIL.
5. 3/4 INCH DRAIN FROM GENERATOR E/A DUCT. ROUTE TO NEAREST FLOOR DRAIN. TERMINATE WITH 1 INCH AIR GAP. PROVIDE FABRICATED DIAMOND PLATE COVER OVER PIPING TO PROTECT DRAIN PIPING. BARE PIPING IS A TRIPPING HAZARD, SECURE COVER TO FLOOR.
6. PROVIDE WATER TIGHT DRIP PAN BELOW VENT PIPING OVER ELECTRICAL PANELS.
7. TERMINATE AT A 45 DEGREE ANGLE WITH WELDED BIRDSCREEN. FLASH AND SEAL WATERTIGHT.

HVAC SEQUENCE OF OPERATION

SPACE HEATING
 GAS-FIRED UNIT HEATER, GUH-1, SHALL CYCLE ON A CALL FOR HEAT FROM THE WALL MOUNTED THERMOSTAT (50 DEG F, ADJUSTABLE). ELECTRIC UNIT HEATER, EH-1, SHALL CYCLE ON CALL FOR HEAT FROM THE ADJUSTABLE INTEGRAL THERMOSTAT. EH-1 IS INTENDED TO SERVE AS BACK-UP HEAT SOURCE SHOULD GUH-1 FAIL TO MAINTAIN SPACE TEMPERATURE.

DEHUMIDIFICATION
 DEHUMIDIFIER, DH-1, SHALL OPERATE BASED ON CALL FOR DEHUMIDIFICATION FROM INTEGRAL HUMIDISTAT SET TO LOW.

VENTILATION
 SUPPLY FAN, SF-1, SHALL OPERATE BASED ON A CALL FOR VENTILATION FROM THE WALL MOUNTED THERMOSTAT (90 DEG F, ADJUSTABLE). WHEN SF-1 ENABLED, DA-1 AND DA-2 TO MODULATE TO FULL OPEN POSITION. WHEN SF-1 DISABLED, DA-1 AND DA-2 TO MODULATE TO FULL CLOSE POSITION.

GENERATOR VENTILATION
 MOTORIZED CONTROL DAMPER FOR L-1 TO BE INTERLOCKED WITH MOTORIZED INTAKE LOUVER ON GENERATOR ENCLOSURE. WHEN MOTORIZED INTAKE LOUVER ON GENERATOR ENCLOSURE OPENS, MOTORIZED CONTROL DAMPER FOR L-1 TO OPEN TO FULL OPEN POSITION. WHEN MOTORIZED INTAKE LOUVER ON GENERATOR ENCLOSURE CLOSES, MOTORIZED CONTROL DAMPER FOR L-1 TO CLOSE TO FULL CLOSE POSITION.



FINAL DESIGN
VERIFY SCALE
 BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD DESIGN
 WHITTIER, ALASKA
 PROJECT No. 20403.14
MECHANICAL FLOOR PLAN


REVISION SCHEDULE		
NO.	DESCRIPTION	DATE

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN BCA
 DESIGNED TLM
 REVIEWED TLM


SHEET NO. **M101**

PLOT DATE: 4/26/2022 4:45:31 PM


1 MECHANICAL FLOOR PLAN
 SCALE: 1/2" = 1'-0"




1 WELL A SECTION
 SCALE: 1/2" = 1'-0"



2 FUTURE WELL SECTION
 SCALE: 1/2" = 1'-0"



3 WELL B SECTION
 SCALE: 1/2" = 1'-0"



4 GENERATOR SECTION
 SCALE: 1/2" = 1'-0"



FINAL DESIGN
VERIFY SCALE
 BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY


WHITTIER WELL FIELD DESIGN
 WHITTIER, ALASKA
 PROJECT No. 20403.14
SECTION VIEWS

REVISION SCHEDULE		
NO.	DESCRIPTION	DATE


PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN BCA
 DESIGNED TLM
 REVIEWED TLM
 SHEET NO.

M301

PLOT DATE: 4/26/2022 4:45:32 PM



2 PIPING SCHEMATIC
SCALE: NTS



NOTES:
DRIP PANS FOR VENT
PIPING NOT SHOW
FOR CLARITY.

ALL NEW GAS PIPING
AND FITTINGS TO BE
SCHEDULE 40 BLACK
STEEL.

GAS METER SET AND SIZED BY ENSTAR UTILITY	
UPC 2018	TABLE 1215.2(1)
TOTAL CONNECTED LOAD	29.0 CFH
TOTAL DEVELOPED LENGTH	65 FT

1 GAS-FIRED UNIT HEATER AND GAS PIPING SCHEMATIC
SCALE: NTS



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD DESIGN
WHITTIER, ALASKA
PROJECT No. 20403.14

PIPING AND INSTRUMENTATION SCHEMATICS


REVISION SCHEDULE

#	DESCRIPTION	DATE


PROJECT NO. 20403.14
DATE DEC 2021
DRAWN BCA
DESIGNED TLM
REVIEWED TLM

SHEET NO.


M401




1 PIPE SUPPORT DETAIL
SCALE: NTS




2 THREADOLET TAP ASSEMBLY DETAIL
SCALE: NTS




3 PIPE DRAIN DETAIL
SCALE: NTS




4 FLOOR DRAIN DETAIL
SCALE: NTS




5 DEHUMIDIFIER
SCALE: NTS




6 LOUVER HEAT TRACE
SCALE: NTS



7 RELIEF HOOD DETAIL
SCALE: NTS



8 SUPPLY FAN DETAIL
SCALE: NTS



NOTES:
1. MANUFACTURED BY GTE INDUSTRIES OR APPROVED EQUAL.
2. VERIFY WALL THICKNESS PRIOR TO ORDERING.
3. EXHAUST THIMBLE SHALL BE STAINLESS STEEL.

9 EXHAUST THIMBLE
SCALE: NTS

REVISION SCHEDULE		
NO.	DESCRIPTION	DATE

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	BCA
DESIGNED	TLM
REVIEWED	TLM
SHEET NO.	

LEGEND


	BUS
	EXPOSED CONDUIT
	CONDUIT/CABLE RUN UNDERGROUND OR IN CONCRETE
	HOMERUN TO PANEL "X", CIRCUITS NO. Y AND Z CONDUIT RUNS NOT DEFINED ARE 1/2" C with 3#12.
	GROUND
	CONDUIT RUN - CHANGE IN ELEVATION
	GROUND ROD
	LIQUID-TIGHT FLEXIBLE CONDUIT
	MOTOR, HP AS SHOWN, SINGLE PHASE, "F" = FRACTIONAL
	SHEET NOTE "X"
	ELECTRICAL EQUIPMENT TAG "X"
	ELECTRICAL ENCLOSURE AS NOTED
	DISCONNECT SWITCH
	TRANSFORMER
	KILOWATT-HOUR METER
	125V DUPLEX GROUND FAULT INTERRUPT WEATHER PROOF RECEPTACLE, CONFIGURATION 5 - 20R
	GENERATOR
	TRANSFER SWITCH
	FLEX CONDUIT
	STARTER
	CURRENT TRANSFORMER

	MOTOR OVERLOAD
	FIELD MOUNTED INSTRUMENT XX = FUNCTION; YY = TAG NO.
	INSTRUMENT DEVICE LOCATION (SEE TAG)
	NORMALLY OPEN CONTACT
	NORMALLY CLOSED CONTACT
	PILOT LIGHT R=RED, B=BLUE, A=AMBER, G=GREEN, W=WHITE
	RELAY COIL
	TIME DELAY ENERGIZED RELAY CONTACTS NORMALLY CLOSED TIMED OPEN XXX= DESCRIPTION YYY=RELATED COIL & CONTACT #
	TIME DELAY ENERGIZED RELAY CONTACTS NORMALLY OPEN TIMED CLOSED XXX= DESCRIPTION YYY=RELATED COIL & CONTACT #
	TIME DELAY DE-ENERGIZED RELAY CONTACTS NORMALLY OPEN TIMED OPEN XXX= DESCRIPTION YYY=RELATED COIL & CONTACT #
	TIME DELAY DE-ENERGIZED RELAY CONTACTS NORMALLY CLOSED TIMED CLOSED XXX= DESCRIPTION YYY=RELATED COIL & CONTACT #
	FLOAT OPERATED SWITCH, NORMALLY CLOSED
	FLOAT OPERATED SWITCH, NORMALLY OPEN
	PUSHBUTTON NORMALLY CLOSED, MOMENTARY CONTACT
	PUSHBUTTON NORMALLY OPEN, MOMENTARY CONTACT
	MOTORIZED VALVE
	TEMPERATURE SWITCH, CLOSE ON RISE
	TEMPERATURE SWITCH, OPEN ON RISE

	JB-X-XX JUNCTION BOX OR FITTING
	CONDUIT TEE
	FUSE, X=SIZE IN AMPS
	MOLDED CASE CIRCUIT BREAKER, X = AMPERE RATING, Y = NO. OF POLES THERMAL/MAGNETIC UON
	CONTROL PANEL
	SINGLE POLE SWITCH 120/277V 20A
	SEAL-OFF FITTING
	PHOTO ELECTRIC CONTROL
	INSTRUMENT DEVICE LOCATION (SEE TAG)
	MUSHROOM HEAD, EMERGENCY PUSHBUTTON
	REMOTE OPERATOR FOR CONTROL PANEL
	PUSH TO TEST PILOT LIGHT X= LENS TINT
	TERMINAL - X = CONTRACTOR DERIVED NUMBERING
	STROBE ALARM
	HAND-OFF-AUTO SWITCH

ABBREVIATIONS

A	AMPERE
AFF	ABOVE FINISH FLOOR
AIC	AMPERES INTERRUPTING CAPACITY
ATS	AUTOMATIC TRANSFER SWITCH
BCU	BARE COPPER
C	CONDUCTOR
C	CONDUIT
C1D1	CLASS 1, DIVISION 1
C1D2	CLASS 1, DIVISION 2
CEA	CHUGACH ELECTRIC ASSOCIATION
COAX	COAXIAL CABLE
CP	CONTROL PANEL
CPP	CONTROL POWER PANEL
CT	CURRENT TRANSFORMER
CU	COPPER
DWG	DRAWING
EA	EACH
ESD	EMERGENCY SHUTDOWN
EXP	EXPLOSION PROOF
FD	FUSED DISCONNECT
FVNR	FULL VOLTAGE NON-REVERSING, THERMAL MAGNETIC OCP
G	GROUND CONDUCTOR
GFI	GROUND FAULT INTERRUPTING
H	HOT CONDUCTOR
HOA	HAND OFF AUTO
HP	HORSEPOWER
KVA	KILO-VOLT-AMPERES
KW	KILOWATT
LFMC	LIQUID-TIGHT FLEXIBLE METAL CONDUIT
LTG	LIGHTING
MAX	MAXIMUM
MCM	THOUSAND CIRCULAR MILLS
MCP	MAIN CONTROL PANEL
MIN	MINIMUM
MV	MOTORIZED VALVE
MS	MOTOR STARTER
MTS	MANUAL TRANSFER SWITCH
N	NEUTRAL CONDUCTOR
NEC	NATIONAL ELECTRICAL CODE
NEMA	NATIONAL ELECTRICAL MANUFACTURES ASSOCIATION
NTS	NOT TO SCALE
OCP	OVERCURRENT PROTECTION
P	POLE
PNL/MPZ	PANEL / MINI POWER ZONE
RCP	RECEPTACLE
RMC	RIGID METAL CONDUIT, GALVANIZED
SIG	SIGNAL CONDUCTOR
SL	SWITCH LEG
SPD	SURGE PROTECTION DEVICE
SS	STAINLESS STEEL
TDD	TIME DELAY DE-ENERGIZED
TDE	TIME DELAY ENERGIZED
TSP	TWISTED/SHIELDED PAIR
TWSH	TWISTED/SHIELDED CONDUCTOR
TYP	TYPICAL
U/G	UNDERGROUND
UON	UNLESS OTHERWISE NOTED
V	VOLTS
VA	VOLT-AMPERES
VAC	VOLTS AC POWER
VFD	VARIABLE FREQUENCY DRIVE
WP	WEATHER PROOF
XFMR	TRANSFORMER




FINAL DESIGN

VERIFY SCALE
BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY


WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
ELECTRICAL LEGEND

REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH
SHEET NO.	E001




1 **POWER ONE-LINE - INITIAL INSTALLATION AND GROUNDING PLAN**



CONSTRUCTION NOTE


A) DUE TO AVAILABLE POWER LIMITATIONS, UNTIL WELLS 2 AND 3 ARE REMOVED FROM SERVICE, WELL A AND WELL B CANNOT BE ENABLED AT THE SAME TIME.

B) SEE C101 FOR SITE PLAN



2 **GROUNDING PLAN**

- NOTES**
- ① VFD B TO BE DISABLED WHILE VFD A IS BEING COMMISSIONED OR IN USE. VFD A TO BE DISABLED WHILE VFD B IS BEING COMMISSIONED OR IN USE. THIS CONSTRAINT TO REMAIN UNTIL WELL 2 AND WELL 3 POWER LOADS ARE REMOVED. PROVIDE LOCKOUTS AND SIGNAGE.
 - ② 100 HP HEAVY DUTY VFD
 - ③ HIGH SPEED FUSE, BUSSMAN FWP-350A OR APPROVED EQUAL
 - ④ WIRED INTERNALLY BY MANUFACTURER
 - ⑤ #3 CU
 - ⑥ #4 CU
 - ⑦ #6 CU
 - ⑧ #8 CU
 - ⑨ #1 CU
 - ⑩ SPLICE NEW GROUND TO EXISTING GROUND
 - ⑪ #2 CU
 - ⑫ BOND ENCLOSURE PER NEC ART 250



FINAL DESIGN


VERIFY SCALE
 BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
POWER ONE-LINE - INITIAL INSTALLATION AND GROUNDING PLAN


REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN ILH
 DESIGNED ILH
 REVIEWED ILH

SHEET NO. **E002**



1 POWER ONE-LINE WELL 2 AND 3 DEMOLITION WITH REVISED WELL 1 POWER FEED



2 POWER ONE-LINE WITH WELL 1 POWER ONLINE, PRIOR TO WELL C (FUTURE) ONLINE


NOTES

- ① FOR IN-GROUND CONDUIT, REMOVE CABLES, INSTALL PULLSTRING, CAP CONDUIT
- ② DEMOLISH WELLHOUSES, IN GROUND JUNCTION BOXES, AND ELECTRICAL EQUIPMENT. SEE SHEETS C301, C302
- ③ PROVIDE LOCKOUTS AND SIGNAGE INDICATING THAT DUE TO POWER LIMITATIONS OF THE UTILITY TRANSFORMER, ONLY TWO WELLS CAN BE POWERED AT ANY GIVEN TIME. DO NOT POWER MORE THAN TWO PUMPS AT ANY GIVEN TIME UNTIL THE TRANSFORMER IS UPSIZED.

CONSTRUCTION NOTE

- A) DUE TO AVAILABLE POWER LIMITATIONS, ONLY TWO PUMPS CAN BE POWERED AT ANY GIVEN TIME.
- B) SEE C101 FOR SITE PLAN

TOTAL CONNECTED LOAD: 168KVA/204A AT 480VAC
 TOTAL DEMAND LOAD: 184KVA/221A AT 480VAC



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY


WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
POWER ONE-LINE - WELL 2, 3 DEMO AND WELL 1 POWER FEED RELOCATION

REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21


PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH

SHEET NO. **E003**

A B C D




2 **POWER ONE-LINE WITH WELL 1 DEMOLITION, PRIOR TO WELL C (FUTURE) ONLINE (NIC)**



1 **POWER ONE-LINE WITH WELL 1 POWER ONLINE, WELL C (FUTURE) INSTALLED (NIC)**

CONSTRUCTION NOTE
 A) DUE TO AVAILABLE POWER LIMITATIONS, ONLY TWO PUMPS CAN BE POWERED AT ANY GIVEN TIME.
 B) SEE C101 FOR SITE PLAN

- NOTES**
- ① FOR IN-GROUND CONDUIT, REMOVE CABLES, INSTALL PULLSTRING, CAP CONDUIT
 - ② DEMOLISH WELLHOUSES, IN GROUND JUNCTION BOXES, AND ELECTRICAL EQUIPMENT. SEE SHEETS C301, C302
 - ③ PROVIDE LOCKOUTS AND SIGNAGE INDICATING THAT DUE TO POWER LIMITATIONS OF THE UTILITY TRANSFORMER, ONLY TWO WELLS CAN BE POWERED AT ANY GIVEN TIME. DO NOT POWER MORE THAN TWO PUMPS AT ANY GIVEN TIME UNTIL THE TRANSFORMER IS UPSIZED.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
 PROJECT No. 20403.14

POWER ONE-LINE - WELL 1 DEMO AND WELL C POWER FEED (N.I.C.)

REVISION SCHEDULE


NO.	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN ILH
 DESIGNED ILH
 REVIEWED ILH

SHEET NO.

E004

PLOT DATE: 1/7/2022




1 ELECTRICAL AND CONTROLS FLOOR PLAN

SYMBOL	DESCRIPTION	MANUFACTURER	PART #	MOUNTING
[Symbol]	INSIDE LIGHTS	LITHONIA	FEM L48 4000LM LPPCL WD MVOLT GZ10 50K 90CRI	CEILING
[Symbol]	OUTSIDE LIGHTS	LITHONIA	TWP LED ALO 40K T3M MVOLT PE TP DBLBXD	WALL
[Symbol]	EMERGENCY/EXIT LIGHTS	LITHONIA	ECRG HO SQ M6	CEILING

2 LIGHTING SCHEDULE

NOTES

- ① PROVIDE THE FOLLOWING ALL MOUNTED TO THE POLE: SIGNAL LIGHTS, CLAXON, AND ANTENNA
- ② WELL C MAGMETER TO BE INSTALLED IN THE FUTURE. INSTALL FIT-103, RACEWAY AND CONDUCTORS TO ALLOW FOR EASE OF INSTALL OF WELL C MAGMETER IN THE FUTURE.
- ③ CONDUITS FOR GENERATOR STRIP HEATER, BATTERY CHARGER, JACKET WATER HEATER. LOCATION OF CONDUITS APPROXIMATE. COORDINATE LOCATIONS WITH ACTUAL GENERATOR DRAWINGS.
- ④ MOUNT TSH AT 6' AFF, AND TSL AT 3' AFF.
- ⑤ MOUNT XS-101 ON FLOOR BELOW FIT-102. PROVIDE BLACK PLACARD WITH WHITE TEXT ON WALL AT 3' AFF ABOVE XS-101 STATING "LEAK DETECTOR LOCATED BELOW"



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
ELECTRICAL AND INSTRUMENTATION FLOOR PLAN

REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH

SHEET NO.
E005

RACEWAY AND CONDUCTOR SCHEDULE - MANIFOLD BUILDING						
TAG	FROM	TO	RACEWAY	CONDUCTORS	TYPE	COMMENT
P-00	UTILITY TRANSFORMER	CT	3"	2 OF (3) 3/0	XHHW-2	TAP AT TRANSFORMER OR INSTALL SPLICE. SHOWN ON ONELINE.
P-01	CT	ATS VIA MAIN DISCONNECT	3"	2 OF (3) 3/0	XHHW-2	SHOWN ON ONELINE
P-02	GENERATOR	ATS	3"	2 OF (3) 3/0	XHHW-2	SHOWN ON ONELINE
P-03	ATS	POWER DIST BOX	3"	2 OF (3) 3/0	XHHW-2	SHOWN ON ONELINE
P-04	POWER DIST BOX	MINI POWER ZONE	1-1/4"	(3) #3, (1) #3 G	XHHW-2	SHOWN ON ONELINE
P-05	POWER DIST BOX	VFD WELL A DISCONNECT	2-1/2"	(3) 3/0, (1) #3 G	XHHW-2	SHOWN ON ONELINE
P-06	POWER DIST BOX	VFD WELL B DISCONNECT	2-1/2"	(3) 3/0, (1) #3 G	XHHW-2	SHOWN ON ONELINE
P-07	POWER DIST BOX	VFD WELL C DISCONNECT	2-1/2"	(3) 3/0, (1) #3 G	XHHW-2	SHOWN ON ONELINE
P-08	POWER DIST BOX	WELL 1 FUSED DISCONNECT	2"	(3) 3/0, (1) #1 G	XHHW-2	SHOWN ON ONELINE
P-09	MINI POWER ZONE	LIGHTS	3/4"	(2) #12, (1) #12 G	XHHW-2	
P-10	CPP-1	FLOWMETERS	3/4"	(2) #14, (1) #14 G	XHHW-2	
P-11	CPP-1	MCP-1	3/4"	(2) #14, (1) #14 G	XHHW-2	
P-12	VFD WELL A	WELL A PUMP	3"	(3) 2/0, (1) #3 G	VFD CABLE	SHOWN ON ONELINE, FIELD ROUTE WITH PIPE, INSTALL IN CONDUIT WHEN EXPOSED, DIRECT BURY WHEN IN GROUND, SEE TRENCH DETAIL
P-13	VFD WELL B	WELL B PUMP	3"	(3) 2/0, (1) #3 G	VFD CABLE	SHOWN ON ONELINE, FIELD ROUTE WITH PIPE, INSTALL IN CONDUIT WHEN EXPOSED, DIRECT BURY WHEN IN GROUND, SEE TRENCH DETAIL
P-14	VFD WELL C	WELL C PUMP	3"	(3) 3/0, (1) #3 G	VFD CABLE	SHOWN ON ONELINE, UPSIZED FOR VOLTAGE DROP, FIELD ROUTE WITH PIPE, INSTALL IN CONDUIT WHEN EXPOSED, DIRECT BURY WHEN IN GROUND, SEE TRENCH DETAIL
P-15	WELL 1 FUSED DISCONNECT	WELL 1	3"	(3) 3/0, (1) #1 G	XHHW-2	SHOWN ON ONELINE
P-16	MINI POWER ZONE	RECEPTS-MANIFOLD ROOM	3/4"	(2) #12, (1) #12 G	XHHW-2	NOT SHOWN ON FLOOR PLANS
P-17	MINI POWER ZONE	CPP-1	3/4"	(2) #12, (1) #12 G	XHHW-2	
P-18	MINI POWER ZONE	GENERATOR CONTROL PANEL	3/4"	(2) #12, (1) #12 G	XHHW-2	
P-19	MINI POWER ZONE	GENERATOR BATTERY CHARGER	3/4"	(2) #12, (1) #12 G	XHHW-2	
P-20	MINI POWER ZONE	GENERATOR STRIP HEATER	1"	(2) #10, (1) #10 G	XHHW-2	
P-21	MINI POWER ZONE	RECEPTS-GENERATOR ROOM	3/4"	(2) #12, (1) #12 G	XHHW-2	NOT SHOWN ON FLOOR PLANS
P-22	NOT USED					NOT USED
P-23	MINI POWER ZONE	GENERATOR JACKET WATER HTR	3/4"	(2) #12, (1) #12 G	XHHW-2	
P-24	MINI POWER ZONE	EH-1	3/4"	(2) #12, (1) #12 G	XHHW-2	
P-25	VFD WELL A DISCONNECT	VFD WELL A	2-1/2"	(3) 3/0, (1) #3 G	XHHW-2	SHOWN ON ONELINE
P-26	VFD WELL B DISCONNECT	VFD WELL B	2-1/2"	(3) 3/0, (1) #3 G	XHHW-2	SHOWN ON ONELINE
P-27	VFD WELL C DISCONNECT	VFD WELL C	2-1/2"	(3) 3/0, (1) #3 G	XHHW-2	SHOWN ON ONELINE
P-28	MINI POWER ZONE	GUH-1	3/4"	(2) #12, (1) #12 G	XHHW-2	
P-29	CPP-1	LEAK SWITCH (XS-101)	3/4"	(1) #14	XHHW-2	CAN BE COMBINED WITH CABLES FROM S-19
P-30	CPP-1	DH-1 RECEPT.	3/4"	(2) #12, (1) #12 G	XHHW-2	
P-31	MINI POWER ZONE	FAN	3/4"	(2) #12, (1) #12 G	XHHW-2	NOT SHOWN ON FLOORPLANS
P-32	MINI POWER ZONE	DAMPER ACTUATORS	3/4"	(2) #12, (1) #12 G	XHHW-2	



RACEWAY AND CONDUCTOR SCHEDULE - OFFICE BUILDING						
TAG	FROM	TO	RACEWAY	CONDUCTORS	TYPE	COMMENT
P-100	EXISTING ELECTRICAL PANEL	CPP-2	3/4"	(2) #12, (1) #12 G	XHHW-2	NOT SHOWN ON FLOOR PLANS
P-101	CPP-2	LEVEL CONTROL PANEL	3/4"	(2) #14, (1) #14 G	XHHW-2	NOT SHOWN ON FLOOR PLANS, (1) #14 SPARE
P-102	CPP-2	RCP-1	3/4"	(2) #14, (1) #14 G	XHHW-2	NOT SHOWN ON FLOOR PLANS

RACEWAY AND CONDUCTOR SCHEDULE - MANIFOLD BUILDING						
TAG	FROM	TO	RACEWAY	CONDUCTORS	TYPE	COMMENT
S-00	MCP-1	VFD WELL A	3/4"	(9) #14, (2) #16 TSP	XHHW-2	
S-01	MCP-1	FIT-101	3/4"	(3) #14, (1) #16 TSP	XHHW-2	
S-02	MCP-1	WELL A SALINITY, LEVEL AND PUMP OVERTEMP SENSORS	1"	(3) #16 TSP	XHHW-2 IN MC-HL	DIRECT BURY, FIELD ROUTE WITH PIPE, SEE TRENCH DETAIL
S-03	MCP-1	VFD WELL B	3/4"	(9) #14, (2) #16 TSP	XHHW-2	
S-04	MCP-1	FIT-102	3/4"	(3) #14, (1) #16 TSP	XHHW-2	
S-05	MCP-1	WELL B SALINITY, LEVEL AND PUMP OVERTEMP SENSORS	1"	(3) #16 TSP	XHHW-2 IN MC-HL	DIRECT BURY, FIELD ROUTE WITH PIPE, SEE TRENCH DETAIL
S-06	MCP-1	VFD WELL C	3/4"	(9) #14, (2) #16 TSP	XHHW-2	
S-07	MCP-1	FIT-103	3/4"	(3) #14, (1) #16 TSP	XHHW-2	
S-08	MCP-1	WELL B SALINITY, LEVEL AND PUMP OVERTEMP SENSORS	1"	(3) #16 TSP	XHHW-2 IN MC-HL	DIRECT BURY, FIELD ROUTE WITH PIPE, SEE TRENCH DETAIL
S-09	MCP-1	MODEM	3/4"	CAT6	TBD	
S-10	MCP-1	OUTSIDE BEACONS AND CLAXON	3/4"	(6) #14	XHHW-2	
S-11	MCP-1	IO ANTENNA	3/4"	COAX	TBD	PROCURE CABLE FROM WIRELESS IO VENDOR
S-12	MCP-1	PIT-100	3/4"	(1) #16 TSP	XHHW-2	
S-13	MCP-1	GENERATOR CONTROL PANEL	3/4"	(4) #14	XHHW-2	
S-14	GENERATOR CONTROL PANEL	ATS-1	3/4"	(2) #14	XHHW-2	WIRE ATS TWO WIRE START TO GENERATOR E25 AND E29
S-15	MODEM	INTERNET ANTENNA	3/4"	COAX	TBD	PROCURE FROM MODEM VENDOR
S-16	FIT-101	WELL A MAGMETER	N/A	ARMORED VENDOR CABLE	TBD	PROCURED WITH MAGMETER
S-17	FIT-102	WELL B MAGMETER	N/A	ARMORED VENDOR CABLE	TBD	PROCURED WITH MAGMETER
S-18	FIT-103	WELL C MAGMETER	N/A	ARMORED VENDOR CABLE	TBD	PROCURED WITH MAGMETER
S-19	MCP-1	LEAK SWITCH (XS-101)	3/4"	(3) #14	XHHW-2	CAN BE COMBINED WITH CABLES FROM P-29
S-20	MCP-1	TSH-101	3/4"	(2) #14	XHHW-2	
S-21	MCP-1	TSL-101	3/4"	(2) #14	XHHW-2	

RACEWAY AND CONDUCTOR SCHEDULE - OFFICE BUILDING						
TAG	FROM	TO	RACEWAY	CONDUCTORS	TYPE	COMMENT
S-100	RCP-1	LEVEL CONTROL PANEL	3/4"	(2) #14	XHHW	ONE SPARE, NOT SHOWN ON DRAWINGS
S-101	RCP-1	OFFICE ANTENNA	3/4"	COAX	TBD	PROCURE CABLE FROM WIRELESS IO VENDOR, NOT SHOWN ON DRAWINGS

25 KVA MINI POWER ZONE									
LOCATION: MANIFOLD BUILDING			120V/240V			2φ, 4 WIRE			18,000 AIC
SERVED FROM: ATS VIA POWER DISTRIBUTION BOX			100			NEMA 3R			
POLE #	AMP TRIP	LOAD DESCRIPTION	POLE KVA	MLO Aφ	POLE Bφ	KVA	LOAD DESCRIPTION	AMP TRIP	POLE #
1	15/1	LIGHTING	0.45	1.89		1.44	RECEPTACLES - MANIFOLD ROOM	15/1	2*
3	15/1	GUH - GAS FIRED UNIT HEATER	0.24		0.56	0.32	CPP-1	15/1	4
5*	20/1	HEAT TRACE FOR GENERATOR VENT	0.12	0.22		0.10	GENERATOR CONTROL PANEL	15/1	6
7			0.90		1.69	0.79	GENERATOR BATTERY CHARGER	20/1	8
9	20/2	GENERATOR JACKET WATER HEATER	0.90	4.03		3.13	GENERATOR STRIP HEATER	30/1	10
11*	15/1	RECEPTACLES - GENERATOR ROOM	1.26		1.29	0.03	DAMPER ACTUATORS AND TSTATS	20/1	12
13*		SPACE			0.76		DH-1 DEHUMIDIFIER	20/1	14*
15	20/3	EH-1 - 7.5 KW ELECTRIC UNIT HEATER	3.75		3.91	0.16	FAN	20/1	16
17			3.75		3.75				18
19					0.00				20
21					0.00				22
23					0.00				24
			10.64		7.46		Total kVA =	18.1 kVA	
							Total Amps @ 240V =	75.4 A	

* = GFCI Circuit Breaker



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

ELECTRICAL SCHEDULES AND RACEWAY

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN ILH
DESIGNED ILH
REVIEWED ILH

SHEET NO.

E006

1

2

3

PLOT DATE: 1/22/2024

A

B

C



D

1

2

3

PLOT DATE: 1/22/2024



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

WELL PUMP WIRING DETAIL

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH

SHEET NO.

E007

NOTES

- 1 PROVIDE TERMINAL BOX WITH TERMINALS AND DIVIDER TO SEPARATE SIGNAL CABLES AND TERMINAL BLOCKS (LEVEL SENSING, SALINITY SENSING, THERMAL OVERLOAD SENSING) FROM PUMP POWER CABLES. REFER TO TERMINAL BOX NOTES BELOW.
- 2 MOUNT TERMINAL BOX ON UNISTRUT MOUNTED TO WELL HEAD.

TERMINAL BOX NOTES


PROVIDE NEMA 4 OR 4X LOCKABLE TERMINAL BOX.

PROVIDE TERMINALS TO TERMINATE THE PUMP POWER CABLES, PUMP THERMAL OVERLOAD SWITCH CABLES, LEVEL SENSING CABLES, AND SALINITY SENSING CABLES

PROVIDE DIVIDER TO SEPARATE SENSOR CABLES AND POWER CABLES.

PROVIDE WARNING LABELING ON THE OUTSIDE INDICATING MIXED VOLTAGES PRESENT IN BOX, AND LABELING ON THE INSIDE INDICATING POWER AND SIGNAL SECTIONS.


CONTRACTOR TO NOTE THAT THE THERMAL OVERLOAD SENSING CONDUCTORS ARE BUNDLED WITH THE POWER CABLES IN THE MANUFACTURERS PUMP CABLE COMING FROM THE PUMP TO THE TERMINAL BOX AND ARE BUNDLED WITH THE SIGNAL CABLES FROM THE TERMINAL BOX TO MCP-1



NOTE

REFER TO SHEET C204 FOR ADDITIONAL WELL DETAILS

1 WELL PUMP WIRING DETAIL, TYPICAL
SCALE: NTS




WELL A RUNNING BEACON - AMBER
 WELL B RUNNING BEACON - AMBER
 WELL C RUNNING BEACON - AMBER
 ALARM BEACON - RED
 ALARM CLAXON

900 MHZ RADIO CONNECTION
 USE ONE SET OF 16 PAIR CABLE FROM EXISTING THREE PAIRS

- CITY OFFICE NOTES**
- 1) FIELD LOCATE CPP-2 NEAR RCP-1
 - 2) FIELD LOCATE RCP-1 IN COORDINATION WITH OWNER.
 - 3) FIELD LOCATE 900 MHZ ANTENNA

NOTES

- 1) PANEL SHALL BE UL508A LISTED
- 2) PROVIDE THE FOLLOWING PLACARDS ON THE OUTSIDE OF THE PANEL: IDENTIFIER, TROUBLESHOOTING MATRIX, WHAT PROVIDES POWER TO THE PANEL.
- 3) PROVIDE THE FOLLOWING ADDITIONAL PLACARDS ON MCP-1 AND RCP-1: "CAUTION: THIS EQUIPMENT IS POWERED BY MULTIPLE SOURCES"
- 4) PROVIDE THE FOLLOWING LAMINATED LABEL ON CPP-1 AND -2: "REPLACE BATTERY EVERY 3 YEARS", "BATTERY LAST REPLACED: "
- 5) DATA RECORDER MAY BE LOCATED AS PART OF MCP-1 OR IN A STAND ALONE ENCLOSURE
- 6) GENERATOR AND SKID-MOUNTED CONTROL PANEL FURNISHED BY OWNER, INSTALLED AND WIRED BY CONTRACTOR
- 7) "BYPASS PRESSURE SWITCH" LOCATED ON PANEL BACKPLANE INSIDE CONTROL PANEL.
- 8) PROVIDE LAMINATED FULL SCALE PHOTO OF CONTROL PANEL FRONT MOUNTED ON WALL NEXT TO CONTROL PANEL WITH BRIEF SUMMARY OF SWITCH, LIGHTS, AND INDICATOR MEANING AND USE. REFER TO SPECIFICATION 409513 FOR MORE DETAILS.



FINAL DESIGN

VERIFY SCALE
 BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14

CONTROLS SYSTEM DESIGN

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN ILH
DESIGNED ILH
REVIEWED ILH

SHEET NO. 1001

WHITTIER CONTROL NARRATIVE

THE CONTROL NARRATIVE BELOW OUTLINES HOW WELLS A, B AND C (FUTURE) WILL OPERATE. WELL 1 FUNCTIONALITY IS NOT CHANGED BY THIS PROJECT. REFER TO ELECTRICAL ONELINE FOR POWER FEED CHANGES FOR WELL 1.

LOCATIONS AND IO

THERE ARE THREE LOCATIONS THAT ARE INVOLVED WITH THIS NARRATIVE: RESERVOIR, CITY OFFICE, AND THE MANIFOLD BUILDING

- WATER RESERVOIR:
 - MEASUREMENTS
 - WATER LEVEL (NEW)
 - WATER LEVEL (EXISTING, UNAFFECTED BY THIS PROJECT)
- CITY OFFICE
 - OUTPUTS:
 - WELLS 1, 2, AND 3 HOA (EXISTING)
 - WELLS A, B, AND C (FUTURE) HOA
 - RESERVOIR WATER LEVEL (TO MANIFOLD BUILDING)
 - INPUTS:
 - WELLS 1, 2, AND 3 "READY" AND "FAIL" STATUS LIGHTS (EXISTING)
 - WELLS A, B, AND C (FUTURE)
 - i) "READY"
 - ii) "ALARM"
 - iii) "RUNNING"
 - iv) PUMP FLOW
 - v) AQUIFER LEVEL
 - SYSTEM PRESSURE
 - RESERVOIR TANK WATER LEVEL (FROM RESERVOIR TANK) (EXISTING)
 - RADIO SIGNAL
 - CONNECTION TO MANIFOLD BUILDING
- MANIFOLD BUILDING
 - MEASUREMENTS
 - WELLS A, B, AND C (FUTURE)
 - i) FLOW
 - ii) SALINITY
 - iii) LEVEL
 - iv) VFD ALARM
 - v) VFD RUNNING
 - SYSTEM PRESSURE
 - GENERATOR
 - i) MINOR ALARM
 - ii) FAIL
 - iii) RUNNING
 - CONTROLS
 - WELLS A, B, AND C (FUTURE)
 - i) HOA (VIA HANDSWITCH)
 - ii) MAX FLOWRATE (VIA VFD PARAMETERS)
 - iii) MIN FLOWRATE (VIA VFD PARAMETERS)
 - MAX FLOW MOMENTARY PUSHBUTTON (ALL WELLS)
 - OUTPUTS:
 - WELLS A, B, AND C (FUTURE)
 - i) "READY"
 - ii) "ALARM"
 - iii) "RUNNING"
 - iv) AQUIFER LEVEL
 - SYSTEM PRESSURE
 - BUILDING LOW TEMPERATURE
 - BUILDING HIGH TEMPERATURE
 - LEAK ALARM
 - INPUTS:
 - WELLS A, B, AND C (FUTURE) HOA FROM CITY OFFICE
 - RESERVOIR LEVEL
 - RADIO SIGNAL
 - CONNECTION TO CITY OFFICE

- WELL A LEVEL
- WELL A SALINITY
- WELL A VFD SPEED
- WELL A FLOW
- WELL A RUNTIME (CALCULATED)
- WELL B LEVEL
- WELL B SALINITY
- WELL B VFD SPEED
- WELL B FLOW
- WELL B RUNTIME (CALCULATED)
- WELL C LEVEL
- WELL C SALINITY
- WELL C VFD SPEED
- WELL C FLOW
- WELL C RUNTIME (CALCULATED)
- TOTAL FLOW (CALCULATED)
- TANK LEVEL
- SYSTEM PRESSURE
- RCP-1 COMMUNICATION OK
- GENERATOR RUNNING
- LEAD DEMAND
- LAG DEMAND

3

DATA RECORDER DR-1 DATA POINTS

WELL	MIN GPM	DESIGN GPM	MAX GPM
A	TBD	750	850
B	TBD	500	700
C	TBD	TBD	TBD

	LOW LOW SETPOINT	LOW SETPOINT	HIGH SETPOINT	HIGH HIGH SETPOINT
SYSTEM PRESSURE	70 PSI	80 PSI	95 PSI	110 PSI
TANK LEVEL	75%	85%	98%	N/A
SALINITY	N/A	N/A	800 US/CM	N/A

NOTE


- 1) VFDS WILL RUN AT MAX GPM ONLY WHEN "MAX FLOW OVERRIDE" PUSHBUTTON IS PUSHED.
- 2) VFDS WILL RUN AT MAX GPM ONLY FOR 6 HRS, AFTER WHICH THE VFD WILL NOT RUN AT FOR 18 HRS
- 3) VFDS WILL BE NORMALLY SET AT DESIGN GPM FLOW RATES, AND BE SIZED TO BE ABLE TO BE RUN AT THAT GPM INDEFINITELY.
- 4) WELL GPM SETPOINTS ADJUSTABLE THROUGH THE VFD HMI AS PARAMETER VALUES.
- 5) SYSTEM PRESSURE SETPOINTS ADJUSTABLE THROUGH DIP SWITCHES ON THE LIMIT ALARM RELAY.
- 6) TANK LEVEL SETPOINTS ADJUSTABLE THROUGH DIP SWITCHES ON THE LIMIT ALARM RELAY.

2

SETPOINT TABLES

1

CONTROLS NARRATIVE - LOCATIONS AND IO



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

CONTROLS NARRATIVE

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN ILH
 DESIGNED ILH
 REVIEWED ILH

SHEET NO.

1101


WHITTIER CONTROL NARRATIVE (CONTINUED)

CONTROL SEQUENCE

- THE WELLS ENABLE WHEN THERE IS DEMAND.
 - WHEN SYSTEM PRESSURE IS AT THE LOW SETPOINT, THERE IS A DEMAND FOR THE LEAD PUMP
 - PRESSURE BECOMES LOW DUE TO LOW WATER RESERVOIR AND/OR EXCESSIVE WATER USAGE
 - LOW WATER RESERVOIR LEVEL ALARM FROM THE CITY OFFICE ALSO ENABLES THE DEMAND
 - WHEN SYSTEM PRESSURE IS AT THE LOW LOW SETPOINT, THERE IS A DEMAND FOR THE LAG PUMP
 - LOW LOW WATER RESERVOIR LEVEL ALARM FROM THE OFFICE BUILDING ALSO ENABLES THE DEMAND
- THE WELLS DISABLE WHEN THE DEMAND IS GONE.
 - WHEN SYSTEM PRESSURE IS AT THE HIGH SETPOINT, THE DEMAND IS REMOVED.
 - HIGH WATER RESERVOIR LEVEL ALARM FROM THE OFFICE BUILDING ALSO REMOVES THE DEMAND.
- IN THE EVENT THERE IS A CONFLICT:
 - SYSTEM HIGH PRESSURE WILL OVERRIDE WATER RESERVOIR LOW AND LOW LOW SIGNAL
 - SYSTEM HIGH PRESSURE WILL OVERRIDE VFD IN HAND POSITION
 - SYSTEM LOW PRESSURE WILL OVERRIDE TANK HIGH LEVEL
- WELLS A/B/C ROTATE LEAD/LAG/LAG2
- WHEN A WELL IS IN DEMAND, THE LEAD WELL VFD RAMPS UP TO IDEAL FLOW.
- LAG IS IN DEMAND WHEN THE LEAD PUMP RUNS ALONE FOR 5 HOURS, PRESSURE LOW LOW OCCURS, OR TANK LEVEL LOW LOW OCCURS.
- LAG 2 IS IN DEMAND WHEN THE LAG PUMP HAS BEEN RUNNING FOR 5 HOURS
- WHEN THE WELL IS NO LONGER IN DEMAND, THE VFD RAMPS DOWN TO STOP.
- HAND-OFF-AUTO SWITCHES MANUALLY TURN ON OR DISABLE THE VFD. WHEN MANUALLY TURNED ON THE ASSOCIATED WELL WILL BE CONTINUOUSLY IN DEMAND.
- THE RESTRICT TO ONE PUMP SWITCH WILL DISABLE THE LAG AND LAG 2 PUMP FUNCTIONALITY, AND THERE WILL NEVER BE DEMAND OF LAG OR LAG 2.
- WELL LEVELS WILL BE RECORDED CONTINUOUSLY.
- WHEN THE MAX FLOW OVERRIDE PUSHBUTTON IS PRESSED, THE LEAD, LAG, AND LAG2 PUMP ALL PUMP FOR 6 HOURS AT THE PRESET MAXIMUM FLOW RATE. TO PREVENT DAMAGE TO THE AQUIFER, THE PUMPS WILL BE DISABLED FOR 18 HOURS AFTER THE 6 HOURS OF MAXIMUM FLOW.
- WHEN THE BYPASS HIGH PRESSURE DISABLE SWITCH IS ENABLED, THE HIGH PRESSURE ALARM IS DISABLED.
- DUE TO THE HAND-OFF-AUTO SWITCHES EXISTING AT BOTH THE MANIFOLD BUILDING AND THE WATER OFFICE FOR THE WELL VFDS, THERE IS A POTENTIAL FOR A CONFLICT OF COMMAND. BELOW IS WHAT WILL OCCUR BASED ON THE SWITCH POSITIONS:

CITY OFFICE	MANIFOLD BUILDING	VFD STATUS
HAND	OFF	DISABLED
HAND	HAND	ENABLED, RUNNING
HAND	AUTO	ENABLED, RUNNING
OFF	OFF	DISABLED
OFF	HAND	DISABLED
OFF	AUTO	DISABLED
AUTO	OFF	DISABLED
AUTO	HAND	ENABLED, RUNNING
AUTO	AUTO	FUNCTION PER CONTROL NARRATIVE

- IN THE EVENT OF A COMMUNICATION LOSS TO THE MANIFOLD BUILDING THE WIRELESS I/O DEVICE WILL RECOGNIZE LOSS OF SIGNAL AND THE FOLLOWING WILL OCCUR:
 - PUMPING WILL CONTINUE TO FUNCTION NORMALLY BASED SOLELY OFF SYSTEM PRESSURE
 - AN OVERRIDE WILL OCCUR REGARDING THE RCP-1 HOA SWITCH POSITIONS. MCP-1 WILL REGARDING THE RCP-1 HOA SWITCH POSITIONS. MCP-1 WILL FUNCTION AS IF ALL RCP-1 HOA SWITCHES ARE IN THE AUTO POSITION.
 - UPON REESTABLISHMENT OF COMMUNICATION, CONTROLS WILL RETURN TO NORMAL.



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
 PROJECT No. 20403.14

CONTROLS NARRATIVE CONTINUED

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN ILH
 DESIGNED ILH
 REVIEWED ILH

SHEET NO.

1102

A

B

C





D

1

2

3

PLOT DATE: 11/22/2024



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING

0" 1"

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
 PROJECT No. 20403.14


MANIFOLD BUILDING CONTROLS
CPP-1 WIRING AND MCP-1 MAIN LOGIC

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN ILH
 DESIGNED ILH
 REVIEWED ILH

SHEET NO. **1601**



FINAL DESIGN

VERIFY SCALE
 BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14

MANIFOLD BUILDING CONTROLS
 MCP-1 HOA AND LIGHTS


REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN ILH
 DESIGNED ILH
 REVIEWED ILH

SHEET NO. **1602**

PLOT DATE: 1/22/2024



FINAL DESIGN

VERIFY SCALE
BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14

MANIFOLD BUILDING CONTROLS
MCP-1 LIGHTS, CONTACTS, CLAXON


REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21


PROJECT NO. 20403.14
DATE DEC 2021
DRAWN ILH
DESIGNED ILH
REVIEWED ILH

SHEET NO. **1603**

PLOT DATE: 12/22/2024



WIRING LEGEND
 ——— WIRING INTERNAL TO PANEL
 - - - - WIRING EXTERNAL TO PANEL
 - - - - EXTERNAL DEVICE ENCLOSURE



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
MANIFOLD BUILDING CONTACTS
MCP-1 ENABLE VFD LOGIC

REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH

SHEET NO.
1604


PLOT DATE: 1/7/2022

A

B

C

D




WIRING LEGEND

—— WIRING INTERNAL TO PANEL

----- WIRING EXTERNAL TO PANEL

- - - - EXTERNAL DEVICE ENCLOSURE



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
MANIFOLD BUILDING CONTROLS
MCP-1 DIGITAL RADIO CONNECTION

REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH

SHEET NO.
1605

PLOT DATE: 1/7/2022







A

B

C

D


+24VDC BUS
+24VDC BUS



WIO-1
WIRELESS I/O
TO/ FROM RCP-1 VIA RADIO

WIRING LEGEND

- WIRING INTERNAL TO PANEL
- - - WIRING EXTERNAL TO PANEL
- - - EXTERNAL DEVICE ENCLOSURE



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
MANIFOLD BUILDING CONTROLS
MCP-1 ANALOG RADIO CONNECTION

REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN ILH
DESIGNED ILH
REVIEWED ILH

SHEET NO.
1606



PLOT DATE: 1/7/2022

A

B

C

D



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1" IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
MANIFOLD BUILDING CONTROLS
MCP-1 SALINITY, FLOW REPEATERS

REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH


SHEET NO. 1607

1

2

3

PLOT DATE: 1/7/2022



WIRING LEGEND

- WIRING INTERNAL TO PANEL
- - - - - WIRING EXTERNAL TO PANEL
- - - - - EXTERNAL DEVICE ENCLOSURE

NOTES

1) MOUNT SWITCH INSIDE THE CONTROL PANEL ON THE BACKPLANE

A

B

C


D

1

2


3

PLOT DATE: 1/22/2024



WIRING LEGEND

- WIRING INTERNAL TO PANEL
- WIRING EXTERNAL TO PANEL
- - - EXTERNAL DEVICE ENCLOSURE



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY






WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
MANIFOLD BUILDING CONTROLS
MCP-1 VFD WIRING

REVISION SCHEDULE


#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN ILH
 DESIGNED ILH
 REVIEWED ILH

SHEET NO.
1608



DR-1



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14

MANIFOLD BUILDING CONTROLS
MCP-1 DATA RECORDER, FIT WIRING

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH

SHEET NO.
1609

1
2
3

A

B

C

D

R3-1	LEAD IN DEMAND	B	TO R3-4/5/6
		C	TO DR-1
R3-2	LAG IN DEMAND	A	LATCH
		B	TO R3-4/5/6
		C	TO DR-1
R3-3	TURN OFF PUMPS	A	TO R3-1
		B	TO R3-2
R3-4	DEMAND FOR VFD A	A	TO R3-47
		B	NOT USED
R3-5	DEMAND FOR VFD B	A	TO R3-48
		B	NOT USED
R3-6	DEMAND FOR VFD C	A	TO R3-49
		B	NOT USED
R3-7	VFD A, B, C, MAX SPEED DEMAND	A	TO VFD A
		B	TO VFD B
		C	TO VFD C
R3-8	VFD A, B, C, DESIGN SPEED DEMAND	A	TO VFD A
		B	TO VFD B
		C	TO VFD C
R3-9	MAX SPEED DEMAND OVERRIDE	A	TO R3-1
		B	TO R3-2
R3-10	RCP-1 VFD A HAND	A	LIGHT
		B	TO R3-47
R3-11	RCP-1 VFD A OFF	A	LIGHT
		B	TO R3-47
R3-12	RCP-1 VFD A AUTO	A	LIGHT
		B	TO R3-47
R3-13	RCP-1 VFD B HAND	A	LIGHT
		B	TO R3-47
R3-14	RCP-1 VFD B OFF	A	LIGHT
		B	TO R3-48
R3-15	RCP-1 VFD B AUTO	A	LIGHT
		B	TO R3-48
R3-16	RCP-1 VFD C HAND	A	LIGHT
		B	TO R3-49
R3-17	RCP-1 VFD C OFF	A	LIGHT
		B	TO R3-49
R3-18	RCP-1 VFD C AUTO	A	LIGHT
		B	TO R3-49
R3-19	LEAK DETECTION SWITCH XS-101	A	LIGHT
		B	TO RADIO DI2
		C	TO DR-1
R3-20	TANK HIGH	A	LIGHT
		B	TO R3-3
R3-21	TANK LOW	A	LIGHT
		B	TO R3-1
R3-22	TANK LOW LOW	A	LIGHT
		B	TO R3-2
R3-23	GENERATOR RUNNING	A	LIGHT
		B	TO DR-1
R3-24	GENERATOR FAIL	A	LIGHT
		B	TO R3-53
R3-25	GENERATOR MINOR ALARM	A	LIGHT
		B	TO RADIO DI1
R3-26	VFD A IN ALARM	B	LIGHT
		C	TO R3-53
R3-27	VFD A RUNNING	A	TO RADIO DI4
		B	LIGHT
		C	EXTERNAL LIGHT
R3-28	VFD B IN ALARM	A	TO RADIO DI2
		B	LIGHT
		C	TO R3-53
R3-29	VFD B RUNNING	A	TO RADIO DI5
		B	LIGHT
		C	EXTERNAL LIGHT
R3-30	VFD C IN ALARM	A	TO RADIO DI3
		B	LIGHT
		C	TO R3-53
R3-31	VFD C RUNNING	A	TO RADIO DI6
		B	LIGHT
		C	EXTERNAL LIGHT
R3-32	MCP-1 VFD A HAND	A	NOT USED
		B	TO R3-47
R3-33	MCP-1 VFD A AUTO	A	NOT USED
		B	TO R3-47
R3-34	MCP-1 VFD B HAND	A	NOT USED
		B	TO R3-48
R3-35	MCP-1 VFD B AUTO	A	NOT USED
		B	TO R3-48
R3-36	MCP-1 VFD C HAND	A	NOT USED
		B	TO R3-49
R3-37	MCP-1 VFD C AUTO	A	NOT USED
		B	TO R3-49
R3-38	VFD A READY	A	TO RADIO DI7
		B	LIGHT
R3-39	VFD B READY	A	TO RADIO DI8
		B	LIGHT
R3-40	VFD C READY	A	TO RADIO DI9
		B	LIGHT
R3-41	WELL A SALINITY ALARM	A	LIGHT
R3-42	WELL B SALINITY ALARM	A	LIGHT
R3-43	WELL C SALINITY ALARM	A	LIGHT
R3-44	PRESSURE HIGH HIGH TO LIGHTS AND ALARM	A	LIGHT
		B	NOT USED
		C	TO R3-53
		A	LIGHT
R3-45	PRESSURE LOW	B	TO R3-1
		-	-

R3-46	PRESSURE LOW LOW	C	TO R3-3
		A	LIGHT
R3-47	ENABLE VFD A	B	TO R3-2
		C	TO R3-53
R3-48	ENABLE VFD B	A	TO VFD A ENABLE
		B	NOT USED
R3-49	ENABLE VFD C	A	TO VFD B ENABLE
		B	NOT USED
R3-50	MCP-1 VFD A OFF	A	TO VFD C ENABLE
		B	NOT USED
R3-51	MCP-1 VFD B OFF	A	TO R3-47
		B	NOT USED
R3-52	MCP-1 VFD C OFF	A	TO R3-48
		B	NOT USED
R3-53	MCP-1 IN ALARM	A	TO R3-49
		B	NOT USED
R3-54	WELL PUMP A OVER TEMPERATURE ALARM	A	EXTERNAL LIGHT
		B	CLAXON
		C	LIGHT
R3-55	WELL PUMP B OVER TEMPERATURE ALARM	A	LIGHT
		B	LATCH
		C	VFD A
R3-56	WELL PUMP C OVER TEMPERATURE ALARM	A	LIGHT
		B	LATCH
		C	VFD B
R4-1	MCP-1 TO RCP-1 LINK OK	A	LIGHT
		B	LATCH
		C	VFD C
R4-2	MCP-1 TO RCP-1 LINK OK	A	TO R3-47
		B	TO R3-48
		C	TO R3-49
		D	LIGHT
R4-3	PRESSURE HIGH DISABLE VFDS	A	TO R3-47
		B	TO R3-48
		C	TO R3-49
		D	TO DR-1
R4-4	TSL-1 LOW TEMP SWITCH	A	TO VFD A ENABLE
		B	TO VFD B ENABLE
		C	TO VFD C ENABLE
		D	TO R3-3
R4-5	TSH-1 HIGH TEMP SWITCH	A	R3-53
		B	LIGHT
		C	TO RADIO DI11
		D	TO DR-1
TDD-1	MAX SPEED DEMAND OVERRIDE	NO	TO R3-7, 9
		NC	TO R3-8, TDR0-2
TDE-2	POST MAX SPEED USE DELAY	NO	6 HR DELAY OFF
TDE-3	LEAD RUNNING ALONE DELAY	NO	TO R3-1, 2
		NO	18 HR DELAY OFF
TDE-4	LAG2 ENABLE DELAY	NO	TO R3-2
		NO	5 HR DELAY ON
		NO	AR-1 LAG 2
		NO	5 HR DELAY ON

IF	REASONS	HOW TO CHECK	HOW TO FIX
PUMPS DO NOT RUN WHEN TANK IS LOW	SYSTEM PRESSURE IS HIGH	CHECK PRESSURE READING	N/A - WORKING PROPERLY
	RCP-1 TO MCP-1 COMMUNICATION FAILED	CHECK IF RCP-1 COMM OK LIGHT IS ON	IF LIGHT IS OFF, REFER TO "MCP-1 ALARMS", ITEM "RCP-1 COMM OK"
	HOA IS IN OFF	CHECK HOA POSITIONS	CHECK WITH SUPERVISOR THEN TURN TO AUTO
	VFD HMI IS IN OFF	CHECK VFD HMI	CHECK VFD MANUAL
PUMPS DO NOT TURN OFF WHEN TANK IS HIGH	VFD IS FAULTED	CHECK VFD ALARM LIGHT AND/OR VFD HMI	CHECK VFD MANUAL
	NO POWER TO THE VFD	CHECK IF VFD HMI LCD IS LIT	CLOSE DISCONNECT AND/OR REPLACE FUSES IN DISCONNECT
	RELAY OR DEVICE FAILED	CHECK THE RELAYS/DEVICES	CHECK ITEMS ABOVE THEN PROCEED TO THE FOLLOWING STEPS. 1) CHECK IF RELAY R3-1 IS LIT AND HAS POWER. IF THERE IS POWER AND IS NOT LIT, REPLACE RELAY. IF THERE IS NO POWER, GO TO 2. IF IT IS LIT, GO TO STEP 4. 2) CHECK IF RELAY R3-21 IS LIT AND HAS POWER. IF THERE IS POWER AND IS NOT LIT, REPLACE RELAY. IF THERE IS NO POWER, GO TO 3. 3) CHECK LOCAL INDICATOR FOR THE TANK LEVEL. IF THE INDICATOR IS CORRECT, REPLACE LAM-1 LIMIT ALARM MODULE. IF THE INDICATOR IS INCORRECT, REPLACE REP-11 TANK LEVEL. 4) CHECK IF RELAY R3-4, 5, OR 6 ARE LIT. IF NONE ARE LIT, REPLACE AR-1 (ALTERNATING RELAY). IF ONE IS LIT, GO TO THE FOLLOWING: R3-4 STEP 5A, R3-5 STEP 5B, R3-6 STEP 5C. 5A) CHECK IF RELAYS R3-12, 33 ARE LIT AND HAS POWER. IF THERE IS POWER AND IS NOT LIT, REPLACE RELAY. 5B) CHECK IF RELAYS R3-15, 35 ARE LIT AND HAS POWER. IF THERE IS POWER AND IS NOT LIT, REPLACE RELAY. 5C) CHECK IF RELAYS R3-18, 37 ARE LIT AND HAS POWER. IF THERE IS POWER AND IS NOT LIT, REPLACE RELAY.
	RELAY OR DEVICE FAILED	CHECK THE RELAYS/DEVICES	CHECK ITEMS ABOVE THEN PROCEED TO THE FOLLOWING STEPS. 1) CHECK IF RELAY R3-20 IS LIT AND HAS POWER. IF THERE IS POWER AND IS NOT LIT, REPLACE RELAY. IF THERE IS NO POWER, GO TO 2. IF IT IS LIT, REPLACE RELAY R3-3. 2) CHECK IF LOCAL INDICATOR LI-11 TANK LEVEL IS READING CORRECTLY. IF IT DOES, REPLACE LAM-1 TANK ALARMS. IF NOT, REPLACE REP-11 TANK LEVEL.
PUMPS DO NOT RUN WHEN PRESSURE IS LOW	SYSTEM PRESSURE IS LOW	CHECK PRESSURE READING	N/A - WORKING PROPERLY
	RCP-1 TO MCP-1 COMMUNICATION FAILED	CHECK IF RCP-1 COMM OK LIGHT IS ON	IF LIGHT IS OFF, REFER TO "MCP-1 ALARMS", ITEM "RCP-1 COMM OK"
	HOA IS IN HAND	CHECK HOA POSITIONS	CHECK WITH SUPERVISOR THEN TURN TO AUTO
	VFD HMI IS IN MANUAL	CHECK VFD HMI	CHECK VFD MANUAL
PUMPS DO NOT TURN OFF WHEN PRESSURE IS HIGH	RELAY OR DEVICE FAILED	CHECK THE RELAYS/DEVICES	CHECK ITEMS ABOVE THEN PROCEED TO THE FOLLOWING STEPS. 1) CHECK IF PT-1 SYSTEM PRESSURE TRANSMITTER DISPLAY INDICATES LOW PRESSURE. IF IT DOES NOT, REPLACE PT-1. IF IT DOES, GO TO STEP 2. 2) CHECK IF LOCAL INDICATOR LI-4 SYSTEM PRESSURE IS READING CORRECTLY. IF NOT, REPLACE REP-4A SYSTEM PRESSURE. IF IT DOES, GO TO STEP 3. 3) CHECK IF RELAY R3-45 IS LIT AND HAS POWER. IF IT HAS POWER BUT IS NOT LIT, REPLACE RELAY. IF THERE IS NO POWER REPLACE LAM-2B LOW PRESSURE ALARMS.
	HOA IS IN OFF	CHECK HOA POSITIONS	CHECK WITH SUPERVISOR THEN TURN TO AUTO
	VFD HMI IS IN OFF	CHECK VFD HMI	CHECK VFD MANUAL
	VFD IS FAULTED	CHECK VFD ALARM LIGHT AND/OR VFD HMI	CHECK VFD MANUAL
ALARM BEACON AND CLAXON ARE ON	NO POWER TO THE VFD	CHECK IF VFD HMI LCD IS LIT	CLOSE DISCONNECT AND/OR REPLACE FUSES IN DISCONNECT
	PUMP HAS OVERHEATED	CHECK IF WELL OVERTEMP LIGHT	PRESS "PUMP OVERTEMPERATURE RESET" BUTTON
	RELAY OR DEVICE FAILED	CHECK THE RELAYS/DEVICES	CHECK ITEMS ABOVE THEN PROCEED TO THE FOLLOWING STEPS. 1) CHECK IF PT-1 SYSTEM PRESSURE TRANSMITTER DISPLAY INDICATES HIGH PRESSURE. IF IT DOES NOT, REPLACE PT-1. IF IT DOES, GO TO STEP 2. 2) CHECK IF LOCAL INDICATOR LI-4 SYSTEM PRESSURE IS READING CORRECTLY. IF NOT, REPLACE REP-4A SYSTEM PRESSURE. IF IT DOES, GO TO STEP 3. 3) CHECK IF RELAY R3-44 IS LIT AND HAS POWER. IF IT HAS POWER BUT IS NOT LIT, REPLACE RELAY. IF THERE IS NO POWER REPLACE LAM-2 HIGH PRESSURE ALARMS.
	HOA IS IN HAND	CHECK HOA POSITIONS	CHECK WITH SUPERVISOR THEN TURN TO AUTO
PRESSURE HIGH HIGH TO LIGHTS AND ALARM	VFD HMI IS IN MANUAL	CHECK VFD HMI	CHECK VFD MANUAL
	RELAY OR DEVICE FAILED	CHECK THE RELAYS/DEVICES	CHECK ITEMS ABOVE THEN PROCEED TO THE FOLLOWING STEPS. 1) CHECK IF PT-1 SYSTEM PRESSURE TRANSMITTER DISPLAY INDICATES HIGH PRESSURE. IF IT DOES NOT, REPLACE PT-1. IF IT DOES, GO TO STEP 2. 2) CHECK IF LOCAL INDICATOR LI-4 SYSTEM PRESSURE IS READING CORRECTLY. IF NOT, REPLACE REP-4A SYSTEM PRESSURE. IF IT DOES, GO TO STEP 3. 3) CHECK IF RELAY R3-44 IS LIT AND HAS POWER. IF IT HAS POWER BUT IS NOT LIT, REPLACE RELAY. IF THERE IS NO POWER REPLACE LAM-2 HIGH PRESSURE ALARMS.
	GENERATOR FAIL	CHECK GENERATOR CONTROL PANEL	REFER TO GENERATOR MANUAL
	VFD IN ALARM	CHECK VFD THAT IS IN ALARM, SEE VFD MANUAL	REFER TO VFD MANUAL
PRESSURE LOW	SYSTEM PRESSURE IS HIGH HIGH	CHECK SYSTEM PRESSURE READING	PUT ALL PUMPS IN OFF.
	MANIFOLD BUILDING OVER TEMPERATURE	CHECK IF BUILDING IS HOT	OPEN DOOR TO BUILDING, USE PORTABLE FAN TO COOL ROOM
	MANIFOLD BUILDING UNDER TEMPERATURE	CHECK IF BUILDING IS COLD	CHECK ELECTRIC AND GAS FIRED HEATERS (EH-1 AND GUH-1) ARE WORKING
	RELAY OR DEVICE FAILED	CHECK IF ANY ALARMS EXIST	REMOVE THE FOLLOWING RELAYS, ONE OF THEM HAS FAILED. IF THE ALARM STOPS WHEN THE RELAY IS REMOVED, THAT IS THE BAD RELAY: R3-24, 26, 30, 46, 54, 55



FINAL DESIGN

VERIFY SCALE
BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14

MANIFOLD BUILDING CONTROLS MCP-1 RELAY SCHEDULE, TROUBLESHOOTING


REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH
SHEET NO.	1610

PLOT DATE: 1/22/2024

LIGHT	STATUS	MEANS	HOW TO FIX	PARTS TO REPLACE
24 VDC CONTROL POWER OK	OFF	24 VDC POWER IS OFF	IF 12 VDC CONTROL POWER LIGHT IS ON, REPLACE 24 VDC POWER SUPPLY IN CPP-1 IF 12 VDC CONTROL POWER LIGHT IS OFF, CHECK BREAKER FEEDING CPP-1 AND BREAKER INSIDE CPP-1 IF 12 VDC CONTROL POWER LIGHT IS OFF, AND BREAKER FEEDING CPP-1 OK, REPLACE UPS IN CPP-1.	N/A N/A UPS-1
12 VDC CONTROL POWER OK	OFF	12 VDC POWER IS OFF	IF 24 VDC CONTROL POWER LIGHT IS ON, REPLACE 12 VDC POWER SUPPLY IN CPP-1 IF 24 VDC CONTROL POWER LIGHT IS OFF, CHECK BREAKER FEEDING CPP-1 AND BREAKER INSIDE CPP-1 IF 24 VDC CONTROL POWER LIGHT IS OFF, AND BREAKER FEEDING CPP-1 OK, REPLACE UPS IN CPP-1.	N/A N/A UPS-1
MANIFOLD BUILDING HIGH TEMPERATURE	ON	BUILDING TEMPERATURE IS TOO HIGH	IF THE BUILDING IS HOT, PROVIDE TEMPORARY COOLING FOR THE BUILDING IF THE BUILDING IS NOT HOT, TURN THE TSH-101 HIGH TEMPERATURE SWITCH DIAL TO 100 DEG F IF THIS DOES NOT RESOLVE THE PROBLEM, CHECK RELAY R4-5	N/A N/A R4-5
MANIFOLD BUILDING LOW TEMPERATURE	ON	BUILDING TEMPERATURE IS TOO LOW	IF THE BUILDING IS TOO COLD, PROVIDE TEMPORARY HEATING FOR THE BUILDING IF THE BUILDING IS NOT COLD, TURN THE TSL-101 HIGH TEMPERATURE SWITCH DIAL TO 35 DEG F IF THIS DOES NOT RESOLVE THE PROBLEM, CHECK RELAY R4-4	N/A N/A R4-4
LEAK	ON	WATER SENSOR ON FLOOR DETECTS STANDING WATER	CHECK FLOOR FOR WATER AND PIPES FOR LEAKS IF NO LEAKS ARE IDENTIFIED AND THERE IS FLUID IN THE FLOOR DRAIN, THE LEAK STOPPED. IF NO LEAKS ARE IDENTIFIED, CHECK LEAK SWITCH NEAR FLOOR TRANSMITTERS. THE SENSOR HAS A 'MOISUTRE' LED THAT LIGHTS UP RED WHEN MOISTURE IS PRESENT. DRY FLOOD SWITCH AND HIT RESET.	N/A N/A XS-101
RCP-1 COMM OK	OFF	NO COMMUNICATION TO RCP-1	CHECK IF REMOTE CONTROL PANEL HAS POWER. IF REMOTE CONTROL PANEL HAS NO POWER, REFER TO RCP-1 TROUBLESHOOTING. IF REMOTE CONTROL PANEL HAS POWER, CHECK ANTENNAS AT OFFICE BUILDING AND MANIFOLD BUILDING.	N/A
RESERVOIR HIGH LEVEL	ON	RESERVOIR IS AT HIGH LEVEL	CHECK TO CONFIRM NO PUMPS ARE ON. IF NO PUMPS ARE ON, NO ACTION (NORMAL) -IF PUMPS ARE ON, CONFIRM PRESSURE IS NOT HIGH (LESS THEN 110 PSI). IF THE PRESSURE IS LESS THEN 110 PSI, THEN THIS IS NORMAL ACTIVITY. THERE WAS A DEMAND (PRESSURE OR TANK WAS LOW) AND PUMP(S) ARE RUNNING UNTIL THE HIGH STATUS IS REACHED. -IF THERE IS LOW PRESSURE AND HIGH TANK, THE PUMPS WILL STILL BE ENABLED. IF PUMPS ARE ON AND PRESSURE IS HIGH, REFER TO PRESSURE HIGH ALARM	N/A N/A N/A
RESERVOIR LOW LEVEL / LOW LOW LEVEL	ON	RESERVOIR IS AT LOW LEVEL	CHECK TO CONFIRM AT LEAST ONE PUMPS IS ON. IF AT LEAST ONE PUMP IS ON, NO ACTION (NORMAL) IF NO PUMPS ARE ON, CHECK PRESSURE HIGH IS ON. IF PRESSURE HIGH IS ON, PUMPS SHOULD NOT BE PUMPING. NO ACTION (NORMAL) IF PUMPS ARE OFF, AND THERE IS PRESSURE HIGH STATUS, VERIFY HOA SWITCHES AT MCP-1 AND RCP-1 ARE IN AUTO, VFDS HAVE POWER, VFD ALARM LIGHTS ARE OFF. -IF THE SWITCHES ARE IN OFF, THEN THE PUMP WILL NOT RUN (NORMAL) -IF THE SWITCHES ARE IN HAND, THEN THE PUMPS SHOULD BE RUNNING (NORMAL) -IF THE VFDS DO NOT HAVE POWER, VERIFY BREAKERS TO VFDS ARE CLOSED -IF THE VFDS ALARM LIGHTS ARE ON, CHECK VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A N/A N/A N/A
PRESSURE HIGH	ON	WATER PRESSURE IS HIGH	CHECK TO CONFIRM NO PUMPS ARE ON. IF NO PUMPS ARE ON, NO ACTION (NORMAL) -IF PUMPS ARE STILL ON, ROTATE HOA SWITCH TO OFF TO DISABLE PUMP. VERIFY PUMP IS OFF. - IF VFD FOR THE PUMP IS STILL RUNNING, TURN OFF VFD AT THE VFD LCD. CHECK THE VFD LCD SCREEN IF THE VFD LCD WAS IN MANUAL MODE. - IF THE VFD IS IN MANUAL, PUT THE VFD IN AUTO MODE AND ROTATE HOA TO AUTO. - IF NOT, THE ISSUE IS WITH THE VFD. REFER TO VFD MANUAL REGARDING A VFD RUNNING IN AUTO MODE WHEN NOT ENABLED.	N/A N/A
PRESSURE LOW / PRESSURE LOW LOW	ON	RESERVOIR IS AT LOW LEVEL	CHECK TO CONFIRM AT LEAST ONE PUMP IS ON. IF AT LEAST ONE PUMP IS ON, NO ACTION (NORMAL) IF PUMPS ARE OFF, VERIFY HOA SWITCHES AT MCP-1 AND RCP-1 ARE IN AUTO, VFDS HAVE POWER, VFD ALARM LIGHTS ARE OFF. -IF THE SWITCHES ARE IN OFF, THEN THE PUMP WILL NOT RUN (NORMAL). SOMEONE PUT THE SWITCH IN OFF FOR A REASON, CHECK WITH TEAM PRIOR TO ROTATING TO AUTO. -IF THE VFDS DO NOT HAVE POWER, VERIFY DISCONNECTS TO VFDS ARE CLOSED (IN THE ON POSITION). IF THE DISCONNECT IS IN THE ON POSITION AND THERE IS NO POWER TO THE VFD, GET AN ELECTRICIAN TO REPLACE THE DISCONNECT FUSES -IF THE VFDS HAVE POWER AND ALARM LIGHTS ARE ON, CHECK VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A N/A WELL A - 300A FUSES WELL B, C - 200A FUSES
GENERATOR FAIL	ON	GENERATOR FAILED TO START UPON DEMAND	GO TO GENERATOR CONTROL PANEL, REFER TO GENERATOR TROUBLESHOOTING MANUAL	N/A
GENERATOR MINOR ALARM	ON	GENERATOR CONTROL PANEL HAS A MINOR ALARM	GO TO GENERATOR CONTROL PANEL, REFER TO GENERATOR TROUBLESHOOTING MANUAL	N/A
WELL A VFD ALARM	ON	WELL A VFD IS IN ALARM	LOOK AT VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A
WELL A SALINITY ALARM	ON	WELL A SALINITY IS TOO HIGH	LOOK AT LOCAL INDICATOR TO CONFIRM HIGH READING (GREATER THEN 800 uS/cm). IF LOCAL INDICATOR CONFIRMS ALARM, OBTAIN SAMPLE OF WELL A AND PERFORM MANUAL TESTING TO CONFIRM SALINITY IS HIGH. IF MANUAL TESTING SALINITY IS HIGH, INFORM SUPERVISOR. ALARM IS ACCURATE AND CAN NOT BE RESOLVED. DO NOT USE WELL. IF MANUAL TESTING SALINITY IS LOW, SALINITY AT THE DATA RECORDER. IF READING IS LOW, REPLACE INDICATOR. IF MANUAL TESTING SALINITY IS LOW, AND DATA RECORDER READS MATCHES THE INDICATOR, REPLACE REPEATER. IF MANUAL TESTING SALINITY IS LOW, AND REPLACING THE REPEATER DOES NOT WORK, REPLACE SALINITY SENSOR.	N/A N/A N/A LI-5 REP-5
WELL B VFD ALARM	ON	WELL B VFD IS IN ALARM	LOOK AT VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A
WELL B SALINITY ALARM	ON	WELL B SALINITY IS TOO HIGH	LOOK AT LOCAL INDICATOR TO CONFIRM HIGH READING (GREATER THEN 800 uS/cm). IF LOCAL INDICATOR CONFIRMS ALARM, OBTAIN SAMPLE OF WELL B AND PERFORM MANUAL TESTING TO CONFIRM SALINITY IS HIGH. IF MANUAL TESTING SALINITY IS HIGH, INFORM SUPERVISOR. ALARM IS ACCURATE AND CAN NOT BE RESOLVED. DO NOT USE WELL. IF MANUAL TESTING SALINITY IS LOW, SALINITY AT THE DATA RECORDER. IF READING IS LOW, REPLACE INDICATOR. IF MANUAL TESTING SALINITY IS LOW, AND DATA RECORDER READS MATCHES THE INDICATOR, REPLACE REPEATER. IF MANUAL TESTING SALINITY IS LOW, AND REPLACING THE REPEATER DOES NOT WORK, REPLACE SALINITY SENSOR.	N/A N/A N/A LI-6 REP-6
WELL C VFD ALARM	ON	WELL C VFD IS IN ALARM	LOOK AT VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A
WELL C SALINITY ALARM	ON	WELL C SALINITY IS TOO HIGH	LOOK AT LOCAL INDICATOR TO CONFIRM HIGH READING (GREATER THEN 800 uS/cm). IF LOCAL INDICATOR CONFIRMS ALARM, OBTAIN SAMPLE OF WELL C AND PERFORM MANUAL TESTING TO CONFIRM SALINITY IS HIGH. IF MANUAL TESTING SALINITY IS HIGH, INFORM SUPERVISOR. ALARM IS ACCURATE AND CAN NOT BE RESOLVED. DO NOT USE WELL. IF MANUAL TESTING SALINITY IS LOW, SALINITY AT THE DATA RECORDER. IF READING IS LOW, REPLACE INDICATOR. IF MANUAL TESTING SALINITY IS LOW, AND DATA RECORDER READS MATCHES THE INDICATOR, REPLACE REPEATER. IF MANUAL TESTING SALINITY IS LOW, AND REPLACING THE REPEATER DOES NOT WORK, REPLACE SALINITY SENSOR.	N/A N/A N/A LI-7 REP-7
ALARM BEACON	ON	ONE OF THE FOLLOWING ALARMS HAS OCCURRED: WELL A VFD ALARM, WELL B VFD ALARM, WELL C VFD ALARM,	REFER TO SPECIFIC ALARM	N/A
ALARM CLAXON	ON	GENERATOR FAIL, PRESSURE HIGH		N/A

LIGHT	CONDITION	MEANS
24 VDC CONTROL POWER OK	ON	24 VDC POWER IS OK
12 VDC CONTROL POWER OK	ON	24 VDC POWER IS OK
RCP-1 COMM OK	ON	COMMUNICATION LINK TO REMOTE CONTROL PANEL OK
MANIFOLD BUILDING HIGH TEMPERATURE	OFF	MANIFOLD BUILDING TEMPERATURE BELOW 100 DEG F
MANIFOLD BUILDING LOW TEMPERATURE	OFF	MANIFOLD BUILDING TEMPERATURE ABOVE 35 DEG F
WATER LEAK	OFF	NO SIGNIFICANT AMOUNT OF WATER ON THE FLOOR
RESERVOIR HIGH LEVEL	OFF	RESERVOIR IS NOT IN HIGH LEVEL
RESERVOIR LOW LEVEL	OFF	RESERVOIR IS NOT IN LOW LEVEL
RESERVOIR LOW LOW LEVEL	OFF	RESERVOIR IS NOT IN LOW LEVEL
PRESSURE HIGH	OFF	PRESSURE IS NOT HIGH
PRESSURE LOW	OFF	PRESSURE IS NOT LOW
PRESSURE LOW LOW	OFF	PRESSURE IS NOT LOW LOW
GENERATOR FAIL	OFF	GENERATOR DID NOT FAIL
GENERATOR RUNNING	OFF	GENERATOR IS NOT RUNNING
GENERATOR MINOR ALARM	ON	GENERATOR IS RUNNING
GENERATOR MINOR ALARM	OFF	GENERATOR DOES NOT HAVE AN ALARM
WELL A OVERTEMP ALARM	OFF	PUMP A IS NOT OVERHEATING
WELL A VFD ALARM	OFF	VFD A DOES NOT HAVE AN ALARM
WELL A SALINITY ALARM	OFF	WELL A SALINITY IS OK
WELL A VFD RUNNING	OFF	VFD A IS NOT RUNNING
WELL A VFD RUNNING	ON	VFD A IS RUNNING
WELL A VFD READY	OFF	VFD A IS EITHER RUNNING OR HAS AN ALARM
WELL A VFD READY	ON	VFD A IS READY TO RUN
WELL B OVERTEMP ALARM	OFF	PUMP B IS NOT OVERHEATING
WELL B VFD ALARM	OFF	VFD B DOES NOT HAVE AN ALARM
WELL B SALINITY ALARM	OFF	WELL B SALINITY IS OK
WELL B VFD RUNNING	OFF	VFD B IS NOT RUNNING
WELL B VFD RUNNING	ON	VFD B IS RUNNING
WELL B VFD READY	OFF	VFD B IS EITHER RUNNING OR HAS AN ALARM
WELL B VFD READY	ON	VFD B IS READY TO RUN
WELL C OVERTEMP ALARM	OFF	PUMP C IS NOT OVERHEATING
WELL C VFD ALARM	OFF	VFD C DOES NOT HAVE AN ALARM
WELL C SALINITY ALARM	OFF	WELL C SALINITY IS OK
WELL C VFD RUNNING	OFF	VFD C IS NOT RUNNING
WELL C VFD RUNNING	ON	VFD C IS RUNNING
WELL C VFD READY	OFF	VFD C IS EITHER RUNNING OR HAS AN ALARM
WELL C VFD READY	ON	VFD C IS READY TO RUN
RCP-1 WELL A IN OFF	OFF	RCP-1 HOA WELL A IS NOT IN OFF POSITION
RCP-1 WELL A IN OFF	ON	RCP-1 HOA WELL A IS IN OFF POSITION
RCP-1 WELL A IN AUTO	OFF	RCP-1 HOA WELL A IS NOT IN AUTO POSITION
RCP-1 WELL A IN AUTO	ON	RCP-1 HOA WELL A IS IN AUTO POSITION
RCP-1 WELL A IN HAND	OFF	RCP-1 HOA WELL A IS NOT IN HAND POSITION
RCP-1 WELL A IN HAND	ON	RCP-1 HOA WELL A IS IN HAND POSITION
RCP-1 WELL B IN OFF	OFF	RCP-1 HOA WELL B IS NOT IN OFF POSITION
RCP-1 WELL B IN OFF	ON	RCP-1 HOA WELL B IS IN OFF POSITION
RCP-1 WELL B IN AUTO	OFF	RCP-1 HOA WELL B IS NOT IN AUTO POSITION
RCP-1 WELL B IN AUTO	ON	RCP-1 HOA WELL B IS IN AUTO POSITION
RCP-1 WELL B IN HAND	OFF	RCP-1 HOA WELL B IS NOT IN HAND POSITION
RCP-1 WELL B IN HAND	ON	RCP-1 HOA WELL B IS IN HAND POSITION
WELL A RUNNING BEACON	OFF	VFD A IS NOT RUNNING
WELL A RUNNING BEACON	ON	VFD A IS RUNNING
WELL B RUNNING BEACON	OFF	VFD B IS NOT RUNNING
WELL B RUNNING BEACON	ON	VFD B IS RUNNING
WELL C RUNNING BEACON	OFF	VFD C IS NOT RUNNING
WELL C RUNNING BEACON	ON	VFD C IS RUNNING
ALARM BEACON	OFF	MCP-1 IS NOT IN ALARM
ALARM CLAXON	OFF	MCP-1 IS NOT IN ALARM



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0' = 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

MANIFOLD BUILDING CONTROLS
TROUBLESHOOTING CONTINUED



REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN ILH
DESIGNED ILH
REVIEWED ILH


SHEET NO.

1611



PLOT DATE: 1/7/2022

WIRING LEGEND
 ——— WIRING INTERNAL TO PANEL
 - - - - WIRING EXTERNAL TO PANEL
 - - - - EXTERNAL DEVICE ENCLOSURE



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY


WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14
OFFICE BUILDING CONTROLS
CPP-2 WIRING AND RCP-1 HOA

REVISION SCHEDULE


#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN ILH
 DESIGNED ILH
 REVIEWED ILH

SHEET NO.
1612



PLOT DATE: 1/7/2022



FINAL DESIGN

VERIFY SCALE
 BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
 WHITTIER, ALASKA
 PROJECT No. 20403.14



OFFICE BUILDING CONTROLS
 RCP-1 LIGHTS

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
 DATE DEC 2021
 DRAWN ILH
 DESIGNED ILH
 REVIEWED ILH

SHEET NO. **1613**



WIRING LEGEND
 ——— WIRING INTERNAL TO PANEL
 - - - - WIRING EXTERNAL TO PANEL
 - - - - EXTERNAL DEVICE ENCLOSURE



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
 0" ——— 1"
 IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
 PROJECT No. 20403.14

**OFFICE BUILDING CONTROLS RCP-1
 DIGITAL RADIO CONNECTION**

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH

SHEET NO.

1614

A


B

C

D


WIRING LEGEND

- WIRING INTERNAL TO PANEL
- - - WIRING EXTERNAL TO PANEL
- - - EXTERNAL DEVICE ENCLOSURE



NOTES

- ① USE ONE SET OF 16 PAIR CABLE FROM EXISTING THREE PAIRS



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

OFFICE BUILDING CONTROLS RCP-1
ANALOG RADIO CONNECTION

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH

SHEET NO.

1615

A

B

C

D


1

2

3

PLOT DATE: 1/7/2022

RCP-1 RELAYS				
RELAY	PURPOSE	CONTACTS	PURPOSE	NOTES
R3-101	RCP-1 VFD A HAND	A	TO RADIO D11	
		B		
R3-102	RCP-1 VFD A OFF	A	TO RADIO D12	
		B		
R3-103	RCP-1 VFD A AUTO	A	TO RADIO D13	
		B		
R3-104	RCP-1 VFD B HAND	A	TO RADIO D14	
		B		
R3-105	RCP-1 VFD B OFF	A	TO RADIO D15	
		B		
R3-106	RCP-1 VFD B AUTO	A	TO RADIO D16	
		B		
R3-107	RCP-1 VFD B HAND	A	TO RADIO D17	
		B		
R3-108	RCP-1 VFD B OFF	A	TO RADIO D18	
		B		
R3-109	RCP-1 VFD B AUTO	A	TO RADIO D19	
		B		
R3-110	VFD A ALARM	A	LIGHT	
		B		
R3-111	VFD B ALARM	A	LIGHT	
		B		
R3-112	VFD C ALARM	A	LIGHT	
		B		
R3-113	VFD A RUNNING	A	LIGHT	
		B		
R3-114	VFD B RUNNING	A	LIGHT	
		B		
R3-115	VFD C RUNNING	A	LIGHT	
		B		
R3-116	VFD A READY	A	LIGHT	
		B		
R3-117	VFD B READY	A	LIGHT	
		B		
R3-118	VFD C READY	A	LIGHT	
		B		
R3-119	MCP-1 TO RCP-1 LINK OK	A	LIGHT	
		B		
R3-120	TANK HIGH	A	LIGHT	
		B		
R3-121	TANK LOW	A	LIGHT	
		B		
R3-122	TANK LOW LOW	A	LIGHT	
		B		
R3-123	TSH-101 HIGH TEMP SWITCH	A	LIGHT	
		B		
R3-124	TSL-101 LOW TEMP SWITCH	A	LIGHT	
		B		
R3-125	XS-101 LEAK ALARM	A	LIGHT	
		B		



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING

0" 1"

IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE

WHITTIER, ALASKA
PROJECT No. 20403.14

OFFICE BUILDING CONTROLS
RCP-1 RELAY SCHEDULE

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN ILH
DESIGNED ILH
REVIEWED ILH

SHEET NO.

1616

LIGHT	STATUS	MEANS	HOW TO FIX	PARTS TO REPLACE
24 VDC CONTROL POWER OK	OFF	24 VDC POWER IS OFF	IF 12 VDC CONTROL POWER LIGHT IS ON, REPLACE 24 VDC POWER SUPPLY IN CPP-2 IF 12 VDC CONTROL POWER LIGHT IS OFF, CHECK BREAKER FEEDING CPP-1 AND BREAKER INSIDE CPP-2 IF 12 VDC CONTROL POWER LIGHT IS OFF, AND BREAKER FEEDING CPP-120K, REPLACE UPS IN CPP-2.	N/A N/A UPS-2
12 VDC CONTROL POWER OK	OFF	12 VDC POWER IS OFF	IF 24 VDC CONTROL POWER LIGHT IS ON, REPLACE 12 VDC POWER SUPPLY IN CPP-2 IF 24 VDC CONTROL POWER LIGHT IS OFF, CHECK BREAKER FEEDING CPP-1 AND BREAKER INSIDE CPP-2 IF 24 VDC CONTROL POWER LIGHT IS OFF, AND BREAKER FEEDING CPP-2 OK, REPLACE UPS IN CPP-2.	N/A N/A UPS-2
MANIFOLD BUILDING HIGH TEMPERATURE	ON	BUILDING TEMPERATURE IS TOO HIGH	IF THE BUILDING IS HOT, PROVIDE TEMPORARY COOLING FOR THE BUILDING IF THE BUILDING IS NOT HOT, TURN THE TSH-101 HIGH TEMPERATURE SWITCH DIAL TO 100 DEG F IF THIS DOES NOT RESOLVE THE PROBLEM, CHECK RELAY R4-5 IN MCP-1 AND R3-123 IN RCP-1	N/A N/A R4-5, R3-123
MANIFOLD BUILDING LOW TEMPERATURE	ON	BUILDING TEMPERATURE IS TOO LOW	IF THE BUILDING IS TOO COLD, PROVIDE TEMPORARY HEATING FOR THE BUILDING IF THE BUILDING IS NOT COLD, TURN THE TSL-101 HIGH TEMPERATURE SWITCH DIAL TO 35 DEG F IF THIS DOES NOT RESOLVE THE PROBLEM, CHECK RELAY R4-4 IN MCP-1 AND R3-124 IN RCP-1	N/A N/A R4-4, R3-124
WATER LEAK	ON	WATER SENSOR ON FLOOR DETECTS STANDING WATER	CHECK FLOOR FOR WATER AND PIPES FOR LEAKS IF NO LEAKS ARE IDENTIFIED AND THERE IS FLUID IN THE FLOOR DRAIN, THE LEAK STOPPED. IF NO LEAKS ARE IDENTIFIED, CHECK LEAK SWITCH NEAR FLOOR TRANSMITTERS. THE SENSOR HAS A 'MOISUTRE' LED THAT LIGHTS UP RED WHEN MOISTURE IS PRESENT. DRY FLOOD SWITCH AND HIT RESET.	N/A N/A XS-101
MCP-1 COMM OK	OFF	NO COMMUNICATION TO MCP-1	CHECK IF MAIN CONTROL PANEL HAS POWER AND IS FUNCTIONING. IF MAIN CONTROL PANEL HAS NO POWER OR IS MALFUNCTIONING, REFER TO MCP-1 TROUBLESHOOTING. IF MAIN CONTROL PANEL HAS POWER AND IS FUNCTIONAL, CHECK ANTENNAS AT OFFICE BUILDING AND MANIFOLD BUILDING.	N/A
RESERVOIR HIGH LEVEL	ON	RESERVOIR IS AT HIGH LEVEL	CHECK TO CONFIRM NO PUMPS ARE ON. IF NO PUMPS ARE ON, NO ACTION (NORMAL) -IF PUMPS ARE ON, CONFIRM PRESSURE IS NOT HIGH (LESS THEN 110 PSI). IF THE PRESSURE IS LESS THEN 110 PSI, THEN THIS IS NORMAL ACTIVITY. THERE WAS A DEMAND (PRESSURE OR TANK WAS LOW AND PUMPS) ARE RUNNING UNTIL THE HIGH STATUS IS REACHED. -IF THERE IS LOW PRESSURE AND HIGH TANK, THE PUMPS WILL STILL BE ENABLED. IF PUMPS ARE ON AND PRESSURE IS HIGH, REFER TO PRESSURE HIGH ALARM	N/A N/A N/A
RESERVOIR LOW LEVEL / LOW LOW LEVEL	ON	RESERVOIR IS AT LOW LEVEL	CHECK TO CONFIRM AT LEAST ONE PUMPS IS ON. IF AT LEAST ONE PUMP IS ON, NO ACTION (NORMAL) IF NO PUMPS ARE ON, CHECK PRESSURE HIGH IS ON. IF PRESSURE HIGH IS ON, PUMPS SHOULD NOT BE PUMPING. NO ACTION (NORMAL) IF PUMPS ARE OFF, AND THERE IS PRESSURE HIGH STATUS, VERIFY HOA SWITCHES AT MCP-1 AND RCP-1 ARE IN AUTO, VFDS HAVE POWER, VFD ALARM LIGHTS ARE OFF. -IF THE SWITCHES ARE IN OFF, THEN THE PUMP WILL NOT RUN (NORMAL) -IF THE SWITCHES ARE IN HAND, THEN THE PUMPS SHOULD BE RUNNING (NORMAL) -IF THE VFDS DO NOT HAVE POWER, VERIFY BREAKERS TO VFDS ARE CLOSED -IF THE VFDS ALARM LIGHTS ARE ON, CHECK VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A N/A N/A N/A
PRESSURE HIGH	ON	WATER PRESSURE IS HIGH	CHECK TO CONFIRM NO PUMPS ARE ON. IF NO PUMPS ARE ON, NO ACTION (NORMAL) -IF PUMPS ARE STILL ON, ROTATE HOA SWITCH TO OFF TO DISABLE PUMP. VERIFY PUMP IS OFF. - IF VFD FOR THE PUMP IS STILL RUNNING, TURN OFF VFD AT THE VFD LCD. CHECK THE VFD LCD SCREEN IF THE VFD LCD WAS IN MANUAL MODE. - IF THE VFD IS IN MANUAL, PUT THE VFD IN AUTO MODE AND ROTATE HOA TO AUTO. - IF NOT, THE ISSUE IS WITH THE VFD. REFER TO VFD MANUAL REGARDING A VFD RUNNING IN AUTO MODE WHEN NOT ENABLED.	N/A N/A
PRESSURE LOW / PRESSURE LOW LOW	ON	RESERVOIR IS AT LOW LEVEL	CHECK TO CONFIRM AT LEAST ONE PUMP IS ON. IF AT LEAST ONE PUMP IS ON, NO ACTION (NORMAL) IF PUMPS ARE OFF, VERIFY HOA SWITCHES AT MCP-1 AND RCP-1 ARE IN AUTO, VFDS HAVE POWER, VFD ALARM LIGHTS ARE OFF. -IF THE SWITCHES ARE IN OFF, THEN THE PUMP WILL NOT RUN (NORMAL) SOMEONE PUT THE SWITCH IN OFF FOR A REASON, CHECK WITH TEAM PRIOR TO ROTATING TO AUTO. -IF THE VFDS DO NOT HAVE POWER, VERIFY DISCONNECTS TO VFDS ARE CLOSED (IN THE ON POSITION). IF THE DISCONNECT IS IN THE ON POSITION AND THERE IS NO POWER TO THE VFD, GET AN ELECTRICIAN TO REPLACE THE DISCONNECT FUSES -IF THE VFDS HAVE POWER AND ALARM LIGHTS ARE ON, CHECK VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A N/A N/A WELL A - 300A FUSES WELL B, C - 200A FUSES
WELL A VFD ALARM	ON	WELL A VFD IS IN ALARM	LOOK AT VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A
WELL B VFD ALARM	ON	WELL B VFD IS IN ALARM	LOOK AT VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A
WELL C VFD ALARM	ON	WELL C VFD IS IN ALARM	LOOK AT VFD LCD SCREEN FOR ALARM CODE AND REFER TO VFD MANUAL	N/A
ALARM BEACON	ON	ONE OF THE FOLLOWING ALARMS HAS OCCURRED: WELL A VFD ALARM, WELL B VFD ALARM, WELL C VFD ALARM, GENERATOR FAIL, PRESSURE HIGH	REFER TO SPECIFIC ALARM	N/A
ALARM CLAXON	ON			N/A

LIGHT	CONDITION	MEANS
24 VDC CONTROL POWER OK	ON	24 VDC POWER IS OK
12 VDC CONTROL POWER OK	ON	24 VDC POWER IS OK
MCP-1 COMM OK	ON	COMMUNICATION LINK TO MAIN CONTROL PANEL OK
MANIFOLD BUILDING HIGH TEMPERATURE	OFF	MANIFOLD BUILDING TEMPERATURE BELOW 100 DEG F
MANIFOLD BUILDING LOW TEMPERATURE	OFF	MANIFOLD BUILDING TEMPERATURE ABOVE 35 DEG F
WATER LEAK	OFF	NO SIGNIFICANT AMOUNT OF WATER ON THE FLOOR
RESERVOIR HIGH LEVEL	OFF	RESERVOIR IS NOT IN HIGH LEVEL
RESERVOIR LOW LEVEL	OFF	RESERVOIR IS NOT IN LOW LEVEL
RESERVOIR LOW LOW LEVEL	OFF	RESERVOIR IS NOT IN LOW LEVEL
WELL A VFD ALARM	OFF	VFD A DOES NOT HAVE AN ALARM
WELL A VFD RUNNING	ON	VFD A IS RUNNING
WELL A VFD READY	OFF	VFD A IS EITHER RUNNING OR HAS AN ALARM
WELL B VFD ALARM	OFF	VFD B DOES NOT HAVE AN ALARM
WELL B VFD RUNNING	ON	VFD B IS RUNNING
WELL B VFD READY	OFF	VFD B IS EITHER RUNNING OR HAS AN ALARM
WELL C VFD ALARM	OFF	VFD C DOES NOT HAVE AN ALARM
WELL C VFD RUNNING	ON	VFD C IS RUNNING
WELL C VFD READY	OFF	VFD C IS EITHER RUNNING OR HAS AN ALARM
WELL A RUNNING BEACON	ON	VFD A IS READY TO RUN
WELL B RUNNING BEACON	ON	VFD A IS NOT RUNNING
WELL C RUNNING BEACON	ON	VFD A IS RUNNING
ALARM BEACON	OFF	VFD B IS NOT RUNNING
ALARM CLAXON	OFF	VFD B IS RUNNING
	OFF	VFD C IS NOT RUNNING
	OFF	VFD C IS RUNNING
	OFF	MCP-1 IS NOT IN ALARM
	OFF	MCP-1 IS NOT IN ALARM



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
OFFICE BUILDING CONTROLS TROUBLESHOOTING LOGIC

REVISION SCHEDULE		
#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO.	20403.14
DATE	DEC 2021
DRAWN	ILH
DESIGNED	ILH
REVIEWED	ILH

SHEET NO.

1617

A		B			C		D
INSTRUMENT INDEX							
TAG	DESCRIPTION	MAKE	MODEL	OR APPROVAL EQUAL?	QTY	COMMENTS	
LT-#	WELL LEVEL SENSOR, 2 WIRE	ENDRESS + HAUSER	FMX21-AA211MDE25H+F1LRPOPUPW	YES	3	PROVIDE THE FOLLOWING ACCESSORIES: SUSPENSION CLAMP, CABLE MOUNTING SCREWS, ADDITIONAL WEIGHT, CABLE SHORTENING KIT. SENSOR TO BE APPROVED FOR DRINKING WATER AND BE NRTL LISTED PRIOR TO ORDERING CONTRACTOR TO CONFIRM SENSOR CABLE LENGTH AND ORDER SENSOR WITH APPROPRIATE LENGTH AS REQUIRED.	
PT-#	SYSTEM PRESSURE SENSOR AND TRANSMITTER, 2 WIRE	ENDRESS + HAUSER	PMP51-AA12D2P0FACJA1+F1HALRMHPA	YES	1		
AE-#	SALINITY SENSOR ELEMENT, 2 WIRE	PHIONICS	ST SERIES, 0-1000 uS/CM	NO	3	VERIFY LENGTH REQUIRED PRIOR TO ORDERING	
AL1-#	LIGHT BEACON, AMBER, STEADY	EDWARDS SIGNALLING	125LEDSA24D WITH 125GRD	YES	3	MOUNT ON EXTERIOR POLE	
AL2-#	LIGHT BEACON, RED, FLASHING	EDWARDS SIGNALLING	125LEDFR24D WITH 125GRD	YES	1	MOUNT ON EXTERIOR POLE	
LT2-#	RESERVOIR LEVEL SENSOR, 2 WIRE	ENDRESS + HAUSER	FMX21-AA211HDE11H+F1LRPOPUPW	YES	1	PROVIDE THE FOLLOWING ACCESSORIES: SUSPENSION CLAMP, CABLE MOUNTING SCREWS, ADDITIONAL WEIGHT, CABLE SHORTENING KIT. SENSOR TO BE APPROVED FOR DRINKING WATER AND BE NRTL LISTED PRIOR TO ORDERING CONTRACTOR TO CONFIRM SENSOR CABLE LENGTH AND ORDER SENSOR WITH APPROPRIATE LENGTH AS REQUIRED.	
HRN-#	ALARM CLAXON	EDWARDS SIGNALLING	868-AQ WITH 869-WPB BACK BOX	YES	1	MOUNT ON EXTERIOR POLE	
FIT-10#	WELL A FLOW METER - 6" MAG METER WITH TRANSMITTER	ABB	FEV121.150.V.1.S.1.A1.B.1.A.1.A.2.A.3.B.4.A.1-1-M5.VO.CWC.T3	YES	3	<1% ERROR OVER 700 GPM TO 850 GPM RANGE, FIT-103 FOR FUTURE USE	
TS#-#	TEMPERATURE SWITCH	COLUMBUS ELECTRIC	ETD9STGS	YES	2	TSL CLOSES ON LOW TEMP, TSH CLOSES AT HIGH TEMP. COORDINATE WITH PANEL WIRING.	
VFD-#	VFD FOR WELL PUMP	ALLEN BRADLEY	CSB-24G163D156LNDCCNNNN-P51-HD-A-PO-A-A-N-B-D-A-A-N-B-D-N-B1-ENG	NO	3	VFD-C FOR FUTURE USE	
XS-#	LEAK DETECTION SWITCH	DIVERSITECH	WS-1	YES	1		

Panel	TAG	DESCRIPTION	MAKE	MODEL	OR APPROVAL EQUAL?	Qty	COMMENTS
MCP-1	N/A	15 AMP SINGLE POLE BREAKER - UL 489	ALLEN BRADLEY	1489-M1C150	YES	9	RATED TO 10 KAIC
	N/A	PANEL ENCLOSURES - VARIOUS SIZES	HOFFMAN	VARIOUS SIZES - NEMA 12	YES	1	CONTRACTOR TO SIZE AS REQUIRED
	WIO-#	WIRELESS I/O SYSTEM - MAIN MODULE	SYNETCOM	DIN-S-9	NO	1	
		WIRELESS I/O SYSTEM - MULTI MODULE	SYNETCOM	DIN-IO-1	NO	2	
		WIRELESS I/O SYSTEM - DI MODULE	SYNETCOM	DIN-IO-4	NO	1	CONTRACTOR TO COORDINATE WITH VENDOR TO DETERMINE APPROPRIATE LENGTH AND INSTALLATION OF COAXIAL CABLE AND ANTENNA.
		WIRELESS I/O SYSTEM - DO MODULE	SYNETCOM	DIN-IO-5	NO	1	ALL ACCESSORIES FOR THE WIRELESS I/O SYSTEM MUST BE BOUGHT FROM SYNETCOM TO ENSURE A COMPLETE SYSTEM.
		WIRELESS I/O SYSTEM - AI MODULE	SYNETCOM	DIN-IO-2	NO	1	
		WIRELESS I/O SYSTEM - AO MODULE	SYNETCOM	DIN-IO-3	NO	1	
		WIRELESS I/O SYSTEM - ACCESSORIES	SYNETCOM	DIRECTIONAL ANTENNA, COAX CABLE, CONNECTIONS	NO	1	
	R3-#	THREE POLE DOUBLE THROW RELAY 24 VDC COIL	OMRON	MKS3PIN-D 24VDC	YES	55	WITH MECHANICAL INDICATOR, LOCKABLE TEST BUTTON, LED INDICATOR, DIODE, BASE
	R4-#	FOUR POLE DOUBLE THROW RELAY 24 VDC COIL	PHOENIX CONTACT	REL-IR4/LDP- 24DC/4X21	YES	3	WITH MECHANICAL INDICATOR, LOCKABLE TEST BUTTON, LED INDICATOR, DIODE, BASE
	TD#-#	TIME DELAY DOUBLE POLE DOUBLE THROW RELAY 12/24 VDC COIL	DAYTON	5DR3	YES	4	PROVIDE WITH BASE
	REP-#	QUAD OUTPUT 4-20MA SPLITTER/RETRANSMITTER	LAUREL ELECTRONICS	QLS-2	NO	11	
	LAM-#	LIMIT ALARM MODULE, AI INPUT FOUR RELAY OUTPUT	AUTOMATION DIRECT	FC-3RLY4	NO	2	
	LI-#	LOCAL INDICATOR WITH DUAL SINKING OUTPUT CARD	REDLION	CUB5PB00 WITH CUB5SNKO	NO	11	
DR-#	DATA RECORDER	ENDRESS + HAUSER	MEMOGRAPH M, RSG45	NO	1	WITH TELEALARM SOFTWARE, AND CAPACITY FOR AT LEAST TWENTY 4-20 MA INPUTS, TEN DIGITAL INPUTS, AND SIX DRY CONTACT OUTPUTS. CONTRACTOR TO CONFIGURE GRAPHING AND DATA LOGGING FOR DATA POINTS AS SHOWN ON SHEET 1102, DETAIL 3, AND FOUR ADDITIONAL DATA POINTS. CONTRACTOR TO CONFIGURE TELEALARM SOFTWARE FOR TEN UNIQUE ALARM SCENARIOS	
AR-#	TRIPLEX ALTERNATING RELAY	MACROMATIC	ATP024A7R WITH SD12-PC SOCKET	NO	1		
PB1-#	MOMENTARY PUSHBUTTON, NO, LOCKABLE COVER	ALLEN BRADLEY	800TC-A6 WITH 800H-N163	YES	1	MOUNT KEY WITH CHAIN ON PANEL. PROVIDE SPARE KEY, LABELED, INSIDE PANEL ENCLOSURE	
SW3-#	THREE POSITION HOA SWITCH	ALLEN BRADLEY	800HC-JR2KC1B	YES	3	OFF POSITION IS WIRED TO A RELAY IN THE PANEL	
SW2-#	TWO POSITION SWITCH, DOUBLE THROW, LOCKABLE COVER	ALLEN BRADLEY	800TC-H2B WITH 800H-N163	YES	1	MOUNT KEY WITH CHAIN ON PANEL. PROVIDE SPARE KEY, LABELED, INSIDE PANEL ENCLOSURE	
SW2A-#	TWO POSITION SWITCH, SINGLE THROW	ALLEN BRADLEY	800TC-H2A	YES	1	MOUNT ON PANEL BACKPLANE	
N/A	CONTROL PANEL INDICATOR LIGHT, LED, AMBER, 24VDC, PUSH TO TEST	SCHNEIDER	XB4W25B5	YES	12		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 12VDC,	ALLEN BRADLEY	800T-QH2W	YES	1		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, GREEN, 24VDC, PUSH TO TEST	SCHNEIDER	XB4W23B5	YES	6		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 24VDC, PUSH TO TEST	SCHNEIDER	XB4W21B5	YES	1		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 24VAC/DC	SCHNEIDER	XB4FV81	YES	1		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 120VAC	SCHNEIDER	XB4FV81	YES	0		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, RED, 24VDC, PUSH TO TEST	SCHNEIDER	XB4W24B5	YES	16		


TAG	MAKE	MODEL	CONTRACTOR PROVIDED SPARES
PS12-#	SOLA/HEVI-DUTY	SDN 16-12-100P	1
PS24-#	SOLA/HEVI-DUTY	SDN-10-24-100P	1
SA-#	DEHNGUARD	IP120R	1
N/A	ALLEN BRADLEY	1489-M1C150	1
R3-#	OMRON	MKS3PIN-D 24VDC	2
R4-#	PHOENIX CONTACT	REL-IR4/LDP- 24DC/4X21	1
TDRO-#	DAYTON	5DR3	1
REP-#	LAUREL ELECTRONICS	QLS-2	1
LAM-#	AUTOMATION DIRECT	FC-3RLY4	1
LI-#	REDLION	CUB5PB00 WITH CUB5SNKO	1
AR-#	MACROMATIC	ATP024A7R WITH SD12-PC SOCKET	1
PB1-#	ALLEN BRADLEY	800TC-A6 WITH 800H-N163	1
SW3-#	ALLEN BRADLEY	800HC-JR2KC1B	1
SW2-#	ALLEN BRADLEY	800TC-H2B WITH 800H-N163	1
SW2A-#	ALLEN BRADLEY	800TC-H2A	1
N/A	SCHNEIDER	XB4W25B5	1
N/A	ALLEN BRADLEY	800T-QH2W	1
N/A	SCHNEIDER	XB4W23B5	1
N/A	SCHNEIDER	XB4FV81	1
N/A	SCHNEIDER	XB4FV81	1
N/A	SCHNEIDER	XB4W24B5	1
TS#-#	COLUMBUS ELECTRIC	ETD9STGS	1
XS-#	DIVERSITECH	WS-1	1

Panel	TAG	DESCRIPTION	MAKE	MODEL	OR APPROVAL EQUAL?	Qty	COMMENTS
RCP-1	N/A	15 AMP SINGLE POLE BREAKER - UL 489	ALLEN BRADLEY	1489-M1C150	YES	3	RATED TO 10 KAIC
	N/A	PANEL ENCLOSURES - VARIOUS SIZES	HOFFMAN	VARIOUS SIZES - NEMA 12	YES	1	CONTRACTOR TO SIZE AS REQUIRED
	WIO-#	WIRELESS I/O SYSTEM - MAIN MODULE	SYNETCOM	DIN-S-9	NO	1	
		WIRELESS I/O SYSTEM - MULTI MODULE	SYNETCOM	DIN-IO-1	NO	2	
		WIRELESS I/O SYSTEM - DI MODULE	SYNETCOM	DIN-IO-4	NO	1	CONTRACTOR TO COORDINATE WITH VENDOR TO DETERMINE APPROPRIATE LENGTH AND INSTALLATION OF COAXIAL CABLE AND ANTENNA.
		WIRELESS I/O SYSTEM - DO MODULE	SYNETCOM	DIN-IO-5	NO	1	ALL ACCESSORIES FOR THE WIRELESS I/O SYSTEM MUST BE BOUGHT FROM SYNETCOM TO ENSURE A COMPLETE SYSTEM.
		WIRELESS I/O SYSTEM - AI MODULE	SYNETCOM	DIN-IO-2	NO	1	
		WIRELESS I/O SYSTEM - AO MODULE	SYNETCOM	DIN-IO-3	NO	1	
		WIRELESS I/O SYSTEM - ACCESSORIES	SYNETCOM	DIRECTIONAL ANTENNA, COAX CABLE, CONNECTIONS	NO	1	
	R3-#	THREE POLE DOUBLE THROW RELAY 24 VDC COIL	OMRON	MKS3PIN-D 24VDC	YES	25	WITH MECHANICAL INDICATOR, LOCKABLE TEST BUTTON, LED INDICATOR, DIODE, BASE
	REP-#	QUAD OUTPUT 4-20MA SPLITTER/RETRANSMITTER	LAUREL ELECTRONICS	QLS-2	NO	1	
	LAM-#	LIMIT ALARM MODULE, AI INPUT FOUR RELAY OUTPUT	AUTOMATION DIRECT	FC-3RLY4	NO	1	
	LI-#	LOCAL INDICATOR WITH DUAL SINKING OUTPUT CARD	REDLION	CUB5PB00 WITH CUB5SNKO	NO	8	
	SW3-#	THREE POSITION HOA SWITCH	ALLEN BRADLEY	800HC-JR2KC1B	YES	3	OFF POSITION IS WIRED TO A RELAY IN THE PANEL
	N/A	CONTROL PANEL INDICATOR LIGHT, LED, AMBER, 24VDC, PUSH TO TEST	SCHNEIDER	XB4W25B5	YES	5	
N/A	CONTROL PANEL INDICATOR LIGHT, LED, GREEN, 24VDC, PUSH TO TEST	SCHNEIDER	XB4W23B5	YES	3		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 24VDC, PUSH TO TEST	SCHNEIDER	XB4W21B5	YES	1		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 24VAC/DC	SCHNEIDER	XB4FV81	YES	2		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, RED, 24VDC, PUSH TO TEST	SCHNEIDER	XB4W24B5	YES	8		

Panel	TAG	DESCRIPTION	MAKE	MODEL	OR APPROVAL EQUAL?	QTY	COMMENTS
CPP-1	UPS-#	850VA/510W UPS WITH BATTERIES	SOLA/HEVI-DUTY	SDU 850	YES	1	PROVIDE WITH BATTERIES
	PS12-#	12 VDC POWER SUPPLY	SOLA/HEVI-DUTY	SDN 16-12-100P	YES	1	
	PS24-#	24 VDC POWER SUPPLY	SOLA/HEVI-DUTY	SDN 10-24-100P	YES	1	
	SA-#	SURGE ARRESTOR	DEHNGUARD	IP120R	YES	1	
	N/A	15 AMP SINGLE POLE BREAKER - UL 489	ALLEN BRADLEY	1489-M1C150	YES	6	RATED TO 10 KAIC
	N/A	PANEL ENCLOSURES - VARIOUS SIZES	HOFFMAN	VARIOUS SIZES - NEMA 12	YES	1	CONTRACTOR TO SIZE AS REQUIRED
	N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 12VDC,	ALLEN BRADLEY	800T-QH2W	YES	1	
	N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 24VAC/DC	SCHNEIDER	XB4FV81	YES	2	
	N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 120VAC	SCHNEIDER	XB4FV81	YES	1	
	TR-#	96 VA CLASS 2 TRANSFORMER, 120VAC TO 24 VAC	DAYTON	4VZF8	YES	1	

Panel	TAG	DESCRIPTION	MAKE	MODEL	OR APPROVAL EQUAL?	QTY	COMMENTS
CPP-2	UPS-#	850VA/510W UPS WITH BATTERIES	SOLA/HEVI-DUTY	SDU 850	YES	1	PROVIDE WITH BATTERIES
	PS12-#	12 VDC POWER SUPPLY	SOLA/HEVI-DUTY	SDN 16-12-100P	YES	1	
	PS24-#	24 VDC POWER SUPPLY	SOLA/HEVI-DUTY	SDN 10-24-100P	YES	1	
	SA-#	SURGE ARRESTOR	DEHNGUARD	IP120R	YES	1	
	N/A	15 AMP SINGLE POLE BREAKER - UL 489	ALLEN BRADLEY	1489-M1C150	YES	5	RATED TO 10 KAIC
	N/A	PANEL ENCLOSURES - VARIOUS SIZES	HOFFMAN	VARIOUS SIZES - NEMA 12	YES	1	CONTRACTOR TO SIZE AS REQUIRED
	N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 12VDC,	ALLEN BRADLEY	800T-QH2W	YES	1	
N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 24VAC/DC	SCHNEIDER	XB4FV81	YES	1		
N/A	CONTROL PANEL INDICATOR LIGHT, LED, WHITE, 120VAC	SCHNEIDER	XB4FV81	YES	1		

INSTRUMENT INDEX, CONTROL PANEL COMPONENTS, AND CONTRACTOR PROVIDED SPARES



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" = 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
INSTRUMENT INDEX AND OVERALL PANEL BOM

REVISION SCHEDULE

#	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN ILH
DESIGNED ILH
REVIEWED ILH

SHEET NO.

1618


PLOT DATE: 1/7/2022



1 EXHIBIT PHOTO OF RESERVOIR TOPSIDE




2 EXHIBIT PHOTO OF LOOKING INTO RESERVOIR




3 RESERVOIR BUILDING FLOOR PLAN

NTS



4 TRANSDUCER CONNECTION

NTS



FINAL DESIGN

VERIFY SCALE

BAR REPRESENTS 1" ON ORIGINAL DRAWING
0" 1"
IF BAR IS NOT 1", ADJUST DRAWING SCALE ACCORDINGLY

WHITTIER WELL FIELD UPGRADE
WHITTIER, ALASKA
PROJECT No. 20403.14
WATER RESERVOIR INSTRUMENT DETAILS

REVISION SCHEDULE

NO.	DESCRIPTION	DATE
0	IFC	12/21

PROJECT NO. 20403.14
DATE DEC 2021
DRAWN ILH
DESIGNED ILH
REVIEWED ILH

SHEET NO.

1619

1

2

3

PLOT DATE: 1/7/2022